

April 18, 2024

Stephanie and Joseph Hasler 125 N Locust Street Reedsburg, WI 53959

SUBJECT: 3<sup>rd</sup> Round Vapor Sampling Results - <u>Contaminant Detection Below DNR Screening Level</u> PROPERTY: Reedsburg Cleaners, 125 N. Locust Street (PSI B); BRRTS # 02-57-001682

Dear Stephanie and Joseph Hasler,

Included are the findings of our 3<sup>rd</sup> round investigation on your property conducted by Bay West, LLC (Bay West) an environmental consultant hired by the Wisconsin Department of Natural Resources (WDNR).

### **Background:**

As you are aware, this investigation was conducted because of the potential for contaminant vapors from the nearby Reedsburg Cleaners property identified above to migrate through soil, accumulate beneath the foundation of your home, and possibly enter your indoor air. The contaminant of concern at the Reedsburg Cleaners property is tetrachloroethylene (PCE) and trichloroethylene (TCE). The history of this site and the potential concerns to neighboring residents were described in detail in the original letter sent to your home.

### Sampling:

On March 14, 2024, Bay West deployed passive air sampling devices at each floor of your residence and installed one passive vapor sampler below the concrete floor of your basement for the collection of indoor air, sub-slab soil, and outdoor vapor samples. On March 28, 2024, the sample devices were retrieved then submitted to Beacon Environmental, where it underwent laboratory analysis for five contaminants, including PCE, TCE, cis-1,2-dichloroethene (DCE), trans-1,2-dichloroethene (DCE) and vinyl chloride (VC).

### **Your Test Results:**

Attached are copies of the laboratory report for your passive vapor sub-slab and indoor air samples. The results of this  $3^{\rm rd}$  round of sampling shows that a small amount of PCE was detected in one of the samples taken from beneath your basement floor. The sub-slab sample analysis detected PCE beneath your basement floor at 4.51 micrograms per cubic meter ( $\mu g/m^3$ ) which is below the applicable DNR screening level of 1,400  $\mu g/m^3$  beneath basement concrete floors. In addition, the indoor air samples detected PCE at 0.628  $\mu g/m^3$  and 1.04  $\mu g/m^3$  which are also below the applicable DNR screening level of 42  $\mu g/m^3$  in indoor air vapors.

Although PCE was detected in soil vapors at your home, the level at which it was detected is such that it does not pose a threat to you or your family. This is called "a detection below screening level" and is explained in the enclosed fact sheet.

In conclusion, sampling the air indoors and beneath your home on three different occasions revealed no detections of the chemicals of concern. As a result, no further air sampling is planned at your home. Thank you for your cooperation with sampling. Please contact us if you have any questions now or in the future.



We appreciate the opportunity to assist you with this vapor investigation effort. Please feel free to contact us if you have any questions about these results.

Sincerely,

Tarek Aboueid
Environmental Scientist
651.724.9757
taboueid@baywest.com

Jason Kunze
Senior Project M

Senior Project Manager

651.291.3438

Jkunze@baywest.com

Copy: Rob Hoverman, PG, WDNR, 414.497.0896, Robert.Hoverman@wisconsin.gov

Jeff Ackerman, WDNR PM, 608.275.3323, jeff.ackerman@wisconsin.gov

Jeramiah Yee, Wisconsin Dept of Health Services, 608-266-1865, dhsdphoperations@dhs.wisconsin.gov

Attachments:

### **TABLE**

Table – Tabulated vapor analytical results with the sample dates, sample type (sub-slab or indoor air), and location.

### **FIGURES**

Figure 1 – Property Location Map

Figure 2 and 2A – Building Map showing sampling locations.

### **APPENDIX**

Appendix A – Access Agreement

Appendix B – Laboratory Analytical Results with Chain of Custody (3<sup>rd</sup> Round)

Appendix C – Vapor Sampling Field Checklist from (3<sup>rd</sup> Round)

Appendix D – Understanding Chemical Vapor Testing Results (DNR PUB-RR-977)



#### Table 1B

#### **Indoor Air Sub-Slab Analytical Results**

**Bay West** 

157001460 – Reedsburg Cleaners 125 N. Locust Street, Reedsburg, WI Property Sample Identifier (PSI) - B

	Location								1	125 N Locust Street (PSI I	3)					
	Sample ID	Indoor Air VAL	Sub-Slab Vapor	08B_SSV_02_20230801	08B_SSV_02_20231219	08B_SSV_02_20240328	08B_IAB_04_20230801	08B_IAB_04_20231219	08B_IAB_04_20240328	08B_IA1_05_20230801	08B_IA1_05_20231219	08B_IA1_05_20240328	08B_IA2_06_20230801	08B_IA2_06_20231219	08B_IA2_06_20240328	08B_OA_02_20240328
Date	es Sampled	Residential	VRSL Residential	7/18 to 8/1/2023	12/5 to 12/19/2023	3/14 to 3/28	7/18 to 8/1/2023	12/5 to 12/19/2023	3/14 to 3/28	7/18 to 8/1/2023	12/5 to 12/19/2023	3/14 to 3/28	7/18 to 8/1/2023	12/5 to 12/19/2023	3/14 to 3/28	3/14 to 3/28
Applicable A	Action Level				VRSL			VAL			VAL			VAL		VAL
Volatile Organic Compound	ds (method	EPA TO-17)														
cis-1,2-Dichloroethene	156-59-2	42	1400	< 0.940	< 0.937	< 0.936	< 0.933	< 0.929	<0.465	< 0.933	< 0.929	<0.465	< 0.934	< 0.929	<0.465	<0.481
Tetrachloroethene (PCE)	127-18-4	42	1400	5.17	3.14	4.51	< 1.21	< 1.20	<0.601	< 1.21	< 1.20	0.628 J	< 1.21	2.44	1.04 J	<0.622
trans-1,2-Dichloroethene	156-60-5	42	1400	< 1.13	< 1.13	<1.13	< 1.12	< 1.12	<0.560	< 1.12	< 1.12	<0.560	< 1.12	< 1.12	<0.560	<0.579
Trichloroethene (TCE)	79-01-6	2.1	70	< 1.51	< 1.50	<1.50	< 1.50	< 1.49	<0.746	< 1.50	< 1.49	<0.746	< 1.50	< 1.49	<0.747	<0.772
Vinyl chlorido	75 01 4	1.7	EE	< 0.61E	< 0.612	∠0 £12	< 0.610	< 0.508	<0.204	< 0.611	< 0.508	<0.204	< 0.611	< 0.600	<0.204	<0.21E

#### Notes:

All results are in micrograms per cubic meter (µg/m³)

USEPA VISL – United States Environmental Protection Agency Vapor Intrusion Screening Leve

WIDNR - Wisconsin Department of Natural Resources

VAL – WIDNR Vapor Action Level, calculated using USEPA VISLs published November 2023

VRSL – WIDNR Vapor Risk Screening Level, calculated using USEPA VISLs published November 2023

— - No USEPA VISL established

< - Less than the laboratory Reporting Limit (RL)


Bold - Analyte detected

Grey – Result exceeds the Residential VAL

Orange – Result exceeds the Residential VRSL



# **FIGURES**



# Figure 1


# Site Location Map

Reedsburg Cleaners WDNR ERP Case #: 02-57-001682 WDNR PS Act. ID: VIZC\_REEDSBURG

Reedsburg, WI 53959



Map Projection: NAD 1983 UTM Zone 15 N, Meters Basemap: ESRI USA Topo Maps WMS




1:24,000





Drawn By: N.J. Date Drawn/Revised:8/28/2023 Project No.J230382




# Figure 2 **Site Map**

**Reedsburg Cleaners** WDNR ERP Case #: 02-57-001682 WDNR PS Act. ID: VIZC\_REEDSBURG

Reedsburg, WI 53959



Map Projection: NAD 1983 UTM Zone 15N, Meters Basemap: WI DNR Aerial Imagery WMS, 10/14/2022




- Manhole
- Sanitary Sewers
- 120 N Locust St (PSI A)
- 125 N Locust St (PSI B)
- 335 E Main St (PSI C)
- ROW (PSIR)
- 349 E Main St (Source)
  - Parcel Boundaries



Drawn By: N.J.

Date Drawn/Revised:8/28/2023 Project No.J230382




# Figure 2B **Site Map**

**Reedsburg Cleaners** WDNR ERP Case #: 02-57-001682 WDNR PS Act. ID: VIZC\_REEDSBURG

> 125 N Locust Street Reedsburg, WI 53959



Map Projection: NAD 1983 UTM Zone 15N, Meters Basemap: WI DNR Aerial Imagery WMS, 10/14/2022



- 125 N Locust St (PSI B)
- 335 E Main St (PSI C)
- ROW (PSIR)
- 349 E Main St (Source)
  - Parcel Boundaries

### **Features**



Passive Vapor Sample Location

All results are in micrograms per cubic meter (μg/m<sup>3</sup>) < - Less than the laboratory Reporting Limit (RL)

### Bold - Analyte detected

Grey - Result exceeds the Residential VAL Orange - Result exceeds the Residential VRSL




Date Drawn/Revised:8/28/2023 Project No.J230382



# APPENDIX A

# Wisconsin Department of Natural Resources ACCESS PERMISSION AGREEMENT



Tenant(s) email address

(DNR) and its employees, duly authorized representatives, agents and contractors, to enter upon and have access at reasonable times to the home/business located at

(ADDRESS) 125 N LOCUST ST Reeds burg. W1 53959

(Print as Listed on Title / County GIS)

The property is located in the SE 1/4 of the NW 1/4 of Sec 10, T12N, R04E, Sauk County, Wisconsin. The access permission is for the following purposes: The DNR may perform an investigation of the home/business for vapor migration from trichloroethylene (TCE) and tetrachloroethylene (PCE) located in groundwater, associated with the Reedsburg Cleaners Site, BRRTS #02-57-001682 located near your property. This permission allows the DNR or its authorized representative to:

- Install and maintain sub-slab vapor probe(s) into the foundation of the home or business. (1)
- (2)Collect at least three (3) separate vapor samples from the sub-slab probe(s) at different times of the year.
- Collect indoor air samples on each level of the home or business and within the sealed sump headspace, (3)if applicable.
- Collect water sample(s) from the sump, if applicable. (4)
- Abandon the vapor probe(s) when no longer needed. (5)

The permission that is granted shall remain in effect for one year from the signature date when the vapor investigation work is expected to be complete. If an extension is necessary to complete the work, DNR will inform you in writing.

The property owner agrees not to damage or interfere with the use of any sub-slab probe installed as permitted herein.

IN WITNESS WHEREOF:	
Signature of Property Owner Representative	2 May 2023 Signature Date
STEPHANIEN, HASLER Print Name, Title	Matame France Charter. net Email address
Mailing Address of Owner	Area Code and Telephone Number
TENANT(S) / LESSEE(S) by UNIT NUMBER, ETC.	
Name of Tenant(s)/Lessee(s)	Mail or email correspondence regarding this site to:
Tenant(s) phone number	Department of Natural Resources

ATTN: Rob Hoverman 1027 West St. Paul Avenue Milwaukee, WI 53233-2641

Robert.Hoverman@wisconsin.gov

Phone: 414.497.0896



# APPENDIX B



### Beacon Environmental

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

### CERTIFICATE OF ANALYSIS

Beacon Proposal No.: 230427H02 Laboratory Work Order: 0007650

### **Project Description:**

Reedsburg Cleaners

Prepared for:

Jason Kunze

**Bay West LLC** 

5 Empire Drive

St. Paul, MN 55103

Ryan W. Schneider Senior Project Manager

April 09, 2024

All data meet requirements as specified in the Beacon Environmental Quality Assurance Project Plan and the results relate only to the samples reported. The work performed was in accordance with ISO/IEC 17025:2017. This report shall not be reproduced, except in full, without written approval of the laboratory. Release of the data contained in this data package has been authorized by the Laboratory Director or his signee, as verified by the following signatures:

Steven C. Thornley Laboratory Director

teven Thornley

Peter B. Kelly Quality Manager

# **Table of Contents**

Cover Page	1
Sample Summary	3
Case Narrative	4
Analytical Results	5
Summary of Compound Detections	6
Data Summary Table	7
Detailed Analytical Results	8
0007650-01 - 08B_IAB_04_20240328	9
0007650-02 - 08B_IA1_05_20240328	10
0007650-03 - 08B_IA2_06_20240328	11
0007650-04 - 08B_OA_02_20240328	12
QC Summaries	13
Additional QC Information	30
Sample Result Calculations	31
Equation	32
LOD/MRL Calculation Table	33
Certifications	34
Notes and Definitions	35
Sample Management Records	36
Chain of Custody	37



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# Sample Summary

Lab Sample ID	Client Sample ID	Received	Analysis	Matrix
0007650-01 Sampler Type:	08B_IAB_04_20240328 Beacon Passive Sampler	03/29/2024	TO-17 (Passive)	Indoor Air
0007650-02 Sampler Type:	08B_IA1_05_20240328 Beacon Passive Sampler	03/29/2024	TO-17 (Passive)	Indoor Air
0007650-03 Sampler Type:	08B_IA2_06_20240328 Beacon Passive Sampler	03/29/2024	TO-17 (Passive)	Indoor Air
0007650-04 Sampler Type:	08B_OA_02_20240328 Beacon Passive Sampler	03/29/2024	TO-17 (Passive)	Ambient Air

### **Project Completeness**

Samples Received: 4
Samples Analyzed: 4



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

### Case Narrative

Beacon Environmental provided thermally conditioned Beacon Samplers for sampling, with analyses following U.S. EPA Method TO-17, with analytical results reported in μg/m3. Beacon calculated concentration results using the exposure period, target analyte mass, and the following procedures detailed in ISO 16017-2, *Indoor, ambient and workplace air-Sampling and analysis of volatile organic compounds by sorbent tube/thermal desorption/capillary gas chromatography-Part 2: Diffusive sampling*.

Beacon reports results and reporting limits to three significant digits.

### Reporting Limits (RLs) for EPA Method TO-17

The RLs represent a baseline above which results meet laboratory-determined limits of precision and accuracy. Beacon performed dilution analysis when results exceeded the upper calibration limit, bringing all reported results within the calibration range. The project method quantitation limit (MQL) is the limit of detection (LOD) as noted in the data tables.

#### **Calibration Verification**

All continuing calibration verification (CCV) values are within  $\pm 30\%$  of the true values as defined by the initial calibration and met the requirements specified in BEACON's Quality Manual.

### **Internal Standards and Surrogates**

Internal standards and surrogates are spiked on all blanks (ICB, BLK), field samples and laboratory control samples (ICV/CALV, BS, ICV and CCV). Acceptance criteria for internal standards are 60 to 140 percent and surrogate recoveries are 70 to 130 percent; all internal standards and surrogates are within the acceptance criteria unless noted in the Case Narrative.

### **Blank Contamination**

No targeted compounds above the limit of detection (LOD) for each compound were observed in the Laboratory Method Blanks unless noted in the Case Narrative.

### **Laboratory Control Samples**

Acceptance criteria for surrogate and analytes recoveries are 70 to 130 percent; all recoveries are within the acceptance criteria unless noted in the Case Narrative.

### Discussion

Samples were received in proper condition and laboratory control parameters were met unless otherwise noted below. The work performed was in accordance with ISO/IEC 17025:2017.



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Analytical Results

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# Summary of Compound Detections- Concentration

Lab Sample ID:	0007650-02	<b>08B_IA1</b>	05_20240 loor Air	328			Method	: TO-17 (Passive)
Analyte		CAS#	Result (µg/m³)	Q	RT	LOQ (µg/m³)	LOD (µg/m³)	File ID
Tetrachloroeth	ene	127-18-4	0.628	J	8.074	1.20	0.601	Kb24040222.D

Lab Sample ID:	0007650-03	08B_	IA2_06_20240 Indoor Air	)328			Method	d: TO-17 (Passive)
Analyte		CAS#	Result (µg/m³)	Q	RT	LOQ (μg/m³)	LOD (µg/m³)	File ID
Tetrachloroeth	ene	127-18-4	1.04	J	8.071	1.20	0.601	Ka24040307.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# Data Summary Table- Concentration

Compound	Frequency	LOD (μg/m³)	Max Value (μg/m³)
Tetrachloroethene	2	0.601	1.04



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# **Detailed Analytical Results**



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name: Reedsburg CleanersBeacon Proposal: 230427H025 Empire DriveSite Location: WisconsinLab Work Order: 0007650St. Paul, MN 55103Project Manager: Jason KunzeReported: 04/09/2024

Lab Sample ID: 0007650-01 08B\_IAB\_04\_20240328 Method: TO-17 (Passive)

Indoor Air

Analyte	CAS#	Result (μg/m³)		$\frac{\text{LOD}}{(\mu g/m^3)}$	LOQ (μg/m³)	Analyzed	File ID
Vinyl Chloride	75-01-4	< 0.304	U	0.304	0.608	04/03/2024 07:29	Kb24040229.D
trans-1,2-Dichloroethene	156-60-5	< 0.560	U	0.560	1.12	04/03/2024 07:29	Kb24040229.D
cis-1,2-Dichloroethene	156-59-2	< 0.465	U	0.465	0.929	04/03/2024 07:29	Kb24040229.D
Trichloroethene	79-01-6	< 0.746	U	0.746	1.49	04/03/2024 07:29	Kb24040229.D
Tetrachloroethene	127-18-4	< 0.601	U	0.601	1.20	04/03/2024 07:29	Kb24040229.D
Analyte	CAS#	% Recovery	Recov	ery Limits	Q	Analyzed	File ID
Surrogate: 1,2-DCA-d4	17060-07-0	99.2%	70	0-130		04/03/2024 07:29	Kb24040229.D
Surrogate: Toluene-d8	2037-26-5	97.6%	70	0-130		04/03/2024 07:29	Kb24040229.D
Surrogate: Bromofluorobenzene	460-00-4	88.6%	70	0-130		04/03/2024 07:29	Kb24040229.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Lab Sample ID: 0007650-02 **08B\_IA1\_05\_20240328** Method: TO-17 (Passive)

Indoor Air

		Result		LOD	LOO		
Analyte	CAS#	(μg/m³)		$(\mu g/m^3)$	$(\mu g/m^3)$	Analyzed	File ID
Vinyl Chloride	75-01-4	< 0.304	U	0.304	0.608	04/03/2024 01:51	Kb24040222.D
trans-1,2-Dichloroethene	156-60-5	< 0.560	U	0.560	1.12	04/03/2024 01:51	Kb24040222.D
cis-1,2-Dichloroethene	156-59-2	< 0.465	U	0.465	0.930	04/03/2024 01:51	Kb24040222.D
Trichloroethene	79-01-6	< 0.746	U	0.746	1.49	04/03/2024 01:51	Kb24040222.D
Tetrachloroethene	127-18-4	0.628	J	0.601	1.20	04/03/2024 01:51	Kb24040222.D
Analyte	CAS#	% Recovery	Recov	ery Limits	Q	Analyzed	File ID
Surrogate: 1,2-DCA-d4	17060-07-0	96.4%	70	0-130		04/03/2024 01:51	Kb24040222.D
Surrogate: Toluene-d8	2037-26-5	91.9%	70	0-130		04/03/2024 01:51	Kb24040222.D
Surrogate: Bromofluorobenzene	460-00-4	86.3%	70	0-130		04/03/2024 01:51	Kb24040222.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

 Lab Sample ID:
 0007650-03
 08B\_IA2\_06\_20240328
 Method:
 TO-17 (Passive)

 Indoor Air
 TO-17 (Passive)
 TO-17

Analyte	CAS#	Result (μg/m³)		$\begin{array}{c} \textbf{LOD} \\ (\mu g/m^3) \end{array}$	$\begin{array}{c} \textbf{LOQ} \\ (\mu g/m^3) \end{array}$	Analyzed	File ID
Vinyl Chloride	75-01-4	<0.304	U	0.304	0.608	04/03/2024 12:04	Ka24040307.D
trans-1,2-Dichloroethene	156-60-5	< 0.560	U	0.560	1.12	04/03/2024 12:04	Ka24040307.D
cis-1,2-Dichloroethene	156-59-2	< 0.465	U	0.465	0.930	04/03/2024 12:04	Ka24040307.D
Trichloroethene	79-01-6	< 0.747	U	0.747	1.49	04/03/2024 12:04	Ka24040307.D
Tetrachloroethene	127-18-4	1.04	J	0.601	1.20	04/03/2024 12:04	Ka24040307.D
Analyte	CAS#	% Recovery	Recov	ery Limits	Q	Analyzed	File ID
Surrogate: 1,2-DCA-d4	17060-07-0	98.8%	70	0-130		04/03/2024 12:04	Ka24040307.D
Surrogate: Toluene-d8	2037-26-5	87.1%	70	0-130		04/03/2024 12:04	Ka24040307.D
Surrogate: Bromofluorobenzene	460-00-4	93.3%	70	0-130		04/03/2024 12:04	Ka24040307.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Lab Sample ID: 0007650-04 **08B\_OA\_02\_20240328** Method: TO-17 (Passive)

Ambient Air

Analyte	CAS#	Result (μg/m³)		$\frac{\text{LOD}}{(\mu g/m^3)}$	LOQ (μg/m³)	Analyzed	File ID
Vinyl Chloride	75-01-4	< 0.315	U	0.315	0.629	04/03/2024 02:48	Kb24040224.D
trans-1,2-Dichloroethene	156-60-5	< 0.579	U	0.579	1.16	04/03/2024 02:48	Kb24040224.D
cis-1,2-Dichloroethene	156-59-2	< 0.481	U	0.481	0.962	04/03/2024 02:48	Kb24040224.D
Trichloroethene	79-01-6	< 0.772	U	0.772	1.54	04/03/2024 02:48	Kb24040224.D
Tetrachloroethene	127-18-4	< 0.622	U	0.622	1.24	04/03/2024 02:48	Kb24040224.D
Analyte	CAS#	% Recovery	Recov	ery Limits	Q	Analyzed	File ID
Surrogate: 1,2-DCA-d4	17060-07-0	90.8%	70	0-130		04/03/2024 02:48	Kb24040224.D
Surrogate: Toluene-d8	2037-26-5	90.9%	70	0-130		04/03/2024 02:48	Kb24040224.D
Surrogate: Bromofluorobenzene	460-00-4	89.4%	70	0-130		04/03/2024 02:48	Kb24040224.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

QC Information/Summary



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24A120 - Instrument: K System - File ID: Kb24013016.D

B24A120-ICV1 (LCSD/Second Source Verification/CALV)

					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	53.7	10	5	ng	50.0		107	70-130			
trans-1,2-Dichloroethene	52.6	10	5	ng	50.0		105	70-130			
cis-1,2-Dichloroethene	50.6	10	5	ng	50.0		101	70-130			
Trichloroethene	49.6	10	5	ng	50.0		99.2	70-130			
Tetrachloroethene	46.3	10	5	ng	50.0		92.5	70-130			
Surrogate: 1,2-DCA-d4	51.5			ng	50.0		103	70-130			
Surrogate: Toluene-d8	50.1			ng	50.0		100	70-130			
Surrogate: Bromofluorobenzene	45.9			ng	50.0		91.9	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24A120 - Instrument: K System - File ID: Kb24013020.D

### B24A120-ICB1 (Lab Blank/Initial Calibration Blank)

•											
					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	<5	10	5	ng							U
trans-1,2-Dichloroethene	<5	10	5	ng							U
cis-1,2-Dichloroethene	<5	10	5	ng							U
Trichloroethene	<5	10	5	ng							U
Tetrachloroethene	<5	10	5	ng							U
Surrogate: 1,2-DCA-d4	104			ng	100		104	70-130			
Surrogate: Toluene-d8	101			ng	100		101	70-130			
Surrogate: Bromofluorobenzene	91.4			ng	100		91.4	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

### Sequence: B24D010 - Batch: 24D0009 - Instrument: K System - File ID: Ka24040302.D

### 24D0009-BS1 (LCS, Calibration Source Verification)

Analyte	Result	LOQ	LOD	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	41.2	10	5	ng	50.0		82.3	70-130			
trans-1,2-Dichloroethene	46.3	10	5	ng	50.0		92.5	70-130			
cis-1,2-Dichloroethene	48.3	10	5	ng	50.0		96.7	70-130			
Trichloroethene	49.5	10	5	ng	50.0		99.0	70-130			
Tetrachloroethene	41.8	10	5	ng	50.0		83.5	70-130			
Surrogate: 1,2-DCA-d4	49.5			ng	50.0		99.1	70-130			
Surrogate: Toluene-d8	45.0			ng	50.0		90.0	70-130			
Surrogate: Bromofluorobenzene	37.7			ng	50.0		75.4	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

### Sequence: B24D010 - Batch: 24D0009 - Instrument: K System - File ID: Ka24040303.D

### 24D0009-BLK1 (Lab Blank)

Analyte	Result	LOQ	LOD	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
•	<0.304	0.608	0.304		Level	resurt	701120	Lilino	на Б	Emme	U
Vinyl Chloride				μg/m³							
trans-1,2-Dichloroethene	<0.559	1.12	0.559	μg/m³							U
cis-1,2-Dichloroethene	< 0.464	0.929	0.464	μg/m³							U
Trichloroethene	< 0.746	1.49	0.746	$\mu g/m^3$							U
Tetrachloroethene	< 0.600	1.20	0.600	μg/m³							U
Surrogate: 1,2-DCA-d4	99.9			ng	100		99.9	70-130			
Surrogate: Toluene-d8	99.2			ng	100		99.2	70-130			
Surrogate: Bromofluorobenzene	83.5			ng	100		83.5	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D010 - Instrument: K System - File ID: Ka24040304.D

B24D010-ICV1 (LCSD/Second Source Verification/CALV)

					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	46.5	10	5	ng	50.0		93.1	70-130			
trans-1,2-Dichloroethene	47.9	10	5	ng	50.0		95.7	70-130			
cis-1,2-Dichloroethene	49.7	10	5	ng	50.0		99.5	70-130			
Trichloroethene	51.9	10	5	ng	50.0		104	70-130			
Tetrachloroethene	47.4	10	5	ng	50.0		94.7	70-130			
Surrogate: 1,2-DCA-d4	49.1			ng	50.0		98.1	70-130			
Surrogate: Toluene-d8	48.8			ng	50.0		97.5	70-130			
Surrogate: Bromofluorobenzene	40.4			ng	50.0		80.8	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D010 - Instrument: K System - File ID: Ka24040312.D

B24D010-CCV1 (LCS, Closing Calibration Verification)

					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	39.7	10	5	ng	50.0		79.4	70-130			
trans-1,2-Dichloroethene	47.3	10	5	ng	50.0		94.5	70-130			
cis-1,2-Dichloroethene	48.4	10	5	ng	50.0		96.9	70-130			
Trichloroethene	48.7	10	5	ng	50.0		97.4	70-130			
Tetrachloroethene	45.9	10	5	ng	50.0		91.8	70-130			
Surrogate: 1,2-DCA-d4	51.1			ng	50.0		102	70-130			
Surrogate: Toluene-d8	51.1			ng	50.0		102	70-130			
Surrogate: Bromofluorobenzene	42.4			ng	50.0		84.8	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D010 - Instrument: K System - File ID: Ka24040313.D

### B24D010-CCB1 (Lab Blank)

					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	<5	10	5	ng							U
trans-1,2-Dichloroethene	<5	10	5	ng							U
cis-1,2-Dichloroethene	<5	10	5	ng							U
Trichloroethene	<5	10	5	ng							U
Tetrachloroethene	<5	10	5	ng							U
Surrogate: 1,2-DCA-d4	102			ng	100		102	70-130			
Surrogate: Toluene-d8	101			ng	100		101	70-130			
Surrogate: Bromofluorobenzene	84.6			ng	100		84.6	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D009 - Batch: 24D0008 - Instrument: K System - File ID: Kb24040202.D

### 24D0008-BS1 (LCS, Calibration Source Verification)

Analyte	Result	LOQ	LOD	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	40.5	10	5	ng	50.0		81.0	70-130			
trans-1,2-Dichloroethene	45.5	10	5	ng	50.0		91.0	70-130			
cis-1,2-Dichloroethene	47.3	10	5	ng	50.0		94.5	70-130			
Trichloroethene	48.0	10	5	ng	50.0		96.1	70-130			
Tetrachloroethene	42.3	10	5	ng	50.0		84.6	70-130			
Surrogate: 1,2-DCA-d4	49.0			ng	50.0		97.9	70-130			
Surrogate: Toluene-d8	43.4			ng	50.0		86.8	70-130			
Surrogate: Bromofluorobenzene	37.1			ng	50.0		74.2	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

### Sequence: B24D009 - Batch: 24D0008 - Instrument: K System - File ID: Kb24040203.D

### 24D0008-BLK1 (Lab Blank)

					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	< 0.304	0.608	0.304	$\mu g/m^3$							U
trans-1,2-Dichloroethene	< 0.559	1.12	0.559	$\mu g/m^3$							U
cis-1,2-Dichloroethene	< 0.464	0.929	0.464	$\mu g/m^3$							U
Trichloroethene	< 0.746	1.49	0.746	$\mu g/m^3$							U
Tetrachloroethene	< 0.600	1.20	0.600	$\mu g/m^3$							U
Surrogate: 1,2-DCA-d4	99.6			ng	100		99.6	70-130			
Surrogate: Toluene-d8	100			ng	100		100	70-130			
Surrogate: Bromofluorobenzene	82.3			ng	100		82.3	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D009 - Instrument: K System - File ID: Kb24040204.D

B24D009-ICV1 (LCSD/Second Source Verification/CALV)

					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	51.5	10	5	ng	50.0		103	70-130			
trans-1,2-Dichloroethene	48.2	10	5	ng	50.0		96.4	70-130			
cis-1,2-Dichloroethene	49.3	10	5	ng	50.0		98.5	70-130			
Trichloroethene	50.1	10	5	ng	50.0		100	70-130			
Tetrachloroethene	48.5	10	5	ng	50.0		97.0	70-130			
Surrogate: 1,2-DCA-d4	49.9			ng	50.0		99.9	70-130			
Surrogate: Toluene-d8	48.3			ng	50.0		96.7	70-130			
Surrogate: Bromofluorobenzene	40.5			ng	50.0		81.1	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D009 - Instrument: K System - File ID: Kb24040215.D

B24D009-CCV1 (LCS, Closing Calibration Verification)

Analyte	Result	LOQ	LOD	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	41.4	10	5	ng	50.0		82.9	70-130			
trans-1,2-Dichloroethene	47.0	10	5	ng	50.0		94.1	70-130			
cis-1,2-Dichloroethene	47.7	10	5	ng	50.0		95.4	70-130			
Trichloroethene	48.9	10	5	ng	50.0		97.9	70-130			
Tetrachloroethene	46.4	10	5	ng	50.0		92.9	70-130			
Surrogate: 1,2-DCA-d4	49.8			ng	50.0		99.6	70-130			
Surrogate: Toluene-d8	48.6			ng	50.0		97.2	70-130			
Surrogate: Bromofluorobenzene	42.1			ng	50.0		84.3	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D009 - Instrument: K System - File ID: Kb24040216.D

### B24D009-CCB1 (Lab Blank)

					Spike	Source		%REC		RPD	
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	<5	10	5	ng							U
trans-1,2-Dichloroethene	<5	10	5	ng							U
cis-1,2-Dichloroethene	<5	10	5	ng							U
Trichloroethene	<5	10	5	ng							U
Tetrachloroethene	<5	10	5	ng							U
Surrogate: 1,2-DCA-d4	102			ng	100		102	70-130			
Surrogate: Toluene-d8	98.7			ng	100		98.7	70-130			
Surrogate: Bromofluorobenzene	80.7			ng	100		80.7	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D009 - Instrument: K System - File ID: Kb24040230.D

B24D009-CCV2 (Continuing Calibration Verification)

Analyte	Result	LOQ	LOD	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	41.3	10	5	ng	50.0		82.6	70-130			
trans-1,2-Dichloroethene	47.7	10	5	ng	50.0		95.4	70-130			
cis-1,2-Dichloroethene	48.9	10	5	ng	50.0		97.8	70-130			
Trichloroethene	49.2	10	5	ng	50.0		98.5	70-130			
Tetrachloroethene	45.8	10	5	ng	50.0		91.6	70-130			
Surrogate: 1,2-DCA-d4	50.5			ng	50.0		101	70-130			
Surrogate: Toluene-d8	50.2			ng	50.0		100	70-130			
Surrogate: Bromofluorobenzene	42.2			ng	50.0		84.4	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D009 - Instrument: K System - File ID: Kb24040231.D

#### B24D009-CCB2 (Lab Blank)

	D. J.	1.00	LOD	** **	Spike	Source	A/DEG	%REC	DDD	RPD	37.
Analyte	Result	LOQ	LOD	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	<5	10	5	ng							U
trans-1,2-Dichloroethene	<5	10	5	ng							U
cis-1,2-Dichloroethene	<5	10	5	ng							U
Trichloroethene	<5	10	5	ng							U
Tetrachloroethene	<5	10	5	ng							U
Surrogate: 1,2-DCA-d4	99.2			ng	100		99.2	70-130			
Surrogate: Toluene-d8	102			ng	100		102	70-130			
Surrogate: Bromofluorobenzene	85.3			ng	100		85.3	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## TO-17 (Passive) - LCS/LCSD RPD Quality Control Summary

 LCS:
 24D0009-BS1
 File ID: Ka24040302.D
 Analyzed:
 4/3/24
 10:30

 LCSD:
 B24D010-ICV1
 File ID: Ka24040304.D
 Analyzed:
 4/3/24
 9:26

		LCS Result	%REC		Spike Level	LCSD Result	%REC	%REC	RPD	RPD	
Analyte	CAS#	(ng)		Q	(ng)	(ng)		Limits		Limit	Q
Vinyl Chloride	75-01-4	41.15	82.3		50	46.54	93.10	70-130	12.29	30	
trans-1,2-Dichloroethene	156-60-5	46.27	92.54		50	47.85	95.70	70-130	3.36	30	
cis-1,2-Dichloroethene	156-59-2	48.33	96.66		50	49.73	99.50	70-130	2.86	30	
Trichloroethene	79-01-6	49.52	99.04		50	51.86	104.00	70-130	4.62	30	
Tetrachloroethene	127-18-4	41.77	83.54		50	47.36	94.70	70-130	12.54	30	



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## TO-17 (Passive) - LCS/LCSD RPD Quality Control Summary

 LCS:
 24D0008-BS1
 File ID: Kb24040202.D
 Analyzed:
 4/2/24
 17:57

 LCSD:
 B24D009-ICV1
 File ID: Kb24040204.D
 Analyzed:
 4/2/24
 17:08

		LCS Result	%REC		Spike Level	LCSD Result	%REC	%REC	RPD	RPD	
Analyte	CAS#	(ng)		Q	(ng)	(ng)		Limits		Limit	Q
Vinyl Chloride	75-01-4	40.48	80.96		50	51.54	103.00	70-130	24.04	30	
trans-1,2-Dichloroethene	156-60-5	45.48	90.96		50	48.18	96.40	70-130	5.77	30	
cis-1,2-Dichloroethene	156-59-2	47.25	94.5		50	49.26	98.50	70-130	4.17	30	
Trichloroethene	79-01-6	48.03	96.06		50	50.05	100.00	70-130	4.12	30	
Tetrachloroethene	127-18-4	42.30	84.6		50	48.51	97.00	70-130	13.68	30	



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Additional QC Information

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Sample Result Calculation Summary (Concentration)

TO-17 (Passive)

	t Sampling Time	<b>DF</b> Dilution	Uc Uptake	<b>M</b> Initial Result	C Calculated Result	
Analyte	minutes	Factor	Rate	ng	μg/m³	File ID
Lab ID: 0007650-01 Sample I	Name: 08B_IAB_04_2024	0328			Х̄ Тетр (	°C): 21.60
Vinyl Chloride	20,137	1.00	0.817	U	U	Kb24040229.D
trans-1,2-Dichloroethene	20,137	1.00	0.444	U	U	Kb24040229.D
cis-1,2-Dichloroethene	20,137	1.00	0.535	U	U	Kb24040229.D
Trichloroethene	20,137	1.00	0.333	U	U	Kb24040229.D
Tetrachloroethene	20,137	1.00	0.413	U	U	Kb24040229.D
ab ID: 0007650-02 Sample I	Name: 08B_IA1_05_20240	)328			Х̄ Тетр (	°C): 21.60
Vinyl Chloride	20,126	1.00	0.817	U	U	Kb24040222.D
trans-1,2-Dichloroethene	20,126	1.00	0.444	U	U	Kb24040222.D
cis-1,2-Dichloroethene	20,126	1.00	0.535	U	U	Kb24040222.D
Trichloroethene	20,126	1.00	0.333	U	U	Kb24040222.D
Tetrachloroethene	20,126	1.00	0.413	5.23	0.628	Kb24040222.D
ab ID: 0007650-03 Sample I	Name: 08B_IA2_06_2024	)328			Х Тетр (	°C): 21.60
Vinyl Chloride	20,120	1.00	0.817	U	U	Ka24040307.D
trans-1,2-Dichloroethene	20,120	1.00	0.444	U	U	Ka24040307.D
cis-1,2-Dichloroethene	20,120	1.00	0.535	U	U	Ka24040307.D
Trichloroethene	20,120	1.00	0.333	U	U	Ka24040307.D
Tetrachloroethene	20,120	1.00	0.413	8.67	1.04	Ka24040307.D

<b>Lab ID:</b> 0007650-04	Sample Name: 08	B_OA_02_20240	)328			<b>х</b> Тетј	p (°C): 1.67	
Vinyl Chloride		20,146	1.00	0.789	U	U	Kb24040224.D	
trans-1,2-Dichloroethene		20,146	1.00	0.428	U	U	Kb24040224.D	
cis-1,2-Dichloroethene		20,146	1.00	0.516	U	U	Kb24040224.D	
Trichloroethene		20,146	1.00	0.321	U	U	Kb24040224.D	
Tetrachloroethene		20.146	1.00	0.399	U	IJ	Kb24040224.D	



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Calculations:

$$C = \frac{1000 \times M \times DF}{Uc \times t}$$

$$Uc = U * ((\frac{Ts + 273.15}{Tu + 273.15})^{1/2})$$

where: C = concentration  $(\mu g/m^3)$ 

M = mass (ng)
DF = dilution factor

Uc = uptake rate (ml/min), corrected

t = sampling time (minutes)

U = compound specific uptake rate Tu = uptake rate study temperature Ts = sample average temperature

Note: Tu is 16.65°C

Reference: Federal Register/Vol. 79, No. 125/June 30, 2014



Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# Method Detection and Reporting Limit Calculations (Concentration) TO-17 (Passive)

Analyte	t Sampling Time minutes	<b>DF</b> Dilution Factor	Uc Uptake Rate	<b>N</b> Initia LOQ	<b>/I</b> l (ng)   LOD		C d (μg/m³) LOD
<b>ab ID:</b> 0007650-01	Sample Name:			LOQ		x̄ Temp (°C): 21	
Vinyl Chloride	20,137	1.00	0.817	10.00	5.00	0.608	0.304
trans-1.2-Dichloroethene	20,137	1.00	0.817	10.00	5.00	1.12	0.560
cis-1.2-Dichloroethene	20,137	1.00	0.535	10.00	5.00	0.929	0.360
Trichloroethene		1.00		10.00		1.49	0.463
	20,137		0.333		5.00		
Tetrachloroethene	20,137	1.00	0.413	10.00	5.00	1.20	0.601
ab ID: 0007650-02	Sample Name:	08B_IA1_05	20240328			<b>x</b> Temp (°C): 21	1.60
Vinyl Chloride	20,126	1.00	0.817	10.00	5.00	0.608	0.304
trans-1,2-Dichloroethene	20,126	1.00	0.444	10.00	5.00	1.12	0.560
cis-1,2-Dichloroethene	20,126	1.00	0.535	10.00	5.00	0.930	0.465
Trichloroethene	20,126	1.00	0.333	10.00	5.00	1.49	0.746
Tetrachloroethene	20,126	1.00	0.413	10.00	5.00	1.20	0.601
<b>ab ID:</b> 0007650-03	Sample Name:	08B IA2 06	20240328			<b>x</b> Temp (°C): 21	1.60
Vinyl Chloride	20,120	1.00	0.817	10.00	5.00	0.608	0.304
trans-1,2-Dichloroethene	20,120	1.00	0.444	10.00	5.00	1.12	0.560
cis-1,2-Dichloroethene	20,120	1.00	0.535	10.00	5.00	0.930	0.465
Trichloroethene	20,120	1.00	0.333	10.00	5.00	1.49	0.747
Tetrachloroethene	20,120	1.00	0.413	10.00	5.00	1.20	0.601
ab ID: 0007650-04	Sample Name:	08B_OA_02_	20240328			<b>X</b> Temp (°C): 1.	67
Vinyl Chloride	20,146	1.00	0.789	10.00	5.00	0.629	0.315
trans-1,2-Dichloroethene	20,146	1.00	0.428	10.00	5.00	1.16	0.579
· · · · · · · · · · · · · · · · · · ·		l	t			1	<del></del>

20,146

20,146

20,146

1.00

1.00

1.00

0.516

0.321

0.399

10.00

10.00

10.00

5.00

5.00

5.00

0.962

1.54

1.24

cis-1,2-Dichloroethene

Trichloroethene

Tetrachloroethene

0.481

0.772

0.622



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Laboratory Certification List

Certification ID	Certification No.	Description	Expires	Project Required
Alaska CS-LAP	19-002	Alaska Department of Environmental Conservation	12/30/2024	
DoD-ELAP	72690/L22-563	United States Department of Defense Environmental Laboratory Accreditation	11/30/2024	
ISO/IEC 17025:2017	72690/L22-563	General Requirements for the Competence of Testing and Calibration Laboratories	11/30/2024	
NEFAP	72690/L22-564	TNI National Environmental Field Activities Program (NEFAP)	11/30/2024	
NY-NELAC	12097	New York Department of Health	04/01/2025	
Utah-NELAC	MD010912023-14	Utah Department of Health	12/31/2024	



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

#### **Qualifiers/Notes and Definitions**

#### General Definitions:

DF Dilution Factor
DL Detection Limit
LOD Limit of Detection
LOQ Limit of Quantitation
NA Not Applicable
Q Qualifier

RPD Relative Percent Difference RT Retention Times in Minutes

RRT Evaluation of Relative Retention Times in RRT Units (qualified if outside  $\pm 0.06$  control limits)

3σ Uncertainty

∉ Compound not on scope of accreditation

+ values are outside method/contract required QC limits

Compound not on scope of accreditation and analyzed with a one-point calibration

#### Sample/Sample Receipt Qualifiers and Notes:

J Value reported below limit of quantitation (LOQ).

U Analyte was not detected and is reported as less than the limit of detection (LOD). The LOD has been adjusted for any

dilution or concentration of the sample.



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H025 Empire DriveSite Location:WisconsinLab Work Order:0007650St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Sample Management Records



526 Underwood Lane Bel Air, Maryland 21014 USA 1-410-838-8780

## PASSIVE AIR SAMPLING - BEACON SAMPLER

CHAIN-OF-CUSTODY

	jkun	ze @bag	west, co	m /	ERP C	257001682)				
Client Information		Tason /			Client PO:	J2303821 P01309	-			
Company: Bay West LLC	Project Name:	Redsb	uro Cla	aners	Turn around tin				C	
Address: 5 Empire Dr.	Location: /2	5 N LOU	cust Stre	et (PSIB)	Normal	Rush (specify) days	Z	M	RA	SE
City/State/Zip. St. Paul / MN /55103	Submitted by:	Anden 9	antelma	n	Analysis:		000	AMBIENT	<u>۲</u>	× E
Phone: 651-724-9757	Email: 10 A 4	antelman (	a bay wes	1, com	Method 1	FO-17 Method 8260C	INDOOR AIR	F	CRAWL SPACE	SEWER GAS
Location ID	Start Date	Start Time	Stop Date	Stop Time	Aver Temp (C)	Notes	YR.	AIR	CE	AS
09B_FAB_04-20240328	3/14/24	1016	3/28/24		21,6	B-IAB-04	X			
08B_ IAI_05_20240328	3/14/24	1022	3/28/24	0948	21.6	B-IA1-05	X			
08B_JA2_06_20240328	3/14/24	1025	3/28/24	0945	21.6	B-IA2-06	X			
08B_ OA-02_20240328	3/14/24	1033	3/26/24	1019	1,667°	B-0A-02		X		
			-							
1										
4										
N										
V										
Special Notes / Instructions: Analytes P	CE, TCE	=, cis	-1,2-1	DCE, to	ans -1.	,2-DCE and viny	ch	lori	de	
	/Time: 3/28/			Received by (signal		1 10 1   10-1-17	9:30			11:00
Relinquished by (signature): Date	/ Time:		F	Received by (signal	ture):	Date / Time:	nous			
For Lab Use Only	con Job No; 76	50	1	Beacon Proposal:	2304	127H02				
Courier Name: Ship	ment Condition:	d		Yes I		Custody Seal No:	5			



#### Beacon Environmental

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

#### CERTIFICATE OF ANALYSIS

Beacon Proposal No.: 230427H01 Laboratory Work Order: 0007649

#### **Project Description:**

Reedsburg Cleaners Reedsburg, WI

Prepared for:

Jason Kunze

**Bay West LLC** 

5 Empire Drive

St. Paul, MN 55103

Ryan W. Schneider Senior Project Manager

April 09, 2024

All data meet requirements as specified in the Beacon Environmental Quality Assurance Project Plan and the results relate only to the samples reported. The work performed was in accordance with ISO/IEC 17025:2017. This report shall not be reproduced, except in full, without written approval of the laboratory. Release of the data contained in this data package has been authorized by the Laboratory Director or his signee, as verified by the following signatures:

Steven C. Thornley Laboratory Director

teven Thornley

Peter B. Kelly Quality Manager

## **Table of Contents**

Cover Page	1
Sample Summary	3
Case Narrative	4
Analytical Results	5
Summary of Compound Detections	6
Data Summary Table-Mass	8
Data Summary Table-Concentration	9
Detailed Analytical Results	10
- Mass	11
0007649-01 - 08B_SSV_02_20240328	12
- Concentration	13
0007649-01 - 08B_SSV_02_20240328	14
QC Summaries	15
Additional QC Information	25
Sample Result Calculations	26
Equation	26
MRL Calculation Table	27
Certifications	28
Notes and Definitions	29
Sample Management Records	30
Chain of Custody	31



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Sample Summary

Lab Sample IDClient Sample IDReceivedAnalysisMatrix0007649-0108B\_SSV\_02\_20240328<br/>Sampler Type:03/29/2024TO-17 (Passive)Soil GasSampler Type:Beacon Passive Sampler

#### **Project Completeness**

Samples Received: 1
Samples Analyzed: 1



526 Underwood Lane Bel Air, MD 21014 USA 1,410.838.8780

Bay West LLCSite Name:<br/>Sempire DriveReedsburg CleanersBeacon Proposal:<br/>230427H01230427H015 Empire DriveSite Location:<br/>Seedsburg, WILab Work Order:<br/>Reported:0007649St. Paul, MN 55103Project Manager:<br/>Jason KunzeReported:<br/>04/09/202404/09/2024

#### Case Narrative

#### U.S. EPA Method TO-17

All samples were analyzed using thermal desorption-gas chromatography/mass spectrometry (TD-GC/MS) instrumentation following U.S. EPA Method TO-17, with laboratory results provided in nanograms (ng) and micrograms per cubic meter ( $\mu$ g/m³). Laboratory QA/QC procedures included internal standards, surrogates, and blanks based on EPA Method TO-17. Analyses and reporting were under BEACON's Quality Assurance Project Plan.

#### **Passive Soil-Gas Survey Notes**

If sample locations are covered with or near the edge of an impervious surface (e.g., asphalt or concrete), the concentrations of compounds in soil gas are higher than if the surfacing was not present. Therefore, the sample location conditions should be considered when comparing results between locations.

Survey findings are exclusive to this project and when the spatial relationships are compared with results of other BEACON Surveys it is necessary to incorporate information from both investigations (e.g., depth to sources, soil types, porosity, soil moisture, presence of impervious surfacing, sample collection times).

#### **Reporting Limits**

The RLs represent a baseline above which results meet laboratory-determined limits of precision and accuracy. All reported results are within the calibration range. The project method quantitation limit (MQL) is the limit of quantitation (LOQ) as noted in the data tables. Beacon determined uptake rates for a suite of compounds with the Beacon sampler for sampling in air. Beacon calculated the uptake rates for the remaining compounds using Graham's Law of Diffusion. The reported data includes LOQ limits.

#### Discussion

Samples were received in proper condition and laboratory control parameters were met unless otherwise noted below. The work performed was in accordance with ISO/IEC 17025:2017.



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Analytical Results

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Summary of Compound Detections- Mass

Lab Sample ID: 0007649-01	<del>-</del>	<b>08B_SSV_02_20240328</b> Soil Gas							
Analyte	CAS#	Result (ng)	Q RT	LOQ (ng)		File ID			
Tetrachloroethene	127-18-4	37.3	8.071	10.0	K	a24040309.D			

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Summary of Compound Detections- Concentration

Lab Sample ID: 000764	49-01 <b>08E</b>	Soil Gas	328			Method:	TO-17 (Passive)
Analyte		File ID					
Tetrachloroethene	127-18-4	4.51		8.071	1.21	K	a24040309.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Data Summary Table- Mass

Compound	Frequency	LOQ (ng)	Max Value (ng)
Tetrachloroethene	1	10	37



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## Data Summary Table- Concentration

Compound	Frequency	LOQ (μg/m³)	Max Value (μg/m³)
Tetrachloroethene	1	1.21	4.51



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## **Detailed Analytical Results**



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

**Detailed Analytical Results- Mass** 



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Lab Sample ID: 0007649-01 **08B\_SSV\_02\_20240328** Method: TO-17 (Passive)
Soil Gas

		Resu	.14	LOO		
Analyte	CAS#		g) Q	(ng)	Analyzed	File ID
Vinyl Chloride	75-01-4	<10	0.0	10.0	04/03/2024 13:01	Ka24040309.D
trans-1,2-Dichloroethene	156-60-5	<10	0.0	10.0	04/03/2024 13:01	Ka24040309.D
cis-1,2-Dichloroethene	156-59-2	<10	0.0	10.0	04/03/2024 13:01	Ka24040309.D
Trichloroethene	79-01-6	<10	0.0	10.0	04/03/2024 13:01	Ka24040309.D
Tetrachloroethene	127-18-4	37	7.3	10.0	04/03/2024 13:01	Ka24040309.D
Analyte	CAS#	% Recovery	Recovery Limits	Q	Analyzed	File ID
Surrogate: 1,2-DCA-d4	17060-07-0	95.8%	70-130		04/03/2024 13:01	Ka24040309.D
Surrogate: Toluene-d8	2037-26-5	88.0%	70-130		04/03/2024 13:01	Ka24040309.D
Surrogate: Bromofluorobenzene	460-00-4	88.8%	70-130		04/03/2024 13:01	Ka24040309.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Detailed Analytical Results- Concentration



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Lab Sample ID: 0007649-01 **08B\_SSV\_02\_20240328** Method: TO-17 (Passive)

Soil Gas

		Resul	l <b>t</b>	LOO		
Analyte	CAS#	(μg/m <sup>2</sup>		(μg/m³)	Analyzed	File ID
Vinyl Chloride	75-01-4	<0.61	3	0.613	04/03/2024 13:01	Ka24040309.D
trans-1,2-Dichloroethene	156-60-5	<1.1	3	1.13	04/03/2024 13:01	Ka24040309.D
cis-1,2-Dichloroethene	156-59-2	< 0.93	6	0.936	04/03/2024 13:01	Ka24040309.D
Trichloroethene	79-01-6	<1.5	0	1.50	04/03/2024 13:01	Ka24040309.D
Tetrachloroethene	127-18-4	4.5	1	1.21	04/03/2024 13:01	Ka24040309.D
Analyte	CAS#	% Recovery	Recovery Limits	Q	Analyzed	File ID
Surrogate: 1,2-DCA-d4	17060-07-0	95.8%	70-130		04/03/2024 13:01	Ka24040309.D
Surrogate: Toluene-d8	2037-26-5	88.0%	70-130		04/03/2024 13:01	Ka24040309.D
Surrogate: Bromofluorobenzene	460-00-4	88.8%	70-130		04/03/2024 13:01	Ka24040309.D



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

QC Information/Summary



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler (mass) - Quality Control Summary

Sequence: B24A120 - Instrument: K System - File ID: Kb24013016.D

B24A120-ICV1 (LCSD/Second Source Verification/CALV)

Analyte	Result	LOQ	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	53.7	10	ng	50.0		107	70-130			
trans-1,2-Dichloroethene	52.6	10	ng	50.0		105	70-130			
cis-1,2-Dichloroethene	50.6	10	ng	50.0		101	70-130			
Trichloroethene	49.6	10	ng	50.0		99.2	70-130			
Tetrachloroethene	46.3	10	ng	50.0		92.5	70-130			
Surrogate: 1,2-DCA-d4	51.5		ng	50.0		103	70-130			
Surrogate: Toluene-d8	50.1		ng	50.0		100	70-130			
Surrogate: Bromofluorobenzene	45.9		ng	50.0		91.9	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler (mass) - Quality Control Summary

Sequence: B24A120 - Instrument: K System - File ID: Kb24013020.D

#### B24A120-ICB1 (Lab Blank/Initial Calibration Blank)

				Spike	Source		%REC		RPD	
Analyte	Result	LOQ	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	<5	10	ng							U
trans-1,2-Dichloroethene	<5	10	ng							U
cis-1,2-Dichloroethene	<5	10	ng							U
Trichloroethene	<5	10	ng							U
Tetrachloroethene	<5	10	ng							U
Surrogate: 1,2-DCA-d4	104		ng	100		104	70-130			
Surrogate: Toluene-d8	101		ng	100		101	70-130			
Surrogate: Bromofluorobenzene	91.4		ng	100		91.4	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler (mass) - Quality Control Summary

#### Sequence: B24D010 - Batch: 24D0009 - Instrument: K System - File ID: Ka24040302.D

#### 24D0009-BS1 (LCS, Calibration Source Verification)

Analyte	Result	LOO	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	41.2	10	ng	50.0	resure	82.3	70-130	10 0	Limit	110103
trans-1,2-Dichloroethene	46.3	10	ng	50.0		92.5	70-130			
cis-1,2-Dichloroethene	48.3	10	ng	50.0		96.7	70-130			
Trichloroethene	49.5	10	ng	50.0		99.0	70-130			
Tetrachloroethene	41.8	10	ng	50.0		83.5	70-130			
Surrogate: 1,2-DCA-d4	49.5		ng	50.0		99.1	70-130			
Surrogate: Toluene-d8	45.0		ng	50.0		90.0	70-130			
Surrogate: Bromofluorobenzene	37.7		ng	50.0		75.4	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

#### Sequence: B24D010 - Batch: 24D0009 - Instrument: K System - File ID: Ka24040303.D

#### 24D0009-BLK1 (Lab Blank)

				Spike	Source		%REC		RPD	
Analyte	Result	LOQ	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	< 0.613	0.613	$\mu g/m^3$							U
trans-1,2-Dichloroethene	<1.13	1.13	$\mu g/m^3$							U
cis-1,2-Dichloroethene	< 0.936	0.936	$\mu g/m^3$							U
Trichloroethene	<1.50	1.50	$\mu g/m^3$							U
Tetrachloroethene	<1.21	1.21	$\mu g/m^3$							U
Surrogate: 1,2-DCA-d4	99.9		ng	100		99.9	70-130			
Surrogate: Toluene-d8	99.2		ng	100		99.2	70-130			
Surrogate: Bromofluorobenzene	83.5		ng	100		83.5	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler (mass) - Quality Control Summary

#### Sequence: B24D010 - Batch: 24D0009 - Instrument: K System - File ID: Ka24040303.D

#### 24D0009-BLK1 (Lab Blank)

Analyte	Result	LOQ	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	<5.0	10	ng							U
trans-1,2-Dichloroethene	<5.0	10	ng							U
cis-1,2-Dichloroethene	< 5.0	10	ng							U
Trichloroethene	< 5.0	10	ng							U
Tetrachloroethene	<5.0	10	ng							U
Surrogate: 1,2-DCA-d4	99.9		ng	100		99.9	70-130			
Surrogate: Toluene-d8	99.2		ng	100		99.2	70-130			
Surrogate: Bromofluorobenzene	83.5		ng	100		83.5	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler (mass) - Quality Control Summary

Sequence: B24D010 - Instrument: K System - File ID: Ka24040304.D

B24D010-ICV1 (LCSD/Second Source Verification/CALV)

				Spike	Source		%REC		RPD	
Analyte	Result	LOQ	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	46.5	10	ng	50.0		93.1	70-130			
trans-1,2-Dichloroethene	47.9	10	ng	50.0		95.7	70-130			
cis-1,2-Dichloroethene	49.7	10	ng	50.0		99.5	70-130			
Trichloroethene	51.9	10	ng	50.0		104	70-130			
Tetrachloroethene	47.4	10	ng	50.0		94.7	70-130			
Surrogate: 1,2-DCA-d4	49.1		ng	50.0		98.1	70-130			
Surrogate: Toluene-d8	48.8		ng	50.0		97.5	70-130			
Surrogate: Bromofluorobenzene	40.4		ng	50.0		80.8	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler (mass) - Quality Control Summary

Sequence: B24D010 - Instrument: K System - File ID: Ka24040312.D

B24D010-CCV1 (LCS, Closing Calibration Verification)

Analyte	Result	LOQ	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Notes
Vinyl Chloride	39.7	10	ng	50.0		79.4	70-130			
trans-1,2-Dichloroethene	47.3	10	ng	50.0		94.5	70-130			
cis-1,2-Dichloroethene	48.4	10	ng	50.0		96.9	70-130			
Trichloroethene	48.7	10	ng	50.0		97.4	70-130			
Tetrachloroethene	45.9	10	ng	50.0		91.8	70-130			
Surrogate: 1,2-DCA-d4	51.1		ng	50.0		102	70-130			
Surrogate: Toluene-d8	51.1		ng	50.0		102	70-130			
Surrogate: Bromofluorobenzene	42.4		ng	50.0		84.8	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

Organics in Air by EPA TO-17 Using Beacon Sampler - Quality Control Summary

Sequence: B24D010 - Instrument: K System - File ID: Ka24040313.D

#### B24D010-CCB1 (Lab Blank)

				Spike	Source		%REC		RPD	
Analyte	Result	LOQ	Units	Level	Result	%REC	Limits	RPD	Limit	Notes
Vinyl Chloride	<5	10	ng							U
trans-1,2-Dichloroethene	<5	10	ng							U
cis-1,2-Dichloroethene	<5	10	ng							U
Trichloroethene	<5	10	ng							U
Tetrachloroethene	<5	10	ng							U
Surrogate: 1,2-DCA-d4	102		ng	100		102	70-130			
Surrogate: Toluene-d8	101		ng	100		101	70-130			
Surrogate: Bromofluorobenzene	84.6		ng	100		84.6	70-130			



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

TO-17 (Passive) - LCS/LCSD RPD Quality Control Summary

 LCS: 24D0009-BS1
 File ID: Ka24040302.D
 Analyzed:
 4/3/24
 10:30

 LCSD: B24D010-ICV1
 File ID: Ka24040304.D
 Analyzed:
 4/3/24
 9:26

		LCS Result	%REC		Spike Level	LCSD Result	%REC	%REC	RPD	RPD	
Analyte	CAS#	(ng)		Q	(ng)	(ng)		Limits		Limit	Q
Vinyl Chloride	75-01-4	41.15	82.3		50	46.54	93.10	70-130	12.29	30	
trans-1,2-Dichloroethene	156-60-5	46.27	92.54		50	47.85	95.70	70-130	3.36	30	
cis-1,2-Dichloroethene	156-59-2	48.33	96.66		50	49.73	99.50	70-130	2.86	30	
Trichloroethene	79-01-6	49.52	99.04		50	51.86	104.00	70-130	4.62	30	
Tetrachloroethene	127-18-4	41.77	83.54		50	47.36	94.70	70-130	12.54	30	



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# Additional QC Information

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## **Sample Result Calculation Summary (Concentration)**

## TO-17 (Passive)

	t	DF	Uc	M	C	
Analyte	Sampling Time minutes	Dilution Factor	Uptake Rate	Initial Result ng	Calculated Result µg/m³	File ID

ab I	<b>D:</b> 0007649-01 <b>Sample Name:</b> 08	B_SSV_02_2024	0328					
	Vinyl Chloride	20,150	1.00	0.810	U	U	Ka24040309.D	
	trans-1,2-Dichloroethene	20,150	1.00	0.440	U	U	Ka24040309.D	
	cis-1,2-Dichloroethene	20,150	1.00	0.530	U	U	Ka24040309.D	
	Trichloroethene	20,150	1.00	0.330	U	U	Ka24040309.D	
	Tetrachloroethene	20,150	1.00	0.410	37.25	4.51	Ka24040309.D	

Calculations:

$$C = \frac{1000 \times M \times DF}{Uc \times t}$$

$$Uc = U * ((\frac{Ts + 273.15}{Tu + 273.15})^{1/2})$$

where: C = concentration  $(\mu g/m^3)$ 

M = mass (ng)
DF = dilution factor

Uc = uptake rate (ml/min), corrected

t = sampling time (minutes)

U = compound specific uptake rate
Tu = uptake rate study temperature
Ts = sample average temperature

Note: Tu is 16.65°C

Reference: Federal Register/Vol. 79, No. 125/June 30, 2014

526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# Method Detection and Reporting Limit Calculations (Concentration)

	Analyte	t Sampling Time minutes	<b>DF</b> Dilution Factor	Uc Uptake Rate	<b>M</b> Initial LOQ ng	<b>C</b> Calculated LOQ μg/m³	
<b>Lab ID:</b> 00076	49-01 Sample Name: 08B_S	SSV_02_2024032	8				
	Vinyl Chloride	20,150	1.00	0.810	10.0	0.613	
	trans-1,2-Dichloroethene	20,150	1.00	0.440	10.0	1.13	
	cis-1,2-Dichloroethene	20,150	1.00	0.530	10.0	0.936	
	Trichloroethene	20,150	1.00	0.330	10.0	1.50	
	Tetrachloroethene	20,150	1.00	0.410	10.0	1.21	



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg Cleaners5 Empire DriveSite Location:Reedsburg, WISt. Paul, MN 55103Project Manager:Jason Kunze

 Beacon Proposal:
 230427H01

 Lab Work Order:
 0007649

 Reported:
 04/09/2024

## Laboratory Certification List

Certification ID	Certification No.	Description	Expires	Project Required
Alaska CS-LAP	19-002	Alaska Department of Environmental Conservation	12/30/2024	
DoD-ELAP	72690/L22-563	United States Department of Defense Environmental Laboratory Accreditation	11/30/2024	
ISO/IEC 17025:2017	72690/L22-563	General Requirements for the Competence of Testing and Calibration Laboratories	11/30/2024	
NEFAP	72690/L22-564	TNI National Environmental Field Activities Program (NEFAP)	11/30/2024	
NY-NELAC	12097	New York Department of Health	04/01/2025	
Utah-NELAC	MD010912023-14	Utah Department of Health	12/31/2024	



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

## **Qualifiers/Notes and Definitions**

#### General Definitions:

DF Dilution Factor
DL Detection Limit
LOD Limit of Detection
LOQ Limit of Quantitation
NA Not Applicable

Q Qualifier

RPD Relative Percent Difference RT Retention Times in Minutes

RRT Evaluation of Relative Retention Times in RRT Units (qualified if outside ±0.06 control limits)

3σ Uncertainty

∉ Compound not on scope of accreditation

+ values are outside method/contract required QC limits

Ø Compound not on scope of accreditation and analyzed with a one-point calibration



526 Underwood Lane Bel Air, MD 21014 USA 1.410.838.8780

Bay West LLCSite Name:Reedsburg CleanersBeacon Proposal:230427H015 Empire DriveSite Location:Reedsburg, WILab Work Order:0007649St. Paul, MN 55103Project Manager:Jason KunzeReported:04/09/2024

# Sample Management Records



## PASSIVE SOIL GAS SAMPLES

CHAIN-OF-CUSTODY

Project In	formation		Client Information				6		
Site Name: Recomburg Clea	iners		Company Name: Bay Wash LLC Project Manager:			Jason Kunze			
ERP 0257001682			Office Location: 5 Empire Dr, St. Paul, UN, 55103 Client PO: J2			230382/PO1309			
Site Location:	1017	- 01	Submitted by:	Andong Ga		Turn around time (	check one):		
125 N Locust Stre	zed (191	DI	Email: agantelman @ B				Rush (specify) days		
Field Sample ID	Start Date	Start Time	Stop Date	Stop Time	Sampling Hole Depth cm inches	Surface Type (Soil, Aspha Concrete, Gravel)	olt, Optional Information (Location Description, Sample Condition, PID / FID Readings, etc)		
088-44V-02200400							B_55V_02		
088-55V-02-20240328		1005	3/28/24	0955	5 inches	Concrete	B-55V_02		
			-						
			7						
	1								
	0								
	-								
Special Instructions: Anal	ytes 1	PCET	CE. Cis	-1,2-D	CE, trans	-1,2-DCE,	+ vinyla chloriste		
Relinquished by (signature):	,	Date / Time:	3/28/24	1100	Received by (signature):	Micolo Wil	Date / Time: 111124 9:30 3/29/24 11:00		
Relinquished by (signature):		Date / Time:			Received by (signature):	. 0	Date / Time:		
For Lab Use Only		Beacon Job No:	7649		Beacon Proposal:	230427H01	Analytical Method:		
Courier Name: Fed Ex	0	Shipment Condi	tion: Good		Custody Seal Intact:  Yes No	n/a	Custody Seal No: 6047395		



## **APPENDIX C**



## PASSIVE VAPOR SAMPLING INFORMATION

		Project Information	
Project Name:			
Bay West Job #:	J230382	<u> </u>	
Bay West Sampler Name(s)		elman	
Weather Conditions	32 and ra	iny	
		Project Information	
Property Address:	125 N Locus		
Property Owner Name:		and Stephanie Halser	
Property Type:		le Family, Residential	
	Sub	o-Slab Installation information	
Concrete Slab Thickness: 5 in Type of Sub-slab installed: Po Time of Sub-Slab Installation: Time for Sub-Slab Vapor Equi Ambient PID (ppm): 0.0	oured 7/18/2023		
		#1	
Sample ID: 08B_SSV_02_2024 Passive Sampler Type: Passiv Sample Location:Sub-Slab Duration of Test: 2 weeks Analysis: PCE, TCE, cis-1,2-DC and vinyl chloride Laboratory:Beacon	e Soil-Gas Sampler E, trans-1,2-DCE,		
Start (or Grab) Sample		Photo 1: Sub-slab sample as left	Photo 2:
Date: 03/14/2024			
Time: 1005			
PID (ppm): 8.0			
Pressure Reading (Pa): -0.9			
End (or Grab) Sample			
Date: 03/28/2024			
Time: 0955			
PID (ppm): 0.6			
Pressure Reading (Pa): 0.1 Pa	a		
		h	
		Photo 3:	Photo 4:



Sample ID: 08B_IAB_04_20240328  Passive Sampler Type: Passive Air Sampler  Sample Location: Basement, southwest corner  Duration of Test: 2 weeks  Analysis: PCE, TCE, cis-1,2-DCE, trans-1,2-DCE, and vinyl chloride  Laboratory: Beacon		
Start (or Grab) Sample	Photo 1: Basement sample	Photo 2:
Date: 03/14/2024		
Time: 1016		
PID (ppm): 1.2		
End (or Grab) Sample		
Date: 03/28/2024		
Time: 0953		
PID (ppm): 0.1		
	Photo 3:	Photo 4:
	#3	
Sample ID: 08B_IA1_05_20240328 Passive Sampler Type: Passive Air Sampler		

Sample ID: 08B_IA1_05_20240328			
Passive Sampler Type: Passive Air Sampler			
Sample Location: 1 <sup>st</sup> Floor, dining room			
Duration of Test: 2 Weels			
Analysis: PCE, TCE, cis-1,2-DCE, trans-1,2-DCE,			
and vinyl chloride			
Laboratory: Beacon			
Start (or Grab) Sample	Photo 1: 1 <sup>st</sup> floor sample	Photo 2:	
Date: 03/14/2024	·		
Time: 1022			
PID (ppm): 1.2			
End (or Grab) Sample			
Date: 03/28/2024			
Time: 0948			
PID (ppm): 0.2			
	Photo 3:	Photo 4:	





Sample ID: 08B\_IA2\_06\_20240328 Passive Sampler Type: Passive Air Sampler Sample Location: 2<sup>nd</sup> Floor, TV room Duration of Test: 2 Weeks Analysis: PCE, TCE, cis-1,2-DCE, trans-1,2-DCE, and vinyl chloride Laboratory: Beacon Start (or Grab) Sample Date: 03/14/2024 Photo 1: 2<sup>nd</sup> floor ambient Photo 2: Time: 1025 PID (ppm): 3.7 **End (or Grab) Sample** Date: 03/28/2024 Time: 0945 PID (ppm): 0.3 Photo 4: \_ Photo 3: #5 Sample ID: 08B\_OA1\_01\_20240328 Passive Sampler Type: Passive Air Sampler Sample Location: 2<sup>nd</sup> Floor, TV room **Duration of Test: 2 Weeks** Analysis: PCE, TCE, cis-1,2-DCE, trans-1,2-DCE, and vinyl chloride Laboratory: Beacon Start (or Grab) Sample Date: 03/14/2024 Photo 1: 2<sup>nd</sup> floor ambient Photo 2: \_\_\_ Time: 1033 PID (ppm): 0.0 End (or Grab) Sample Date: 03/28/2024 Time: 1019 PID (ppm): 0.0 Photo 3:\_ Photo 4:



## APPENDIX D



# Understanding Chemical Vapor Intrusion Testing Results

RR-977 October 2014

#### From the Lab to You

Chemical vapor samples were taken from underneath your house or building and possibly indoors as well. These samples have been tested by a certified laboratory and a report was issued. The Wisconsin Department of Natural Resources (DNR) uses these test results to determine if people in the building are being exposed to chemical vapors coming from nearby contaminated soil or groundwater, and to decide what, if any, action is needed to prevent this exposure.


#### **Indoor Air Testing Results**

If indoor air samples were collected in your house or building, test results from the lab will be compared to the state Vapor Action Level (VAL) for chemicals of concern. The VAL is a chemical compound's numerical value that represents a health hazard risk to no more than 1 in 100,000 people during a lifetime of exposure. If test results show chemical concentrations in your air below the VAL then adverse health effects are extremely rare, even if you were to breathe the chemical at this concentration for your entire life.

Test results showing chemical concentrations in the air at or above the VAL prompt DNR to recommend that exposure to these chemical vapors be reduced. If test results show concentrations significantly above the VAL, or more than one type of chemical vapor is identified in your indoor air, the risk from exposure increases. If the concentration of any indoor chemical vapor greatly exceeds the VAL, DNR is concerned about even short-term exposure and will typically require immediate action to address the problem.

The VAL for each chemical is set by scientific research. It is protective of all people, including those who are most susceptible to adverse health effects.

If test results identify chemicals in your air that are not present in nearby soil or groundwater contamination, it is likely that these vapors are coming from some product or activity in or near your house or building. Many everyday consumer products (e.g., cleaners, solvents, polish, adhesives, lubricants, aerosols, insect repellants, etc.); combustion processes (e.g., smoking, home heating); fuels in attached garages; dry cleaned clothing or draperies; and occupant activities (e.g., craft hobbies), also release chemical vapors into the air.



## **Sub-slab Soil Gas Testing Results**

Soil gas samples were collected from the ground beneath the concrete slab of your building foundation or basement. The lab measured the concentrations of various chemicals in these samples. DNR compares these measurements to the state Vapor Risk Screening Level (VRSL), which identifies the concentration of a chemical in soil gas that scientific research suggests can be a health risk if vapor enters a building. If soil gas measurements exceed the VRSL for a chemical of concern, action to reduce exposure is strongly recommended.

The VRSL is a higher number (higher chemical concentration) than the VAL because it is presumed that concrete building foundations and basement walls will prevent most soil gas from entering a building. Further, any soil gas that does enter a building through cracks, holes, sump pumps, drains, etc., will be diluted to some extent by the indoor air. So, people inside will not be breathing air that includes the full concentration of chemical vapors that exist in the ground.





DNR generally relies on the test results of the sub-slab soil gas samples when determining what, if any, action should be taken related to chemical vapors coming from nearby soil or groundwater contamination. Indoor air quality is highly variable, and it is difficult to make a definitive decision about vapor intrusion based on indoor air sampling alone.

#### **Follow-Up Actions**


If your test results are less than a VAL for indoor air, or a VRSL for sub-slab soil gas, then the air in the house or building should not present a health concern. Follow-up sampling and testing may be necessary to confirm the results, but no other action is typically suggested.

When test results show soil gas chemical concentrations above a VRSL, both DNR and the Wisconsin Department of

Health Services recommend that owners take action to reduce potential exposure. This typically involves installing a vapor mitigation system that vents chemical vapors from beneath your home or building to the outdoors, similar to a radon mitigation system.

If indoor air concentrations exceed a VAL, but sub-slab concentrations are less than a VRSL, then the chemical vapors are most likely coming from indoor sources. Steps should be taken by the house or building owner to identify the products and practices causing the problem and implement appropriate remedies.

If soil gas mitigation is recommended, a representative of the party who is responsible for the soil or groundwater contamination will contact you to discuss your options.



<u>A Note about Measurement Units:</u> The lab report may include some unfamiliar technical language. The most important point to note is whether or not the test result for a specific chemical exceeds a VAL or VRSL, which are also sometimes referred to, generically, as "screening levels."

The concentration of gaseous pollutants in air is typically described in two different ways: 1) as units of mass per volume, where  $\mu g/m3$  represents micrograms of gaseous pollutant per cubic meter of ambient air; and 2) as parts per billion by volume (ppbv), where the volume of a gaseous pollutant is compared to a set volume of ambient air. These are the numbers that are compared to the VAL and VRSL.

## For more information, visit <a href="mailto:dnr.wi.gov/topic/Brownfields/Vapor.html">dnr.wi.gov/topic/Brownfields/Vapor.html</a>

This document contains information about certain state statutes and administrative rules but does not necessarily include all of the details found in the statutes and rules. Readers should consult the actual language of the statutes and rules to answer specific questions. The Wisconsin Department of Natural Resources provides equal opportunity in its employment, programs, services, and functions under an Affirmative Action Plan. If you have any questions, please write to Equal Opportunity Office, Department of Interior, Washington, D.C. 20240. This publication is available in alternative format upon request. Please call 608-267-3543 for more information.