

## Gray, Jane K - DNR

---

**From:** Holt, Michael (he/him/his) <Holt.Michael@epa.gov>  
**Sent:** Tuesday, September 3, 2024 9:53 AM  
**To:** OJ Ojinaga  
**Cc:** Fusinski, Keith; Gray, Jane K - DNR  
**Subject:** Wausau Groundwater Contamination Site VI Sampling Map  
**Attachments:** Wausau VI Source ID Plan 9\_3\_24.pdf

**Follow Up Flag:** Follow up  
**Flag Status:** Flagged

**CAUTION: This email originated from outside the organization.  
Do not click links or open attachments unless you recognize the sender and know the content is safe.**

USEPA, upon consultation with and approval by the WDNR, provides the following explanation of the requested further VI sampling.






- Resampling of all points which have returned levels above SLs.
- Indoor air sampling at SS2 to ensure continued protection
- 8 new passive sampling points should be installed
  - 5 in Building A
  - 3 in Building B
- 5 soil borings to groundwater should be completed

A double ring of passive samplers around the entirety of both buildings is also requested. These perimeters should be 50 feet apart. The points within each perimeter should be 50 feet apart from one another as well when possible. This passive sampler perimeter should help prevent the need for future sampling in the areas of the buildings which are not conducive to sampling work.

We can meet to discuss any comments, questions, or concerns the PRP group may have about this plan the week of September 9<sup>th</sup>.

Thank you,

**D. Michael Holt III**  
Remedial Project Manager  
SEMD, Remedial Response Section 3  
U.S. EPA, Region 5 Chicago  
77 W Jackson Blvd. (SR-6J) Chicago, IL 60604  
312-353-6704 | [holt.michael@epa.gov](mailto:holt.michael@epa.gov)

- Double Perimeter = 
- Above SLs = 
- Below SLs = 
- Grid point Passive SS/IA = 
- Soil point = 

**Sampling Protocol/aspects**

- Two sampling events, one winter and one summer
- Resample all points above SLs
- 8 new passive samplers, 7-14 days for both SS and IA
- Five soil borings to groundwater (~30')
- Double ring of passive sampling perimeters around buildings (50 ft apart)

