Known for excellence.
Built on trust.

GEOTECHNICAL
ENVIRONMENTAL
ECOLOGICAL
WATER
CONSTRUCTION MANAGEMENT

17975 West Sarah Lane
Suite 100
Brookfield, WI 53045
T: 262.754.2560
F: 262.923.7758
www.gza.com

October 8, 2021
File No. 20.0150985.17

Mr. David Hanson, Senior Waste Management Specialist
Wisconsin Department of Natural Resources
1027 West St. Paul Avenue
Milwaukee, Wisconsin 53233

Re: Notification of Preliminary Air and Vapor Sampling Results - September 2021
Bayshore Town Center North Parcels – Building N
5800 North Port Washington Road, Glendale, Wisconsin
BRRTS No. 02-41-587697/FID No. 241492130

Dear Mr. Hanson:

On behalf of Cypress Equities, GZA GeoEnvironmental, Inc. (GZA) is providing preliminary laboratory results of recent indoor air and sub-slab vapor sampling conducted in September 2021, in the retail and residential areas of Building N located on the Bayshore Town Center (BTC) North Parcels at 5800 North Port Washington Road in Glendale, Wisconsin ("Site"). Following internal data quality review, GZA is submitting this letter and the attached analytical results as notification to the Wisconsin Department of Natural Resources (WDNR), as required under Wisconsin Administrative Code (Wis. Admin. Code) Chapter NR 716.14. Please note that further analysis, interpretations, and reporting are anticipated regarding these laboratory results and will be included in subsequent reporting to the WDNR. This letter is subject to the Limitations provided in Attachment 1.

Building N is located on the southwestern portion of the BTC North Parcels that was subject to soil, groundwater, and vapor investigation activities and soil removal during the greater BTC development in the 2004 to 2008 timeframe. Building N houses retail space on the first level, an open-air parking deck on the second and third levels, and residential apartments on the fourth through sixth levels. The north half of Building N, due to the presence of detectable methane and limited volatile organic compounds (VOCs), was constructed with a passive sub-slab membrane vapor mitigation system to prevent the accumulation of methane and potential migration into overlying building spaces. The passive system allows sub-slab membrane vapors to vent to the outside instead of migrating into the building.

On May 7, 2021, a virtual meeting was conducted with the WDNR, Cypress Equities, and GZA to re-familiarize the WDNR with Site conditions, historical investigation findings, and previous regulatory decisions related to BTC. During the meeting, given historical evidence of trichloroethene (TCE) in other areas of the Site and the residential use in the upper floor levels of Building N, the WDNR requested a work plan be developed to assess vapor intrusion potential at Building N. On July 20, 2021, GZA submitted a Site Investigation Work Plan[1] for the BTC North Parcels that included a scope of work for vapor sampling in Building N, the results of which are addressed in this correspondence.

[1] *Site Investigation Work Plan, Bayshore Town Center – North Parcels, 5800 North Port Washington Road, Glendale, Wisconsin, BRRTS No. 02-41-587697, FID No. 241492130*, dated July 20, 2021, GZA File No. 20.0150985.17.

VAPOR SAMPLING PROCEDURES

Sub-Slab and Indoor Air Sampling - Retail and Common Space Areas

The air and vapor sampling activities were conducted on September 7 and 8, 2021, in the northern and southern portions of Building N. Figure 1 presents the Site sampling layout.

The first-floor retail area in the north half of Building N contained two vapor points that were installed during building construction, and the south half of Building N required the installation of three Vapor Pin™ sampling points which occurred on September 7, 2021. The sub-slab vapor points were sampled to assess the potential for and to evaluate the presence of methane and VOCs below the floor slab and were purged and sampled as follows:

- A short piece of Tygon™ tubing was placed on the barb fitting of the probe and joined to Nylaflow sample tubing at the sub-slab probe.
- Prior to sampling, at least five sample train volumes of air were purged from each sub-slab probe using a calibrated MultiRAE Lite Pumped Portable Multi-Gas meter (MultiRAE) equipped with a 10.6 eV lamp and calibrated to 100 parts per million (ppm) isobutylene. The maximum MultiRAE readings were recorded during purging of the sub-slab vapor probes.
- After purging with the MultiRAE, GZA evaluated for vapor probe leaks using ultra-pure helium as a tracer gas to evaluate the potential for diluting the sub-slab vapor samples with air from above the floor slab. Vapor probe purge air was pre-screened with a gas meter capable of detecting helium at very low levels (less than 100 parts per million by volume [ppmv]) to evaluate background helium conditions in sub-slab vapor. A shroud was placed over the sub-slab probe and helium gas was introduced into the shroud until a helium concentration of approximately 100% (1,000,000 ppmv) by volume was achieved in the shroud. Purge air was then screened for helium with the helium-filled shroud in place to evaluate if leakage through the soil-gas probe and fittings was occurring. Significant increases in helium concentrations during purging with the helium-filled shroud in place were recorded in sub-slab probe Building N North-3 SS, and upon sealing a leak, the probe passed the helium leak test.
- A shut-in test was performed to ensure no or minimal leakage through connection in the portion of the sample train outside of the shroud. The shut-in test was conducted by using a vacuum pump to exert a vacuum of at least 5 pounds per square inch (psi) on the sample train. The sample train was considered tight and suitable for sampling if it could maintain the 5-psi vacuum for at least one minute. If the sample train could not maintain a vacuum of at least 5 psi for at least one minute, the sampling train was reset (tightened fittings, reset/replace sub-slab probe, etc.) until the shut-in test passed. All probes passed the shut-in test.
- Following purging and system leak testing, sub-slab vapor samples were collected over a period of approximately 30 to 45 minutes using 6-liter SUMMA® canister sampling at a rate of 200 milliliters per minute (ml/min). The initial and final canister vacuums were measured and recorded on the chain-of-custody form. If the initial canister pressure was less than 25 psi, the canister was not used for sampling and was replaced.
- Following sample collection, the SUMMA® canisters were shipped under chain-of-custody protocol to Pace Analytical Services, LLC (Pace) of Minneapolis, Minnesota for VOC analysis by United States Environmental Protection Agency (USEPA) Method TO-15. The laboratory analytical report for sub-slab samples is provided in Attachment 2.

The collection of indoor air samples included the following procedures:

- The indoor air samples were collected in 6-liter, laboratory-certified SUMMA® canisters equipped with a regulator to allow for a 24-hour (versus typical 8-hour commercial sampling time) sample time per the request of the WDNR.
- An outdoor air background sample was collected on the west side of Building N along Port Washington Road and south of the main access ramp to the parking garage.

- If the initial canister pressure was less than 25 psi, the canister was not used for sampling and was replaced. The SUMMA® canisters were set up with a sampling cane to allow for the air within the breathing zone for an average height person to be sampled.
- Following sample collection, the SUMMA® canisters were shipped under chain-of-custody protocol to Pace for VOC analysis by USEPA Method TO-15. The laboratory analytical report for indoor air samples is provided in Attachment 2.

COMMERCIAL SPACE SUB-SLAB VAPOR AND INDOOR AIR SAMPLING RESULTS

Table 1 presents a summary of the commercial/retail sub-slab and indoor air sample results along with the applicable screening levels. The sub-slab sampling results for Building N were compared to the sub-slab large commercial/industrial sub-slab vapor risk screening levels (VRSLs) provided in the Wisconsin Vapor Quick Look-Up Table and in the May 2021 USEPA Regional Screening Level tables. The results for the first-floor sub-slab samples did not identify VOCs at concentrations exceeding the large commercial/industrial VRSLs, with the exception of a chloroform detection in the south area of Building (sample N-South-1 SS). The concentration of 2,080 micrograms per cubic meter (µg/m^3) exceeded the applicable sub-slab VSRL of 530 µg/m^3. The Building N-South-1 SS vapor sample also had elevated concentrations of tetrahydrofuran, ethanol, acetone, and 2-propanol, which were below the respective VRSLs. Alcohols, such as ethanol and 2-propanol, and ketones, such as acetone, are chemicals that are commonly detected in air and have numerous commercial uses and are contained in extensive product lists. Note that active buildout of the interior tenant spaces was occurring within Building N during our sampling activities.

The indoor air sampling results obtained from the first floor of Building N were compared to the indoor air commercial/industrial vapor action levels (VALs) provided in the Wisconsin Vapor Quick Look-Up Table and in the May 2021 USEPA Regional Screening Level tables. Two indoor air samples were collected from the first-floor common areas in the northern and southern portions of Building N. The common areas were first observed for stored or open chemicals or materials that would likely affect the representativeness of the samples prior to collection. No exceedances of Wisconsin VALs were reported for the TO-15 VOC compounds for either common area air sample.

RESIDENTIAL SPACE INDOOR AIR SAMPLING RESULTS

Indoor air samples in the fourth-floor residential space of Building N were collected from Apartments 411, 420, and 449. The apartments were unoccupied at the time of sampling; however, apartment 420 was remodeled in July 2021 and apartment 449 was remodeled in March 2021. Each of the apartments was observed for stored or open chemicals or materials that would likely affect the representativeness of the samples prior to sampling. The indoor air sampling results obtained from the residential floor of Building N were compared to the indoor air residential VALs provided in the Wisconsin Vapor Quick Look-Up Table and in the May 2021 USEPA Regional Screening Level tables.

No VOC exceedances were reported in the indoor air samples. Although no VAL exceedances were observed, GZA did note the detection of TCE at 1.8 µg/m^3 in unoccupied Apartment 420 and continues to evaluate the significance of the detection. No significant TO-15 VOC detections were reported in the outdoor background air sample that would likely affect the indoor sampling were noted.

CONCLUSIONS

The sub-slab sampling results of Building N revealed an exceedance of the applicable VRSL for chloroform in the southern portion of the building. All five sub-slab samples detected chloroform ranging from 1.6 to 2,040 µg/m^3. Indoor air samples in the common areas did not have detectable chloroform and three of the four indoor air samples from the apartments had detectable chloroform, but at concentrations less than the chloroform VAL. Given the exceedance in the sub-slab, GZA reviewed historical soil and groundwater samples that were analyzed for this portion of the Site during BTC development. Chloroform was not observed in the previous groundwater data from samples collected underlying and

near Building N; however, one detection of chloroform was noted in one soil sample collected from the western portion of the Site at a 4- to 6-foot depth at a concentration of 1,210 micrograms per kilogram (µg/kg). Other soil samples from this portion of the Site did not have detectable chloroform. It is also important to note that chloroform is a trihalomethane and often produced as a byproduct of water chlorination in municipal water systems. Chloroform interference in vapor samples has been documented from alternate sources and in 2008, the USEPA reported that chloroform was detected in 73% of 2,210 indoor air samples. The source of chloroform detected in indoor air may be from a source other than subsurface impacts at the Site. Therefore, GZA continues to evaluate the significance of this detection and will provide supplemental conclusions to the WDNR and recommended next steps.

Should you have any questions regarding the attached results, please feel free to contact the undersigned at (262) 754-2560.

Very truly yours,

GZA GeoEnvironmental, Inc.

Heidi A. Woelfel
Project Manager

John C. Osborne, P.G.
Senior Principal/Hydrogeologist

J:\150900to150999\150985 Bayshore\17 Env'l Oversight WDNR\Report\Air Sample Notification 10-2021\
FINAL 20.0150985.17 Notfctn Prelim Air and Vapor Results_Bayshore Bldg N 10-8-21.docx

Attachments: Tables 1 and 2
Figure 1
Limitations
Laboratory Analytical Report

cc: Mr. Kirk Williams, Cypress Equities

TABLES

TABLE 1
INDOOR AIR AND SUB-SLAB VAPOR SAMPLE RESULTS - RETAIL AND COMMON SPACE AREAS
Building N at Bayshore Town Center
5800 North Port Washington Road
Glendale, Wisconsin

		LOCATION	Building N - Outside Background Air	Building N - North Common Area	Building N - South Common Area	LOCATION	Building N - North - 1 SS	Building N - North - 3 SS	Building N - South - 1 SS	Building N - South - 2 SS	Building N - South - 3 SS
Parameter	**Units**	**Large Commercial/Industrial Indoor Air VALs**	**Outside Air**	**Ambient Air**	**Ambient Air**	**Large Commercial/Industrial Sub-Slab VRSLs**	**Sub-Slab**	**Sub-Slab**	**Sub-Slab**	**Sub-Slab**	**Sub-Slab**
1,1,1-Trichloroethane	µg/m^3	22,000	<0.27	<0.29	<0.29	2,200,000	<0.26	<0.26	<0.26	<0.26	<0.27
1,1,2,2-Tetrachloroethane	µg/m^3	2.1	<0.54	<0.58	<0.58	210	<0.52	<0.52	<0.52	<0.52	<0.54
1,1,2-Trichloroethane	µg/m^3	0.88	<0.29	<0.31	<0.31	88	<0.27	<0.27	<0.27	<0.27	<0.28
1,1,2-Trichlorotrifluoroethane	µg/m^3	NS	0.81 J	0.54 J	0.65 J	NS	0.44 J	0.65 J	0.40 J	0.99 J	0.52 J
1,1-Dichloroethane	µg/m^3	77	<0.24	<0.26	<0.26	7,700	<0.23	<0.23	0.72 J	<0.23	<0.24
1,1-Dichloroethene	µg/m^3	880	<0.2	<0.21	<0.21	88,000	<0.19	<0.19	<0.19	<0.19	<0.2
1,2,4-Trichlorobenzene	µg/m^3	8.8	<7.1	<7.6	<7.6	880	<6.8	<6.8	<6.8	<6.8	<7.0
1,2,4-Trimethylbenzene	µg/m^3	260	<0.52	<0.55	<0.55	26,000	3.7	5.3	2.7	5.4	6.3
1,2-Dibromoethane (EDB)	µg/m^3	0.2	<0.44	<0.46	<0.46	20	<0.42	<0.42	<0.42	<0.42	<0.43
1,2-Dichlorobenzene	µg/m^3	880	<0.59	<0.63	<0.63	88,000	<0.56	<0.56	<0.56	<0.56	<0.58
1,2-Dichloroethane	µg/m^3	4.7	<0.28	<0.3	<0.3	470	<0.27	<0.27	<0.27	<0.27	<0.28
1,2-Dichloropropane	µg/m^3	18	<0.39	<0.42	<0.42	1,800	<0.37	<0.37	<0.37	<0.37	<0.39
1,3,5-Trimethylbenzene	µg/m^3	260	<0.42	<0.45	<0.45	26,000	0.98 J	1.4 J	0.88 J	1.4	1.6
1,3-Butadiene	µg/m^3	4.1	<0.18	<0.19	<0.19	410	<0.17	<0.17	<0.17	<0.17	<0.17
1,3-Dichlorobenzene	µg/m^3	NS	<0.74	<0.79	<0.79	NS	<0.71	<0.71	<0.71	<0.71	1.4 J
1,4-Dichlorobenzene	µg/m^3	11	<1.3	<1.4	<1.4	1,100	<1.2	1.3 J	<1.2	<1.2	<1.3
1,4-Dioxane (p-Dioxane)	µg/m^3	25	<1.1	<1.2	<1.2	2,500	<1.0	<1.0	<1.0	<1.0	<1.1
2-Butanone (MEK)	µg/m^3	22,000	1.1 J	1.0 J	2.1 J	2,200,000	1.3 J	2.2 J	16.4	3.4 J	7.3
2-Hexanone	µg/m^3	130	<0.65	<0.69	<0.69	13,000	<0.61	0.81 J	7.9	<0.61	2.0 J
2-Propanol	µg/m^3	880	1.8 J	106	303	88,000	<0.71	1.6 J	476	16.9	27.9
4-Ethyltoluene	µg/m^3	NS	<0.69	<0.73	<0.73	NS	0.89 J	1.2 J	0.95 J	1.2 J	1.5 J
4-Methyl-2-Pentanone (MIBK)	µg/m^3	13,000	<0.47	<0.5	<0.5	1,300,000	<0.45	<0.45	45.8	0.46 J	1.7 J
Acetone	µg/m^3	140,000	7.9 J	19.3	25.1	14,000,000	4.5 J	7.8 J	377	31.1	36.2
Benzene	µg/m^3	16	0.17 J	0.29 J	0.42 J	1,600	<0.16	0.25 J	2.7	0.87	0.58
Benzyl chloride	µg/m^3	2.5	<1.3	<1.4	<1.4	250	<1.2	<1.2	<1.2	<1.2	<1.3
Bromodichloromethane	µg/m^3	3.3	<0.35	<0.37	<0.37	330	3.4	<0.33	1.7 J	<0.33	<0.34
Bromoform	µg/m^3	110	<2.4	<2.5	<2.5	11,000	<2.3	<2.3	<2.3	<2.3	<2.3
Bromomethane	µg/m^3	22	<0.22	<0.23	<0.23	2,200	<0.21	<0.21	<0.21	<0.21	<0.22
Carbon Disulfide	µg/m^3	3,100	<0.19	<0.2	<0.2	310,000	0.58 J	1.3	0.86 J	1.0	0.44 J
Carbon Tetrachloride	µg/m^3	20	<0.41	<0.43	<0.43	2,000	9.1	0.44 J	3.6	<0.39	<0.4
Chlorobenzene	µg/m^3	220	<0.23	<0.24	<0.24	22,000	<0.22	<0.22	<0.22	<0.22	<0.22
Chloroethane	µg/m^3	44,000	<0.33	<0.35	<0.35	4,400,000	<0.31	<0.31	0.86	<0.31	<0.32
Chloroform	µg/m^3	5.3	<0.27	<0.28	<0.28	530	146	15.6	**2,040**	2.7	1.6
Chloromethane	µg/m^3	390	0.59J	0.86	2.8	39,000	<0.12	<0.12	0.8	<0.12	0.16 J
cis-1,2-Dichloroethene	µg/m^3	NS	<0.28	<0.3	<0.3	NS	8.4	<0.27	0.85 J	2.8	4.6
cis-1,3-Dichloropropene	µg/m^3	NS	<0.37	<0.4	<0.4	NS	<0.35	<0.35	<0.35	<0.35	<0.37
Cyclohexane	µg/m^3	26,000	0.51 J	0.89 J	1.7 J	2,600,000	1.2 J	0.44 J	<0.31	0.7 J	0.81 J
Dibromochloromethane	µg/m^3	NS	<0.75	<0.8	<0.8	NS	<0.72	<0.72	0.93 J	<0.72	<0.74

TABLE 1
INDOOR AIR AND SUB-SLAB VAPOR SAMPLE RESULTS - RETAIL AND COMMON SPACE AREAS
Building N at Bayshore Town Center
5800 North Port Washington Road
Glendale, Wisconsin

		LOCATION	Building N - Outside Background Air	Building N - North Common Area	Building N - South Common Area	LOCATION	Building N - North - 1 SS	Building N - North - 3 SS	Building N - South - 1 SS	Building N - South - 2 SS	Building N - South - 3 SS
Parameter	**Units**	**Large Commercial/Industrial Indoor Air VALs**	**Outside Air**	**Ambient Air**	**Ambient Air**	**Large Commercial/Industrial Sub-Slab VRSLs**	**Sub-Slab**	**Sub-Slab**	**Sub-Slab**	**Sub-Slab**	**Sub-Slab**
Dichlorodifluoromethane	µg/m^3	440	2.2	2.2	2.2	44,000	2.3	2.2	1.9	<0.26	2
Dichlorotetrafluoroethane	µg/m^3	NS	<0.29	<0.31	<0.31	NS	<0.28	<0.28	<0.28	<0.28	<0.29
Ethanol	µg/m^3	NS	7.1	1,690	498	NS	30.6	32.6	2,190	205	195
Ethyl Acetate	µg/m^3	310	<0.19	0.78 J	<0.2	31,000	<0.18	<0.18	<0.18	<0.18	2
Ethylbenzene	µg/m^3	49	<0.45	<0.48	<0.48	4,900	0.50 J	0.76 J	1.6	2	1.3
Hexachloro-1,3-butadiene	µg/m^3	5.6	<1.8	<1.9	<1.9	560	<1.7	<1.7	<1.7	<1.7	<1.8
m&p-Xylene	µg/m^3	440	<0.94	<1.0	1.1 J	44,000	1.8 J	2.7	5.8	4.8	4.4
Methylene Chloride	µg/m^3	2,600	<0.87	<0.92	<0.92	260,000	<0.82	<0.82	1.2 J	<0.82	<0.85
Methyl-tert-butyl ether	µg/m^3	470	<0.18	<0.2	<0.2	47,000	<0.18	<0.18	<0.18	<0.18	<0.18
Naphthalene	µg/m^3	3.6	<3.2	<3.4	<3.4	360	<3.0	3.3 J	<3.0	<3.0	5.4
n-Heptane	µg/m^3	1,800	0.32 J	<0.28	2.6	180,000	<0.25	0.36 J	6.4	1.1 J	0.83 J
n-Hexane	µg/m^3	3,100	0.51 J	0.79 J	0.94 J	310,000	0.63 J	0.70J	6.2	0.91 J	0.68 J
o-Xylene	µg/m^3	440	<0.40	<0.42	0.50 J	44,000	1.1 J	1.5	2.7	2.2	2.2
Propylene	µg/m^3	13,000	<0.19	<0.2	<0.2	1,300,000	<0.18	<0.18	<0.18	<0.18	<0.19
Styrene	µg/m^3	4,400	<0.56	<0.6	1.1 J	440,000	1.1 J	1.5	2	1.3	1.3
Tetrachloroethene	µg/m^3	180	<0.43	<0.45	<0.45	18,000	<0.41	<0.41	<0.41	14.8	22.1
Tetrahydrofuran	µg/m^3	8,800	<0.26	<0.28	<0.28	880,000	<0.25	1.8	1,020	1.8	2.6
Toluene	µg/m^3	22,000	0.71 J	1.9	2.4	2,200,000	1.3	1.4	2.2	3.6	2.8
trans-1,2-Dichloroethene	µg/m^3	180	<0.25	<0.26	0.43 J	18,000	4.4	<0.23	<0.23	0.96 J	1.2 J
trans-1,3-Dichloropropene	µg/m^3	31	<0.79	<0.84	<0.84	3,100	<0.76	<0.76	<0.76	<0.76	<0.78
Trichloroethene	µg/m^3	8.8	<0.29	<0.3	<0.3	880	127	1.9	4.4	40.0	34.5
Trichlorofluoromethane	µg/m^3	NS	1.3 J	1.5 J	1.6 J	NS	1.5 J	1.2 J	1.0 J	1.1 J	1.0 J
Vinyl acetate	µg/m^3	880	<0.3	<0.32	<0.32	88,000	<0.29	<0.29	<0.29	<0.29	<0.3
Vinyl chloride	µg/m^3	28	<0.13	<0.13	<0.13	2,800	<0.12	<0.12	<0.12	<0.12	<0.12

Notes:
1. GZA collected the 6-liter SUMMA® canister indoor air samples on September 7 and 8, 2021. Samples were analyzed by Pace Analytical Services, LLC of Minneapolis, Minnesota for volatile organic compounds (VOCs) by United States Environmental Protection Agency (USEPA) Method TO-15.
2. Sample results are provided in micrograms per cubic meter (µg/m^3).
3. The large commercial/industrial indoor air Vapor Action Levels (VALs) and large commercial/industrial sub-slab Vapor Risk Screening Levels (VRSLs) were obtained from the Wisconsin Department of Natural Resources' (WDNR) "Guidance: Wisconsin Vapor Quick Lookup-Up Table, Indoor Air Vapor Action Levels and Vapor Risk Screening Levels" WI Vapor Quick Look Up Table for Indoor Air VALs and VRSLs (Based on May 2021 U.S. EPA Regional Screening Levels)" provided at: https://dnr.wi.gov/files/PDF/pubs/rr/RR0136.pdf.
4. "NS" denotes that no standard (USEPA RSL) has been established for the analyte.
5. **Bold/underlined** font indicates an exceedance of the respective VAL or VRSL.
6. J-flagged results denote an estimated concentration at or above the limit of detection (LOD) and below the limit of quantitation (LOQ).

TABLE 2
INDOOR AIR VAPOR SAMPLE RESULTS - RESIDENTIAL SPACES
Building N at Bayshore Town Center
5800 North Port Washington Road
Glendale, Wisconsin

PARAMETER	UNITS	RESIDENTIAL INDOOR AIR VAL	Building N - Outside Background Air	Building N North Apt. 411	Building N North Apt. 420	Building N South Apt. 449
1,1,1-Trichloroethane	µg/m^3	5,200	<0.27	<0.28	<0.27	<0.28
1,1,2,2-Tetrachloroethane	µg/m^3	0.48	<0.54	<0.57	<0.54	<0.55
1,1,2-Trichloroethane	µg/m^3	0.21	<0.29	<0.3	<0.28	<0.29
1,1,2-Trichlorotrifluoroethane	µg/m^3	NS	0.81 J	0.57 J	0.71 J	0.75 J
1,1-Dichloroethane	µg/m^3	18	<0.24	<0.25	<0.24	<0.25
1,1-Dichloroethene	µg/m^3	210	<0.2	<0.21	<0.2	<0.21
1,2,4-Trichlorobenzene	µg/m^3	2.1	<7.1	<7.4	<7.0	<7.3
1,2,4-Trimethylbenzene	µg/m^3	63	<0.52	0.56 J	0.85 J	<0.53
1,2-Dibromoethane (EDB)	µg/m^3	0.047	<0.44	<0.46	<0.43	<0.45
1,2-Dichlorobenzene	µg/m^3	210	<0.59	<0.62	<0.58	<0.6
1,2-Dichloroethane	µg/m^3	1.1	<0.28	<0.29	0.42 J	<0.29
1,2-Dichloropropane	µg/m^3	4.2	<0.39	<0.41	<0.39	<0.4
1,3,5-Trimethylbenzene	µg/m^3	63	<0.42	<0.44	<0.42	<0.43
1,3-Butadiene	µg/m^3	0.94	<0.18	<0.18	<0.17	<0.18
1,3-Dichlorobenzene	µg/m^3	NS	<0.74	<0.77	1.2 J	<0.76
1,4-Dichlorobenzene	µg/m^3	2.6	<1.3	<1.3	<1.3	<1.3
1,4-Dioxane (p-Dioxane)	µg/m^3	5.6	<1.1	<1.1	<1.1	<1.1
2-Butanone (MEK)	µg/m^3	5,200	1.1 J	2.4 J	22.3	1.1 J
2-Hexanone	µg/m^3	31	<0.65	<0.67	<0.64	<0.66
2-Propanol	µg/m^3	210	1.8 J	50.8	58.7	18.4
4-Ethyltoluene	µg/m^3	NS	<0.69	<0.72	<0.68	<0.7
4-Methyl-2-Pentanone (MIBK)	µg/m^3	3,100	<0.47	<0.49	3.1 J	1.5 J
Acetone	µg/m^3	32,000	7.9 J	112	137	57.9
Benzene	µg/m^3	3.6	0.17 J	0.34 J	0.63	0.71
Benzyl chloride	µg/m^3	0.57	<1.3	<1.4	<1.3	<1.3
Bromodichloromethane	µg/m^3	0.76	<0.35	<0.36	<0.34	<0.35
Bromoform	µg/m^3	26	<2.4	<2.5	<2.3	<2.4
Bromomethane	µg/m^3	5.2	<0.22	<0.23	<0.22	0.43 J
Carbon Disulfide	µg/m^3	730	<0.19	0.23 J	0.3 J	0.54 J
Carbon Tetrachloride	µg/m^3	4.7	<0.41	0.46 J	<0.4	0.43 J
Chlorobenzene	µg/m^3	52	<0.23	<0.24	<0.22	<0.23
Chloroethane	µg/m^3	10,000	<0.33	<0.34	<0.32	<0.33
Chloroform	µg/m^3	1.2	<0.27	0.28 J	0.78	0.89
Chloromethane	µg/m^3	94	0.59J	1.8	1.5	<0.13
cis-1,2-Dichloroethene	µg/m^3	NS	<0.28	<0.3	<0.28	<0.29
cis-1,3-Dichloropropene	µg/m^3	NS	<0.37	<0.39	<0.37	<0.38
Cyclohexane	µg/m^3	6,300	0.51 J	0.67 J	1.3 J	0.8 J
Dibromochloromethane	µg/m^3	NS	<0.75	<0.78	<0.74	<0.77
Dichlorodifluoromethane	µg/m^3	100	2.2	2.1	4.2	2.3
Dichlorotetrafluoroethane	µg/m^3	NS	<0.29	<0.31	<0.29	<0.3
Ethanol	µg/m^3	NS	7.1	500	545	10.8
Ethyl Acetate	µg/m^3	73	<0.19	4.0	8.5	1.9
Ethylbenzene	µg/m^3	11	<0.45	<0.47	0.74 J	<0.46
Hexachloro-1,3-butadiene	µg/m^3	0.13	<1.8	<1.9	<1.8	<1.8

TABLE 2
INDOOR AIR VAPOR SAMPLE RESULTS - RESIDENTIAL SPACES
Building N at Bayshore Town Center
5800 North Port Washington Road
Glendale, Wisconsin

PARAMETER	UNITS	RESIDENTIAL INDOOR AIR VAL	Building N - Outside Background Air	Building N North Apt. 411	Building N North Apt. 420	Building N South Apt. 449
m&p-Xylene	µg/m^3	100	<0.94	<0.98	2.6	1.0 J
Methylene Chloride	µg/m^3	630	<0.87	<0.9	<0.85	<0.88
Methyl-tert-butyl ether	µg/m^3	110	<0.18	<0.19	<0.18	<0.19
Naphthalene	µg/m^3	0.83	<3.2	<3.3	<3.1	<3.2
n-Heptane	µg/m^3	420	0.32 J	<0.28	<0.26	<0.27
n-Hexane	µg/m^3	730	0.51 J	0.88 J	3.2	0.93 J
o-Xylene	µg/m^3	100	<0.40	<0.41	0.86 J	0.48 J
Propylene	µg/m^3	3,100	<0.19	<0.2	<0.19	<0.19
Styrene	µg/m^3	1,000	<0.56	1.9	1.8	1.1 J
Tetrachloroethene	µg/m^3	42	<0.43	<0.44	<0.42	<0.44
Tetrahydrofuran	µg/m^3	2,100	<0.26	<0.27	4.3	<0.27
Toluene	µg/m^3	5,200	0.71 J	1.9	9.0	1.6
trans-1,2-Dichloroethene	µg/m^3	42	<0.25	2.3	0.73 J	<0.25
trans-1,3-Dichloropropene	µg/m^3	7.0	<0.79	<0.83	<0.78	<0.81
Trichloroethene	µg/m^3	2.1	<0.29	<0.3	1.8	<0.29
Trichlorofluoromethane	µg/m^3	NS	1.3 J	1.5 J	1.3 J	1.3 J
Vinyl acetate	µg/m^3	210	<0.3	<0.32	<0.3	<0.31
Vinyl chloride	µg/m^3	1.7	<0.13	<0.13	<0.12	<0.13

Notes:
1. GZA collected the 6-liter SUMMA® canister indoor air samples on September 7 and 8, 2021. Samples were analyzed by Pace Analytical Services, LLC of Minneapolis, Minnesota for volatile organic compounds (VOCs) by United States Environmental Protection Agency (USEPA) Method TO-15.
2. Sample results are provided in micrograms per cubic meter (µg/m^3).
3. The residential indoor air Vapor Action Levels (VALs) were obtained from the Wisconsin Department of Natural Resources' (WDNR) "Guidance: Wisconsin Vapor Quick Lookup-Up Table, Indoor Air Vapor Action Levels and Vapor Risk Screening Levels" WI Vapor Quick Look Up Table for Indoor Air VALs and VRSLs (Based on May 2021 U.S. EPA Regional Screening Levels)" provided at: https://dnr.wi.gov/files/PDF/pubs/rr/RR0136.pdf.
4. "NS" denotes that no standard (USEPA RSL) has been established for the analyte.
5. **Bold/underlined** font indicates an exceedance of the VAL.
6. J-flagged results denote an estimated concentration at or above the limit of detection (LOD) and below the limit of quantitation (LOQ).

FIGURES

© 2021 - GZA GeoEnvironmental, Inc. J:\150900to150999\150985 Bayshore\17 Env'l Oversight WDNR\GIS\Figure11R_BuildingN_Updated.mxd, October 06, 2021 - 8:43:12 AM, colin.byron

Legend

Monitoring Points

Type

- Indoor Ambient Air Sample
- Outdoor Ambient Air Sample - Collected on West side of building along Port Washington Road
- Residential Area Indoor Ambient Air Sample
- Sub-Slab Vapor Sample
- Site Boundary

W Glen Bay Ave

499

N Centerpark Way

6969

North Building N

South Building N

Building P

W Northshore Dr

N Centerpark Way

499

N

W E

S

UNLESS SPECIFICALLY STATED BY WRITTEN AGREEMENT, THIS DRAWING IS THE SOLE PROPERTY OF GZA GEOENVIRONMENTAL, INC. (GZA). THE INFORMATION SHOWN ON THE DRAWING IS SOLELY FOR THE USE BY GZA'S CLIENT OR THE CLIENT'S DESIGNATED REPRESENTATIVE FOR THE SPECIFIC PROJECT AND LOCATION IDENTIFIED ON THE DRAWING. THE DRAWING SHALL NOT BE TRANSFERRED, REUSED, COPIED, OR ALTERED IN ANY MANNER FOR USE AT ANY OTHER LOCATION OR FOR ANY OTHER PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF GZA, ANY TRANSFER, REUSE, OR MODIFICATION TO THE DRAWING BY THE CLIENT OR OTHERS, WITHOUT THE PRIOR WRITTEN EXPRESS CONSENT OF GZA, WILL BE AT THE USER'S SOLE RISK AND WITHOUT ANY RISK OR LIABILITY TO GZA.

0 20 40 80

SCALE IN FEET

BAYSHORE TOWN CENTER NORTH PARCELS
5800 NORTH PORT WASHINGTON ROAD
GLENDALE, WISCONSIN

PREPARED BY:
GZA GeoEnvironmental, Inc.
Engineers and Scientists
www.gza.com

PREPARED FOR:
BAYSHORE SHOPPING CENTER
PROPERTY OWNER LLC
8144 WALNUT HILL LANE, SUITE1200
DALLAS, TX 75231

BUILDING N PROPOSED VAPOR SAMPLING LOCATIONS

PROJ MGR:	HW	REVIEWED BY:	JCO	CHECKED BY:	JCO	FIG/DWG	1
DESIGNED BY:	HW	DRAWN BY:	CJB	SCALE:	1 in = 42 ft		
DATE:	OCTOBER 2021	PROJECT NO:	20.0150985.17	REVISION NO:		SHEET NO:	

ATTACHMENT 1

Limitations

LIMITATIONS

STANDARD OF CARE

1. GZA's findings and conclusions are based on the work conducted as part of the Scope of Services set forth in the Proposal for Services and/or Report and reflect our professional judgment. These findings and conclusions must be considered not as scientific or engineering certainties, but rather as our professional opinions concerning the limited data gathered during the course of our work. Conditions other than described in this report may be found at the subject location(s).
2. GZA's services were performed using the degree of skill and care ordinarily exercised by qualified professionals performing the same type of services, at the same time, under similar conditions, at the same or a similar property. No warranty, expressed or implied, is made. Specifically, GZA does not and cannot represent that the Site contains no hazardous material, oil, or other latent condition beyond that observed by GZA during its study. Additionally, GZA makes no warranty that any response action or recommended action will achieve all of its objectives or that the findings of this study will be upheld by a local, state or federal agency.
3. In conducting our work, GZA relied upon certain information made available by public agencies, Client and/or others. GZA did not attempt to independently verify the accuracy or completeness of that information. Inconsistencies in this information which we have noted, if any, are discussed in the Report.

SUBSURFACE CONDITIONS

4. The generalized soil profile(s) provided in our Report are based on widely-spaced subsurface explorations and are intended only to convey trends in subsurface conditions. The boundaries between strata are approximate and idealized, and were based on our assessment of subsurface conditions. The composition of strata, and the transitions between strata, may be more variable and more complex than indicated. For more specific information on soil conditions at a specific location refer to the exploration logs. The nature and extent of variations between these explorations may not become evident until further exploration or construction. If variations or other latent conditions then become evident, it will be necessary to reevaluate the conclusions and recommendations of this report.
5. Water level readings have been made, as described in this Report, in and monitoring wells at the specified times and under the stated conditions. These data have been reviewed and interpretations have been made in this report. Fluctuations in the level of the groundwater however occur due to temporal or spatial variations in areal recharge rates, soil heterogeneities, the presence of subsurface utilities, and/or natural or artificially induced perturbations. The observed water table may be other than indicated in the Report.

COMPLIANCE WITH CODES AND REGULATIONS

6. We used reasonable care in identifying and interpreting applicable codes and regulations necessary to execute our scope of work. These codes and regulations are subject to various, and possibly contradictory, interpretations. Interpretations and compliance with codes and regulations by other parties is beyond our control.

SCREENING AND ANALYTICAL TESTING

7. GZA collected environmental samples at the locations identified in the Report. These samples were analyzed for the specific parameters identified in the report. Additional constituents, for which analyses were not conducted, may be present in soil, groundwater, surface water, sediment and/or air. Future Site activities and uses may result in a requirement for additional testing.
8. Our interpretation of field screening and laboratory data is presented in the Report. Unless otherwise noted, we relied upon the laboratory's QA/QC program to validate these data.

9. Variations in the types and concentrations of contaminants observed at a given location or time may occur due to release mechanisms, disposal practices, changes in flow paths, and/or the influence of various physical, chemical, biological or radiological processes. Subsequently observed concentrations may be other than indicated in the Report.

INTERPRETATION OF DATA

10. Our opinions are based on available information as described in the Report, and on our professional judgment. Additional observations made over time, and/or space, may not support the opinions provided in the Report.

ADDITIONAL INFORMATION

11. In the event that the Client or others authorized to use this report obtain additional information on environmental or hazardous waste issues at the Site not contained in this report, such information shall be brought to GZA's attention forthwith. GZA will evaluate such information and, on the basis of this evaluation, may modify the conclusions stated in this report.

ADDITIONAL SERVICES

12. GZA recommends that we be retained to provide services during any future investigations, design, implementation activities, construction, and/or property development/ redevelopment at the Site. This will allow us the opportunity to: i) observe conditions and compliance with our design concepts and opinions; ii) allow for changes in the event that conditions are other than anticipated; iii) provide modifications to our design; and iv) assess the consequences of changes in technologies and/or regulations.

ATTACHMENT 2

Laboratory Analytical Report

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

September 17, 2021

Heidi Woelfel
GZA GeoEnvironmental
17975 West Sarah Lane
Suite 100
Brookfield, WI 53045

RE: Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Dear Heidi Woelfel:

Enclosed are the analytical results for sample(s) received by the laboratory on September 10, 2021. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Minneapolis

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Matt Ray
matt.ray@pacelabs.com
(612)607-1700
Project Manager

Enclosures

cc: Alex Amundson, GZA GeoEnvironmental

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

CERTIFICATIONS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Pace Analytical Services, LLC - Minneapolis MN

1700 Elm Street SE, Minneapolis, MN 55414
1800 Elm Street SE, Minneapolis, MN 55414--Satellite Air Lab
A2LA Certification #: 2926.01*
Alabama Certification #: 40770
Alaska Contaminated Sites Certification #: 17-009*
Alaska DW Certification #: MN00064
Arizona Certification #: AZ0014*
Arkansas DW Certification #: MN00064
Arkansas WW Certification #: 88-0680
California Certification #: 2929
Colorado Certification #: MN00064
Connecticut Certification #: PH-0256
EPA Region 8 Tribal Water Systems+Wyoming DW Certification #: via MN 027-053-137
Florida Certification #: E87605*
Georgia Certification #: 959
Hawaii Certification #: MN00064
Idaho Certification #: MN00064
Illinois Certification #: 200011
Indiana Certification #: C-MN-01
Iowa Certification #: 368
Kansas Certification #: E-10167
Kentucky DW Certification #: 90062
Kentucky WW Certification #: 90062
Louisiana DEQ Certification #: AI-03086*
Louisiana DW Certification #: MN00064
Maine Certification #: MN00064*
Maryland Certification #: 322
Michigan Certification #: 9909
Minnesota Certification #: 027-053-137*
Minnesota Dept of Ag Approval: via MN 027-053-137
Minnesota Petrofund Registration #: 1240*
Mississippi Certification #: MN00064
Missouri Certification #: 10100
Montana Certification #: CERT0092
Nebraska Certification #: NE-OS-18-06
Nevada Certification #: MN00064
New Hampshire Certification #: 2081*
New Jersey Certification #: MN002
New York Certification #: 11647*
North Carolina DW Certification #: 27700
North Carolina WW Certification #: 530
North Dakota Certification #: R-036
Ohio DW Certification #: 41244
Ohio VAP Certification (1700) #: CL101
Ohio VAP Certification (1800) #: CL110*
Oklahoma Certification #: 9507*
Oregon Primary Certification #: MN300001
Oregon Secondary Certification #: MN200001*
Pennsylvania Certification #: 68-00563*
Puerto Rico Certification #: MN00064
South Carolina Certification #:74003001
Tennessee Certification #: TN02818
Texas Certification #: T104704192*
Utah Certification #: MN00064*
Vermont Certification #: VT-027053137
Virginia Certification #: 460163*
Washington Certification #: C486*
West Virginia DEP Certification #: 382
West Virginia DW Certification #: 9952 C
Wisconsin Certification #: 999407970
Wyoming UST Certification #: via A2LA 2926.01
USDA Permit #: P330-19-00208
*Please Note: Applicable air certifications are denoted with an asterisk (*).

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SAMPLE SUMMARY

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab ID	Sample ID	Matrix	Date Collected	Date Received
10578413001	**BUILDING N - NORTH COMMON AREA**	Air	09/08/21 08:47	09/10/21 16:00
10578413002	**BUILDING N - NORTH APT. 411**	Air	09/08/21 08:56	09/10/21 16:00
10578413003	**BUILDING N - NORTH APT. 420**	Air	09/08/21 09:10	09/10/21 16:00
10578413004	**BUILDING N - SOUTH APT. 449**	Air	09/08/21 09:00	09/10/21 16:00
10578413005	**BUILDING N - SOUTH COMMON AREA**	Air	09/08/21 09:18	09/10/21 16:00
10578413006	**BUILDING N - BACKGROUND**	Air	09/08/21 09:21	09/10/21 16:00
10578413007	**BUILDING N - NORTH - 1 SS**	Air	09/08/21 12:15	09/10/21 16:00
10578413008	**BUILDING N - NORTH - 3 SS**	Air	09/08/21 13:15	09/10/21 16:00
10578413009	**BUILDING N - SOUTH - 1 SS**	Air	09/08/21 13:41	09/10/21 16:00
10578413010	**BUILDING N - SOUTH - 2 SS**	Air	09/08/21 14:07	09/10/21 16:00
10578413011	**BUILDING N - SOUTH - 3 SS**	Air	09/08/21 14:32	09/10/21 16:00
10578413012	**FC #1020**	Air		09/10/21 16:00
10578413013	**FC #0377**	Air		09/10/21 16:00
10578413014	**FC #1070**	Air		09/10/21 16:00
10578413015	**FC #0329**	Air		09/10/21 16:00
10578413016	**FC #0457**	Air		09/10/21 16:00

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SAMPLE ANALYTE COUNT

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab ID	Sample ID	Method	Analysts	Analytes Reported
10578413001	**BUILDING N - NORTH COMMON AREA**	TO-15	SW	62
10578413002	**BUILDING N - NORTH APT. 411**	TO-15	SW	62
10578413003	**BUILDING N - NORTH APT. 420**	TO-15	SW	62
10578413004	**BUILDING N - SOUTH APT. 449**	TO-15	SW	62
10578413005	**BUILDING N - SOUTH COMMON AREA**	TO-15	SW	62
10578413006	**BUILDING N - BACKGROUND**	TO-15	SW	62
10578413007	**BUILDING N - NORTH - 1 SS**	TO-15	GT	62
10578413008	**BUILDING N - NORTH - 3 SS**	TO-15	GT	62
10578413009	**BUILDING N - SOUTH - 1 SS**	TO-15	GT	62
10578413010	**BUILDING N - SOUTH - 2 SS**	TO-15	GT	62
10578413011	**BUILDING N - SOUTH - 3 SS**	TO-15	GT	62

PASI-M = Pace Analytical Services - Minneapolis

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SUMMARY OF DETECTION

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab Sample ID / Method	Client Sample ID / Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
10578413001	**BUILDING N - NORTH COMMON AREA**					
TO-15	Acetone	19.3	ug/m3	9.4	09/15/21 19:12	
TO-15	Benzene	0.29J	ug/m3	0.50	09/15/21 19:12	
TO-15	2-Butanone (MEK)	1.0J	ug/m3	4.6	09/15/21 19:12	
TO-15	Chloromethane	0.86	ug/m3	0.65	09/15/21 19:12	
TO-15	Cyclohexane	0.89J	ug/m3	2.7	09/15/21 19:12	
TO-15	Dichlorodifluoromethane	2.2	ug/m3	1.6	09/15/21 19:12	
TO-15	Ethanol	1690	ug/m3	3.0	09/15/21 19:12	E
TO-15	Ethyl acetate	0.78J	ug/m3	1.1	09/15/21 19:12	
TO-15	n-Hexane	0.79J	ug/m3	1.1	09/15/21 19:12	
TO-15	2-Propanol	106	ug/m3	3.9	09/15/21 19:12	
TO-15	Toluene	1.9	ug/m3	1.2	09/15/21 19:12	
TO-15	Trichlorofluoromethane	1.5J	ug/m3	1.8	09/15/21 19:12	
TO-15	1,1,2-Trichlorotrifluoroethane	0.54J	ug/m3	2.4	09/15/21 19:12	
10578413002	**BUILDING N - NORTH APT. 411**					
TO-15	Acetone	112	ug/m3	9.2	09/15/21 18:43	
TO-15	Benzene	0.34J	ug/m3	0.49	09/15/21 18:43	
TO-15	2-Butanone (MEK)	2.4J	ug/m3	4.6	09/15/21 18:43	
TO-15	Carbon disulfide	0.23J	ug/m3	0.96	09/15/21 18:43	
TO-15	Carbon tetrachloride	0.46J	ug/m3	1.9	09/15/21 18:43	
TO-15	Chloroform	0.28J	ug/m3	0.75	09/15/21 18:43	
TO-15	Chloromethane	1.8	ug/m3	0.64	09/15/21 18:43	
TO-15	Cyclohexane	0.67J	ug/m3	2.7	09/15/21 18:43	
TO-15	Dichlorodifluoromethane	2.1	ug/m3	1.5	09/15/21 18:43	
TO-15	trans-1,2-Dichloroethene	2.3	ug/m3	1.2	09/15/21 18:43	
TO-15	Ethanol	500	ug/m3	2.9	09/15/21 18:43	
TO-15	Ethyl acetate	4.0	ug/m3	1.1	09/15/21 18:43	
TO-15	n-Hexane	0.88J	ug/m3	1.1	09/15/21 18:43	
TO-15	2-Propanol	50.8	ug/m3	3.8	09/15/21 18:43	
TO-15	Styrene	1.9	ug/m3	1.3	09/15/21 18:43	
TO-15	Toluene	1.9	ug/m3	1.2	09/15/21 18:43	
TO-15	Trichlorofluoromethane	1.5J	ug/m3	1.7	09/15/21 18:43	
TO-15	1,1,2-Trichlorotrifluoroethane	0.57J	ug/m3	2.4	09/15/21 18:43	
TO-15	1,2,4-Trimethylbenzene	0.56J	ug/m3	1.5	09/15/21 18:43	
10578413003	**BUILDING N - NORTH APT. 420**					
TO-15	Acetone	137	ug/m3	8.7	09/15/21 15:48	
TO-15	Benzene	0.63	ug/m3	0.47	09/15/21 15:48	
TO-15	2-Butanone (MEK)	22.3	ug/m3	4.3	09/15/21 15:48	
TO-15	Carbon disulfide	0.30J	ug/m3	0.91	09/15/21 15:48	
TO-15	Chloroform	0.78	ug/m3	0.71	09/15/21 15:48	
TO-15	Chloromethane	1.5	ug/m3	0.60	09/15/21 15:48	
TO-15	Cyclohexane	1.3J	ug/m3	2.5	09/15/21 15:48	
TO-15	1,3-Dichlorobenzene	1.2J	ug/m3	4.4	09/15/21 15:48	
TO-15	Dichlorodifluoromethane	4.2	ug/m3	1.5	09/15/21 15:48	
TO-15	1,2-Dichloroethane	0.42J	ug/m3	1.2	09/15/21 15:48	
TO-15	trans-1,2-Dichloroethene	0.73J	ug/m3	1.2	09/15/21 15:48	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SUMMARY OF DETECTION

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab Sample ID / Method	Client Sample ID / Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
10578413003	**BUILDING N - NORTH APT. 420**					
TO-15	Ethanol	545	ug/m3	2.8	09/15/21 15:48	
TO-15	Ethyl acetate	8.5	ug/m3	1.1	09/15/21 15:48	
TO-15	Ethylbenzene	0.74J	ug/m3	1.3	09/15/21 15:48	
TO-15	n-Hexane	3.2	ug/m3	1.0	09/15/21 15:48	
TO-15	4-Methyl-2-pentanone (MIBK)	3.1J	ug/m3	6.0	09/15/21 15:48	
TO-15	2-Propanol	58.7	ug/m3	3.6	09/15/21 15:48	
TO-15	Styrene	1.8	ug/m3	1.2	09/15/21 15:48	
TO-15	Tetrahydrofuran	4.3	ug/m3	0.86	09/15/21 15:48	
TO-15	Toluene	9.0	ug/m3	1.1	09/15/21 15:48	
TO-15	Trichloroethene	1.8	ug/m3	1.6	09/15/21 15:48	
TO-15	Trichlorofluoromethane	1.3J	ug/m3	1.6	09/15/21 15:48	
TO-15	1,1,2-Trichlorotrifluoroethane	0.71J	ug/m3	2.2	09/15/21 15:48	
TO-15	1,2,4-Trimethylbenzene	0.85J	ug/m3	1.4	09/15/21 15:48	
TO-15	m&p-Xylene	2.6	ug/m3	2.5	09/15/21 15:48	
TO-15	o-Xylene	0.86J	ug/m3	1.3	09/15/21 15:48	
10578413004	**BUILDING N - SOUTH APT. 449**					
TO-15	Acetone	57.9	ug/m3	9.0	09/15/21 19:41	
TO-15	Benzene	0.71	ug/m3	0.48	09/15/21 19:41	
TO-15	Bromomethane	0.43J	ug/m3	1.2	09/15/21 19:41	
TO-15	2-Butanone (MEK)	1.1J	ug/m3	4.5	09/15/21 19:41	
TO-15	Carbon disulfide	0.54J	ug/m3	0.94	09/15/21 19:41	
TO-15	Carbon tetrachloride	0.43J	ug/m3	1.9	09/15/21 19:41	
TO-15	Chloroform	0.89	ug/m3	0.74	09/15/21 19:41	
TO-15	Cyclohexane	0.80J	ug/m3	2.6	09/15/21 19:41	
TO-15	Dichlorodifluoromethane	2.3	ug/m3	1.5	09/15/21 19:41	
TO-15	Ethanol	10.8	ug/m3	2.9	09/15/21 19:41	
TO-15	Ethyl acetate	1.9	ug/m3	1.1	09/15/21 19:41	
TO-15	n-Hexane	0.93J	ug/m3	1.1	09/15/21 19:41	
TO-15	4-Methyl-2-pentanone (MIBK)	1.5J	ug/m3	6.2	09/15/21 19:41	
TO-15	2-Propanol	18.4	ug/m3	3.7	09/15/21 19:41	
TO-15	Styrene	1.1J	ug/m3	1.3	09/15/21 19:41	
TO-15	Toluene	1.6	ug/m3	1.1	09/15/21 19:41	
TO-15	Trichlorofluoromethane	1.3J	ug/m3	1.7	09/15/21 19:41	
TO-15	1,1,2-Trichlorotrifluoroethane	0.75J	ug/m3	2.3	09/15/21 19:41	
TO-15	m&p-Xylene	1.0J	ug/m3	2.6	09/15/21 19:41	
TO-15	o-Xylene	0.48J	ug/m3	1.3	09/15/21 19:41	
10578413005	**BUILDING N - SOUTH COMMON AREA**					
TO-15	Acetone	25.1	ug/m3	9.4	09/15/21 20:10	
TO-15	Benzene	0.42J	ug/m3	0.50	09/15/21 20:10	
TO-15	2-Butanone (MEK)	2.1J	ug/m3	4.6	09/15/21 20:10	
TO-15	Chloromethane	2.8	ug/m3	0.65	09/15/21 20:10	
TO-15	Cyclohexane	1.7J	ug/m3	2.7	09/15/21 20:10	
TO-15	Dichlorodifluoromethane	2.2	ug/m3	1.6	09/15/21 20:10	
TO-15	trans-1,2-Dichloroethene	0.43J	ug/m3	1.2	09/15/21 20:10	
TO-15	Ethanol	498	ug/m3	3.0	09/15/21 20:10	

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SUMMARY OF DETECTION

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab Sample ID / Method	Client Sample ID / Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
10578413005	**BUILDING N - SOUTH COMMON AREA**					
TO-15	n-Heptane	2.6	ug/m3	1.3	09/15/21 20:10	
TO-15	n-Hexane	0.94J	ug/m3	1.1	09/15/21 20:10	
TO-15	2-Propanol	303	ug/m3	3.9	09/15/21 20:10	
TO-15	Styrene	1.1J	ug/m3	1.3	09/15/21 20:10	
TO-15	Toluene	2.4	ug/m3	1.2	09/15/21 20:10	
TO-15	Trichlorofluoromethane	1.6J	ug/m3	1.8	09/15/21 20:10	
TO-15	1,1,2-Trichlorotrifluoroethane	0.65J	ug/m3	2.4	09/15/21 20:10	
TO-15	m&p-Xylene	1.1J	ug/m3	2.7	09/15/21 20:10	
TO-15	o-Xylene	0.50J	ug/m3	1.4	09/15/21 20:10	
10578413006	**BUILDING N - BACKGROUND**					
TO-15	Acetone	7.9J	ug/m3	8.8	09/15/21 20:39	
TO-15	Benzene	0.17J	ug/m3	0.47	09/15/21 20:39	
TO-15	2-Butanone (MEK)	1.1J	ug/m3	4.4	09/15/21 20:39	
TO-15	Chloromethane	0.59J	ug/m3	0.61	09/15/21 20:39	
TO-15	Cyclohexane	0.51J	ug/m3	2.6	09/15/21 20:39	
TO-15	Dichlorodifluoromethane	2.2	ug/m3	1.5	09/15/21 20:39	
TO-15	Ethanol	7.1	ug/m3	2.8	09/15/21 20:39	
TO-15	n-Heptane	0.32J	ug/m3	1.2	09/15/21 20:39	
TO-15	n-Hexane	0.51J	ug/m3	1.0	09/15/21 20:39	
TO-15	2-Propanol	1.8J	ug/m3	3.6	09/15/21 20:39	
TO-15	Toluene	0.71J	ug/m3	1.1	09/15/21 20:39	
TO-15	Trichlorofluoromethane	1.3J	ug/m3	1.7	09/15/21 20:39	
TO-15	1,1,2-Trichlorotrifluoroethane	0.81J	ug/m3	2.3	09/15/21 20:39	
10578413007	**BUILDING N - NORTH - 1 SS**					
TO-15	Acetone	4.5J	ug/m3	8.4	09/15/21 17:34	
TO-15	Bromodichloromethane	3.4	ug/m3	1.9	09/15/21 17:34	
TO-15	2-Butanone (MEK)	1.3J	ug/m3	4.2	09/15/21 17:34	
TO-15	Carbon disulfide	0.58J	ug/m3	0.88	09/15/21 17:34	
TO-15	Carbon tetrachloride	9.1	ug/m3	1.8	09/15/21 17:34	
TO-15	Chloroform	146	ug/m3	0.69	09/15/21 17:34	
TO-15	Cyclohexane	1.2J	ug/m3	2.4	09/15/21 17:34	
TO-15	Dichlorodifluoromethane	2.3	ug/m3	1.4	09/15/21 17:34	
TO-15	cis-1,2-Dichloroethene	8.4	ug/m3	1.1	09/15/21 17:34	
TO-15	trans-1,2-Dichloroethene	4.4	ug/m3	1.1	09/15/21 17:34	
TO-15	Ethanol	30.6	ug/m3	2.7	09/15/21 17:34	
TO-15	Ethylbenzene	0.50J	ug/m3	1.2	09/15/21 17:34	
TO-15	4-Ethyltoluene	0.89J	ug/m3	3.5	09/15/21 17:34	
TO-15	n-Hexane	0.63J	ug/m3	1.0	09/15/21 17:34	
TO-15	Styrene	1.1J	ug/m3	1.2	09/15/21 17:34	
TO-15	Toluene	1.3	ug/m3	1.1	09/15/21 17:34	
TO-15	Trichloroethene	127	ug/m3	0.76	09/15/21 17:34	
TO-15	Trichlorofluoromethane	1.5J	ug/m3	1.6	09/15/21 17:34	
TO-15	1,1,2-Trichlorotrifluoroethane	0.44J	ug/m3	2.2	09/15/21 17:34	
TO-15	1,2,4-Trimethylbenzene	3.7	ug/m3	1.4	09/15/21 17:34	
TO-15	1,3,5-Trimethylbenzene	0.98J	ug/m3	1.4	09/15/21 17:34	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SUMMARY OF DETECTION

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab Sample ID / Method	Client Sample ID / Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
10578413007	**BUILDING N - NORTH - 1 SS**					
TO-15	m&p-Xylene	1.8J	ug/m3	2.5	09/15/21 17:34	
TO-15	o-Xylene	1.1J	ug/m3	1.2	09/15/21 17:34	
10578413008	**BUILDING N - NORTH - 3 SS**					
TO-15	Acetone	7.8J	ug/m3	8.4	09/15/21 18:31	
TO-15	Benzene	0.25J	ug/m3	0.45	09/15/21 18:31	
TO-15	2-Butanone (MEK)	2.2J	ug/m3	4.2	09/15/21 18:31	
TO-15	Carbon disulfide	1.3	ug/m3	0.88	09/15/21 18:31	
TO-15	Carbon tetrachloride	0.44J	ug/m3	1.8	09/15/21 18:31	
TO-15	Chloroform	15.6	ug/m3	0.69	09/15/21 18:31	
TO-15	Cyclohexane	0.44J	ug/m3	2.4	09/15/21 18:31	
TO-15	1,4-Dichlorobenzene	1.3J	ug/m3	4.3	09/15/21 18:31	
TO-15	Dichlorodifluoromethane	2.2	ug/m3	1.4	09/15/21 18:31	
TO-15	Ethanol	32.6	ug/m3	2.7	09/15/21 18:31	
TO-15	Ethylbenzene	0.76J	ug/m3	1.2	09/15/21 18:31	
TO-15	4-Ethyltoluene	1.2J	ug/m3	3.5	09/15/21 18:31	
TO-15	n-Heptane	0.36J	ug/m3	1.2	09/15/21 18:31	
TO-15	n-Hexane	0.70J	ug/m3	1.0	09/15/21 18:31	
TO-15	2-Hexanone	0.81J	ug/m3	5.8	09/15/21 18:31	
TO-15	Naphthalene	3.3J	ug/m3	3.7	09/15/21 18:31	
TO-15	2-Propanol	1.6J	ug/m3	3.5	09/15/21 18:31	
TO-15	Styrene	1.5	ug/m3	1.2	09/15/21 18:31	
TO-15	Tetrahydrofuran	1.8	ug/m3	0.83	09/15/21 18:31	
TO-15	Toluene	1.4	ug/m3	1.1	09/15/21 18:31	
TO-15	Trichloroethene	1.9	ug/m3	0.76	09/15/21 18:31	
TO-15	Trichlorofluoromethane	1.2J	ug/m3	1.6	09/15/21 18:31	
TO-15	1,1,2-Trichlorotrifluoroethane	0.65J	ug/m3	2.2	09/15/21 18:31	
TO-15	1,2,4-Trimethylbenzene	5.3	ug/m3	1.4	09/15/21 18:31	
TO-15	1,3,5-Trimethylbenzene	1.4J	ug/m3	1.4	09/15/21 18:31	
TO-15	m&p-Xylene	2.7	ug/m3	2.5	09/15/21 18:31	
TO-15	o-Xylene	1.5	ug/m3	1.2	09/15/21 18:31	
10578413009	**BUILDING N - SOUTH - 1 SS**					
TO-15	Acetone	377	ug/m3	8.4	09/15/21 19:28	
TO-15	Benzene	2.7	ug/m3	0.45	09/15/21 19:28	
TO-15	Bromodichloromethane	1.7J	ug/m3	1.9	09/15/21 19:28	
TO-15	2-Butanone (MEK)	16.4	ug/m3	4.2	09/15/21 19:28	
TO-15	Carbon disulfide	0.86J	ug/m3	0.88	09/15/21 19:28	
TO-15	Carbon tetrachloride	3.6	ug/m3	1.8	09/15/21 19:28	
TO-15	Chloroethane	0.86	ug/m3	0.75	09/15/21 19:28	
TO-15	Chloroform	2040	ug/m3	20.7	09/16/21 10:33	
TO-15	Chloromethane	0.80	ug/m3	0.58	09/15/21 19:28	
TO-15	Dibromochloromethane	0.93J	ug/m3	2.4	09/15/21 19:28	
TO-15	Dichlorodifluoromethane	1.9	ug/m3	1.4	09/15/21 19:28	
TO-15	1,1-Dichloroethane	0.72J	ug/m3	1.1	09/15/21 19:28	
TO-15	cis-1,2-Dichloroethene	0.85J	ug/m3	1.1	09/15/21 19:28	
TO-15	Ethanol	2190	ug/m3	80.1	09/16/21 10:33	
TO-15	Ethylbenzene	1.6	ug/m3	1.2	09/15/21 19:28	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SUMMARY OF DETECTION

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab Sample ID / Method	Client Sample ID / Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
10578413009	**BUILDING N - SOUTH - 1 SS**					
TO-15	4-Ethyltoluene	0.95J	ug/m3	3.5	09/15/21 19:28	
TO-15	n-Heptane	6.4	ug/m3	1.2	09/15/21 19:28	
TO-15	n-Hexane	6.2	ug/m3	1.0	09/15/21 19:28	
TO-15	2-Hexanone	7.9	ug/m3	5.8	09/15/21 19:28	
TO-15	Methylene Chloride	1.2J	ug/m3	4.9	09/15/21 19:28	
TO-15	4-Methyl-2-pentanone (MIBK)	45.8	ug/m3	5.8	09/15/21 19:28	
TO-15	2-Propanol	476	ug/m3	3.5	09/15/21 19:28	
TO-15	Styrene	2.0	ug/m3	1.2	09/15/21 19:28	
TO-15	Tetrahydrofuran	1020	ug/m3	25.0	09/16/21 10:33	
TO-15	Toluene	2.2	ug/m3	1.1	09/15/21 19:28	
TO-15	Trichloroethene	4.4	ug/m3	0.76	09/15/21 19:28	
TO-15	Trichlorofluoromethane	1.0J	ug/m3	1.6	09/15/21 19:28	
TO-15	1,1,2-Trichlorotrifluoroethane	0.40J	ug/m3	2.2	09/15/21 19:28	
TO-15	1,2,4-Trimethylbenzene	2.7	ug/m3	1.4	09/15/21 19:28	
TO-15	1,3,5-Trimethylbenzene	0.88J	ug/m3	1.4	09/15/21 19:28	
TO-15	m&p-Xylene	5.8	ug/m3	2.5	09/15/21 19:28	
TO-15	o-Xylene	2.7	ug/m3	1.2	09/15/21 19:28	
10578413010	**BUILDING N - SOUTH - 2 SS**					
TO-15	Acetone	31.1	ug/m3	8.4	09/15/21 19:57	
TO-15	Benzene	0.87	ug/m3	0.45	09/15/21 19:57	
TO-15	2-Butanone (MEK)	3.4J	ug/m3	4.2	09/15/21 19:57	
TO-15	Carbon disulfide	1.0	ug/m3	0.88	09/15/21 19:57	
TO-15	Chloroform	2.7	ug/m3	0.69	09/15/21 19:57	
TO-15	Cyclohexane	0.70J	ug/m3	2.4	09/15/21 19:57	
TO-15	cis-1,2-Dichloroethene	2.8	ug/m3	1.1	09/15/21 19:57	
TO-15	trans-1,2-Dichloroethene	0.96J	ug/m3	1.1	09/15/21 19:57	
TO-15	Ethanol	205	ug/m3	2.7	09/15/21 19:57	
TO-15	Ethylbenzene	2.0	ug/m3	1.2	09/15/21 19:57	
TO-15	4-Ethyltoluene	1.2J	ug/m3	3.5	09/15/21 19:57	
TO-15	n-Heptane	1.1J	ug/m3	1.2	09/15/21 19:57	
TO-15	n-Hexane	0.91J	ug/m3	1.0	09/15/21 19:57	
TO-15	4-Methyl-2-pentanone (MIBK)	0.46J	ug/m3	5.8	09/15/21 19:57	
TO-15	2-Propanol	16.9	ug/m3	3.5	09/15/21 19:57	
TO-15	Styrene	1.3	ug/m3	1.2	09/15/21 19:57	
TO-15	Tetrachloroethene	14.8	ug/m3	0.96	09/15/21 19:57	
TO-15	Tetrahydrofuran	1.8	ug/m3	0.83	09/15/21 19:57	
TO-15	Toluene	3.6	ug/m3	1.1	09/15/21 19:57	
TO-15	Trichloroethene	40.0	ug/m3	0.76	09/15/21 19:57	
TO-15	Trichlorofluoromethane	1.1J	ug/m3	1.6	09/15/21 19:57	
TO-15	1,1,2-Trichlorotrifluoroethane	0.99J	ug/m3	2.2	09/15/21 19:57	
TO-15	1,2,4-Trimethylbenzene	5.4	ug/m3	1.4	09/15/21 19:57	
TO-15	1,3,5-Trimethylbenzene	1.4	ug/m3	1.4	09/15/21 19:57	
TO-15	m&p-Xylene	4.8	ug/m3	2.5	09/15/21 19:57	
TO-15	o-Xylene	2.2	ug/m3	1.2	09/15/21 19:57	
10578413011	**BUILDING N - SOUTH - 3 SS**					
TO-15	Acetone	36.2	ug/m3	8.7	09/15/21 20:25	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

SUMMARY OF DETECTION

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab Sample ID / Method	Client Sample ID / Parameters	Result	Units	Report Limit	Analyzed	Qualifiers
10578413011	**BUILDING N - SOUTH - 3 SS**					
TO-15	Benzene	0.58	ug/m3	0.47	09/15/21 20:25	
TO-15	2-Butanone (MEK)	7.3	ug/m3	4.3	09/15/21 20:25	
TO-15	Carbon disulfide	0.44J	ug/m3	0.91	09/15/21 20:25	
TO-15	Chloroform	1.6	ug/m3	0.71	09/15/21 20:25	
TO-15	Chloromethane	0.16J	ug/m3	0.60	09/15/21 20:25	
TO-15	Cyclohexane	0.81J	ug/m3	2.5	09/15/21 20:25	
TO-15	1,3-Dichlorobenzene	1.4J	ug/m3	4.4	09/15/21 20:25	
TO-15	Dichlorodifluoromethane	2.0	ug/m3	1.5	09/15/21 20:25	
TO-15	cis-1,2-Dichloroethene	4.6	ug/m3	1.2	09/15/21 20:25	
TO-15	trans-1,2-Dichloroethene	1.2J	ug/m3	1.2	09/15/21 20:25	
TO-15	Ethanol	195	ug/m3	2.8	09/15/21 20:25	
TO-15	Ethyl acetate	2.0	ug/m3	1.1	09/15/21 20:25	
TO-15	Ethylbenzene	1.3	ug/m3	1.3	09/15/21 20:25	
TO-15	4-Ethyltoluene	1.5J	ug/m3	3.6	09/15/21 20:25	
TO-15	n-Heptane	0.83J	ug/m3	1.2	09/15/21 20:25	
TO-15	n-Hexane	0.68J	ug/m3	1.0	09/15/21 20:25	
TO-15	2-Hexanone	2.0J	ug/m3	6.0	09/15/21 20:25	
TO-15	4-Methyl-2-pentanone (MIBK)	1.7J	ug/m3	6.0	09/15/21 20:25	
TO-15	Naphthalene	5.4	ug/m3	3.8	09/15/21 20:25	
TO-15	2-Propanol	27.9	ug/m3	3.6	09/15/21 20:25	
TO-15	Styrene	1.3	ug/m3	1.2	09/15/21 20:25	
TO-15	Tetrachloroethene	22.1	ug/m3	0.99	09/15/21 20:25	
TO-15	Tetrahydrofuran	2.6	ug/m3	0.86	09/15/21 20:25	
TO-15	Toluene	2.8	ug/m3	1.1	09/15/21 20:25	
TO-15	Trichloroethene	34.5	ug/m3	0.79	09/15/21 20:25	
TO-15	Trichlorofluoromethane	1.0J	ug/m3	1.6	09/15/21 20:25	
TO-15	1,1,2-Trichlorotrifluoroethane	0.52J	ug/m3	2.2	09/15/21 20:25	
TO-15	1,2,4-Trimethylbenzene	6.3	ug/m3	1.4	09/15/21 20:25	
TO-15	1,3,5-Trimethylbenzene	1.6	ug/m3	1.4	09/15/21 20:25	
TO-15	m&p-Xylene	4.4	ug/m3	2.5	09/15/21 20:25	
TO-15	o-Xylene	2.2	ug/m3	1.3	09/15/21 20:25	

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

PROJECT NARRATIVE

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Method: **TO-15**
Description: TO15 MSV AIR
Client: GZA GeoEnvironmental
Date: September 17, 2021

General Information:
11 samples were analyzed for TO-15 by Pace Analytical Services Minneapolis. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):
All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:
All criteria were within method requirements with any exceptions noted below.

Internal Standards:
All internal standards were within QC limits with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Duplicate Sample:
All duplicate sample results were within method acceptance criteria with any exceptions noted below.

Additional Comments:

Analyte Comments:

QC Batch: 770320

E: Analyte concentration exceeded the calibration range. The reported result is estimated.

- BUILDING N - NORTH COMMON AREA (Lab ID: 10578413001)
  - Ethanol
- DUP (Lab ID: 4106409)
  - Ethanol

This data package has been reviewed for quality and completeness and is approved for release.

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH COMMON AREA **Lab ID: 10578413001** Collected: 09/08/21 08:47 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Acetone	**19.3**	ug/m3	9.4	2.8	1.55		09/15/21 19:12	67-64-1	
Benzene	**0.29J**	ug/m3	0.50	0.18	1.55		09/15/21 19:12	71-43-2	
Benzyl chloride	**<1.4**	ug/m3	4.1	1.4	1.55		09/15/21 19:12	100-44-7	
Bromodichloromethane	**<0.37**	ug/m3	2.1	0.37	1.55		09/15/21 19:12	75-27-4	
Bromoform	**<2.5**	ug/m3	8.1	2.5	1.55		09/15/21 19:12	75-25-2	
Bromomethane	**<0.23**	ug/m3	1.2	0.23	1.55		09/15/21 19:12	74-83-9	
1,3-Butadiene	**<0.19**	ug/m3	0.70	0.19	1.55		09/15/21 19:12	106-99-0	
2-Butanone (MEK)	**1.0J**	ug/m3	4.6	0.72	1.55		09/15/21 19:12	78-93-3	
Carbon disulfide	**<0.20**	ug/m3	0.98	0.20	1.55		09/15/21 19:12	75-15-0	
Carbon tetrachloride	**<0.43**	ug/m3	2.0	0.43	1.55		09/15/21 19:12	56-23-5	
Chlorobenzene	**<0.24**	ug/m3	1.5	0.24	1.55		09/15/21 19:12	108-90-7	
Chloroethane	**<0.35**	ug/m3	0.83	0.35	1.55		09/15/21 19:12	75-00-3	
Chloroform	**<0.28**	ug/m3	0.77	0.28	1.55		09/15/21 19:12	67-66-3	
Chloromethane	**0.86**	ug/m3	0.65	0.13	1.55		09/15/21 19:12	74-87-3	
Cyclohexane	**0.89J**	ug/m3	2.7	0.34	1.55		09/15/21 19:12	110-82-7	
Dibromochloromethane	**<0.80**	ug/m3	2.7	0.80	1.55		09/15/21 19:12	124-48-1	
1,2-Dibromoethane (EDB)	**<0.46**	ug/m3	1.2	0.46	1.55		09/15/21 19:12	106-93-4	
1,2-Dichlorobenzene	**<0.63**	ug/m3	4.7	0.63	1.55		09/15/21 19:12	95-50-1	
1,3-Dichlorobenzene	**<0.79**	ug/m3	4.7	0.79	1.55		09/15/21 19:12	541-73-1	
1,4-Dichlorobenzene	**<1.4**	ug/m3	4.7	1.4	1.55		09/15/21 19:12	106-46-7	
Dichlorodifluoromethane	**2.2**	ug/m3	1.6	0.29	1.55		09/15/21 19:12	75-71-8	
1,1-Dichloroethane	**<0.26**	ug/m3	1.3	0.26	1.55		09/15/21 19:12	75-34-3	
1,2-Dichloroethane	**<0.30**	ug/m3	1.3	0.30	1.55		09/15/21 19:12	107-06-2	
1,1-Dichloroethene	**<0.21**	ug/m3	1.2	0.21	1.55		09/15/21 19:12	75-35-4	
cis-1,2-Dichloroethene	**<0.30**	ug/m3	1.2	0.30	1.55		09/15/21 19:12	156-59-2	
trans-1,2-Dichloroethene	**<0.26**	ug/m3	1.2	0.26	1.55		09/15/21 19:12	156-60-5	
1,2-Dichloropropane	**<0.42**	ug/m3	1.5	0.42	1.55		09/15/21 19:12	78-87-5	
cis-1,3-Dichloropropene	**<0.40**	ug/m3	3.6	0.40	1.55		09/15/21 19:12	10061-01-5	
trans-1,3-Dichloropropene	**<0.84**	ug/m3	3.6	0.84	1.55		09/15/21 19:12	10061-02-6	
Dichlorotetrafluoroethane	**<0.31**	ug/m3	2.2	0.31	1.55		09/15/21 19:12	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.2**	ug/m3	11.4	1.2	1.55		09/15/21 19:12	123-91-1	
Ethanol	**1690**	ug/m3	3.0	0.92	1.55		09/15/21 19:12	64-17-5	E
Ethyl acetate	**0.78J**	ug/m3	1.1	0.20	1.55		09/15/21 19:12	141-78-6	
Ethylbenzene	**<0.48**	ug/m3	1.4	0.48	1.55		09/15/21 19:12	100-41-4	
4-Ethyltoluene	**<0.73**	ug/m3	3.9	0.73	1.55		09/15/21 19:12	622-96-8	
n-Heptane	**<0.28**	ug/m3	1.3	0.28	1.55		09/15/21 19:12	142-82-5	
Hexachloro-1,3-butadiene	**<1.9**	ug/m3	8.4	1.9	1.55		09/15/21 19:12	87-68-3	
n-Hexane	**0.79J**	ug/m3	1.1	0.30	1.55		09/15/21 19:12	110-54-3	
2-Hexanone	**<0.69**	ug/m3	6.4	0.69	1.55		09/15/21 19:12	591-78-6	
Methylene Chloride	**<0.92**	ug/m3	5.5	0.92	1.55		09/15/21 19:12	75-09-2	
4-Methyl-2-pentanone (MIBK)	**<0.50**	ug/m3	6.4	0.50	1.55		09/15/21 19:12	108-10-1	
Methyl-tert-butyl ether	**<0.20**	ug/m3	5.7	0.20	1.55		09/15/21 19:12	1634-04-4	
Naphthalene	**<3.4**	ug/m3	4.1	3.4	1.55		09/15/21 19:12	91-20-3	
2-Propanol	**106**	ug/m3	3.9	0.79	1.55		09/15/21 19:12	67-63-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH COMMON AREA **Lab ID: 10578413001** Collected: 09/08/21 08:47 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Propylene	**<0.20**	ug/m3	1.4	0.20	1.55		09/15/21 19:12	115-07-1	
Styrene	**<0.60**	ug/m3	1.3	0.60	1.55		09/15/21 19:12	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.58**	ug/m3	2.2	0.58	1.55		09/15/21 19:12	79-34-5	
Tetrachloroethene	**<0.45**	ug/m3	1.1	0.45	1.55		09/15/21 19:12	127-18-4	
Tetrahydrofuran	**<0.28**	ug/m3	0.93	0.28	1.55		09/15/21 19:12	109-99-9	
Toluene	**1.9**	ug/m3	1.2	0.38	1.55		09/15/21 19:12	108-88-3	
1,2,4-Trichlorobenzene	**<7.6**	ug/m3	11.7	7.6	1.55		09/15/21 19:12	120-82-1	
1,1,1-Trichloroethane	**<0.29**	ug/m3	1.7	0.29	1.55		09/15/21 19:12	71-55-6	
1,1,2-Trichloroethane	**<0.31**	ug/m3	0.86	0.31	1.55		09/15/21 19:12	79-00-5	
Trichloroethene	**<0.30**	ug/m3	1.7	0.30	1.55		09/15/21 19:12	79-01-6	
Trichlorofluoromethane	**1.5J**	ug/m3	1.8	0.36	1.55		09/15/21 19:12	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.54J**	ug/m3	2.4	0.45	1.55		09/15/21 19:12	76-13-1	
1,2,4-Trimethylbenzene	**<0.55**	ug/m3	1.5	0.55	1.55		09/15/21 19:12	95-63-6	
1,3,5-Trimethylbenzene	**<0.45**	ug/m3	1.5	0.45	1.55		09/15/21 19:12	108-67-8	
Vinyl acetate	**<0.32**	ug/m3	1.1	0.32	1.55		09/15/21 19:12	108-05-4	
Vinyl chloride	**<0.13**	ug/m3	0.40	0.13	1.55		09/15/21 19:12	75-01-4	
m&p-Xylene	**<1.0**	ug/m3	2.7	1.0	1.55		09/15/21 19:12	179601-23-1	
o-Xylene	**<0.42**	ug/m3	1.4	0.42	1.55		09/15/21 19:12	95-47-6	

Sample: BUILDING N - NORTH APT. 411 **Lab ID: 10578413002** Collected: 09/08/21 08:56 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Acetone	**112**	ug/m3	9.2	2.8	1.52		09/15/21 18:43	67-64-1	
Benzene	**0.34J**	ug/m3	0.49	0.17	1.52		09/15/21 18:43	71-43-2	
Benzyl chloride	**<1.4**	ug/m3	4.0	1.4	1.52		09/15/21 18:43	100-44-7	
Bromodichloromethane	**<0.36**	ug/m3	2.1	0.36	1.52		09/15/21 18:43	75-27-4	
Bromoform	**<2.5**	ug/m3	8.0	2.5	1.52		09/15/21 18:43	75-25-2	
Bromomethane	**<0.23**	ug/m3	1.2	0.23	1.52		09/15/21 18:43	74-83-9	
1,3-Butadiene	**<0.18**	ug/m3	0.68	0.18	1.52		09/15/21 18:43	106-99-0	
2-Butanone (MEK)	**2.4J**	ug/m3	4.6	0.71	1.52		09/15/21 18:43	78-93-3	
Carbon disulfide	**0.23J**	ug/m3	0.96	0.20	1.52		09/15/21 18:43	75-15-0	
Carbon tetrachloride	**0.46J**	ug/m3	1.9	0.43	1.52		09/15/21 18:43	56-23-5	
Chlorobenzene	**<0.24**	ug/m3	1.4	0.24	1.52		09/15/21 18:43	108-90-7	
Chloroethane	**<0.34**	ug/m3	0.81	0.34	1.52		09/15/21 18:43	75-00-3	
Chloroform	**0.28J**	ug/m3	0.75	0.28	1.52		09/15/21 18:43	67-66-3	
Chloromethane	**1.8**	ug/m3	0.64	0.13	1.52		09/15/21 18:43	74-87-3	
Cyclohexane	**0.67J**	ug/m3	2.7	0.34	1.52		09/15/21 18:43	110-82-7	
Dibromochloromethane	**<0.78**	ug/m3	2.6	0.78	1.52		09/15/21 18:43	124-48-1	
1,2-Dibromoethane (EDB)	**<0.46**	ug/m3	1.2	0.46	1.52		09/15/21 18:43	106-93-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH APT. 411 **Lab ID: 10578413002** Collected: 09/08/21 08:56 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
1,2-Dichlorobenzene	**<0.62**	ug/m3	4.7	0.62	1.52		09/15/21 18:43	95-50-1	
1,3-Dichlorobenzene	**<0.77**	ug/m3	4.7	0.77	1.52		09/15/21 18:43	541-73-1	
1,4-Dichlorobenzene	**<1.3**	ug/m3	4.7	1.3	1.52		09/15/21 18:43	106-46-7	
Dichlorodifluoromethane	**2.1**	ug/m3	1.5	0.29	1.52		09/15/21 18:43	75-71-8	
1,1-Dichloroethane	**<0.25**	ug/m3	1.3	0.25	1.52		09/15/21 18:43	75-34-3	
1,2-Dichloroethane	**<0.29**	ug/m3	1.3	0.29	1.52		09/15/21 18:43	107-06-2	
1,1-Dichloroethene	**<0.21**	ug/m3	1.2	0.21	1.52		09/15/21 18:43	75-35-4	
cis-1,2-Dichloroethene	**<0.30**	ug/m3	1.2	0.30	1.52		09/15/21 18:43	156-59-2	
trans-1,2-Dichloroethene	**2.3**	ug/m3	1.2	0.26	1.52		09/15/21 18:43	156-60-5	
1,2-Dichloropropane	**<0.41**	ug/m3	1.4	0.41	1.52		09/15/21 18:43	78-87-5	
cis-1,3-Dichloropropene	**<0.39**	ug/m3	3.5	0.39	1.52		09/15/21 18:43	10061-01-5	
trans-1,3-Dichloropropene	**<0.83**	ug/m3	3.5	0.83	1.52		09/15/21 18:43	10061-02-6	
Dichlorotetrafluoroethane	**<0.31**	ug/m3	2.2	0.31	1.52		09/15/21 18:43	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.1**	ug/m3	11.1	1.1	1.52		09/15/21 18:43	123-91-1	
Ethanol	**500**	ug/m3	2.9	0.90	1.52		09/15/21 18:43	64-17-5	
Ethyl acetate	**4.0**	ug/m3	1.1	0.20	1.52		09/15/21 18:43	141-78-6	
Ethylbenzene	**<0.47**	ug/m3	1.3	0.47	1.52		09/15/21 18:43	100-41-4	
4-Ethyltoluene	**<0.72**	ug/m3	3.8	0.72	1.52		09/15/21 18:43	622-96-8	
n-Heptane	**<0.28**	ug/m3	1.3	0.28	1.52		09/15/21 18:43	142-82-5	
Hexachloro-1,3-butadiene	**<1.9**	ug/m3	8.2	1.9	1.52		09/15/21 18:43	87-68-3	
n-Hexane	**0.88J**	ug/m3	1.1	0.29	1.52		09/15/21 18:43	110-54-3	
2-Hexanone	**<0.67**	ug/m3	6.3	0.67	1.52		09/15/21 18:43	591-78-6	
Methylene Chloride	**<0.90**	ug/m3	5.4	0.90	1.52		09/15/21 18:43	75-09-2	
4-Methyl-2-pentanone (MIBK)	**<0.49**	ug/m3	6.3	0.49	1.52		09/15/21 18:43	108-10-1	
Methyl-tert-butyl ether	**<0.19**	ug/m3	5.6	0.19	1.52		09/15/21 18:43	1634-04-4	
Naphthalene	**<3.3**	ug/m3	4.0	3.3	1.52		09/15/21 18:43	91-20-3	
2-Propanol	**50.8**	ug/m3	3.8	0.77	1.52		09/15/21 18:43	67-63-0	
Propylene	**<0.20**	ug/m3	1.3	0.20	1.52		09/15/21 18:43	115-07-1	
Styrene	**1.9**	ug/m3	1.3	0.59	1.52		09/15/21 18:43	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.57**	ug/m3	2.1	0.57	1.52		09/15/21 18:43	79-34-5	
Tetrachloroethene	**<0.44**	ug/m3	1.0	0.44	1.52		09/15/21 18:43	127-18-4	
Tetrahydrofuran	**<0.27**	ug/m3	0.91	0.27	1.52		09/15/21 18:43	109-99-9	
Toluene	**1.9**	ug/m3	1.2	0.37	1.52		09/15/21 18:43	108-88-3	
1,2,4-Trichlorobenzene	**<7.4**	ug/m3	11.5	7.4	1.52		09/15/21 18:43	120-82-1	
1,1,1-Trichloroethane	**<0.28**	ug/m3	1.7	0.28	1.52		09/15/21 18:43	71-55-6	
1,1,2-Trichloroethane	**<0.30**	ug/m3	0.84	0.30	1.52		09/15/21 18:43	79-00-5	
Trichloroethene	**<0.30**	ug/m3	1.7	0.30	1.52		09/15/21 18:43	79-01-6	
Trichlorofluoromethane	**1.5J**	ug/m3	1.7	0.35	1.52		09/15/21 18:43	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.57J**	ug/m3	2.4	0.44	1.52		09/15/21 18:43	76-13-1	
1,2,4-Trimethylbenzene	**0.56J**	ug/m3	1.5	0.54	1.52		09/15/21 18:43	95-63-6	
1,3,5-Trimethylbenzene	**<0.44**	ug/m3	1.5	0.44	1.52		09/15/21 18:43	108-67-8	
Vinyl acetate	**<0.32**	ug/m3	1.1	0.32	1.52		09/15/21 18:43	108-05-4	
Vinyl chloride	**<0.13**	ug/m3	0.40	0.13	1.52		09/15/21 18:43	75-01-4	
m&p-Xylene	**<0.98**	ug/m3	2.7	0.98	1.52		09/15/21 18:43	179601-23-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH APT. 411 **Lab ID: 10578413002** Collected: 09/08/21 08:56 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
o-Xylene	**<0.41**	ug/m3	1.3	0.41	1.52		09/15/21 18:43	95-47-6	

Sample: BUILDING N - NORTH APT. 420 **Lab ID: 10578413003** Collected: 09/08/21 09:10 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Acetone	**137**	ug/m3	8.7	2.6	1.44		09/15/21 15:48	67-64-1	
Benzene	**0.63**	ug/m3	0.47	0.16	1.44		09/15/21 15:48	71-43-2	
Benzyl chloride	**<1.3**	ug/m3	3.8	1.3	1.44		09/15/21 15:48	100-44-7	
Bromodichloromethane	**<0.34**	ug/m3	2.0	0.34	1.44		09/15/21 15:48	75-27-4	
Bromoform	**<2.3**	ug/m3	7.6	2.3	1.44		09/15/21 15:48	75-25-2	
Bromomethane	**<0.22**	ug/m3	1.1	0.22	1.44		09/15/21 15:48	74-83-9	
1,3-Butadiene	**<0.17**	ug/m3	0.65	0.17	1.44		09/15/21 15:48	106-99-0	
2-Butanone (MEK)	**22.3**	ug/m3	4.3	0.67	1.44		09/15/21 15:48	78-93-3	
Carbon disulfide	**0.30J**	ug/m3	0.91	0.19	1.44		09/15/21 15:48	75-15-0	
Carbon tetrachloride	**<0.40**	ug/m3	1.8	0.40	1.44		09/15/21 15:48	56-23-5	
Chlorobenzene	**<0.22**	ug/m3	1.3	0.22	1.44		09/15/21 15:48	108-90-7	
Chloroethane	**<0.32**	ug/m3	0.77	0.32	1.44		09/15/21 15:48	75-00-3	
Chloroform	**0.78**	ug/m3	0.71	0.26	1.44		09/15/21 15:48	67-66-3	
Chloromethane	**1.5**	ug/m3	0.60	0.12	1.44		09/15/21 15:48	74-87-3	
Cyclohexane	**1.3J**	ug/m3	2.5	0.32	1.44		09/15/21 15:48	110-82-7	
Dibromochloromethane	**<0.74**	ug/m3	2.5	0.74	1.44		09/15/21 15:48	124-48-1	
1,2-Dibromoethane (EDB)	**<0.43**	ug/m3	1.1	0.43	1.44		09/15/21 15:48	106-93-4	
1,2-Dichlorobenzene	**<0.58**	ug/m3	4.4	0.58	1.44		09/15/21 15:48	95-50-1	
1,3-Dichlorobenzene	**1.2J**	ug/m3	4.4	0.73	1.44		09/15/21 15:48	541-73-1	
1,4-Dichlorobenzene	**<1.3**	ug/m3	4.4	1.3	1.44		09/15/21 15:48	106-46-7	
Dichlorodifluoromethane	**4.2**	ug/m3	1.5	0.27	1.44		09/15/21 15:48	75-71-8	
1,1-Dichloroethane	**<0.24**	ug/m3	1.2	0.24	1.44		09/15/21 15:48	75-34-3	
1,2-Dichloroethane	**0.42J**	ug/m3	1.2	0.28	1.44		09/15/21 15:48	107-06-2	
1,1-Dichloroethene	**<0.20**	ug/m3	1.2	0.20	1.44		09/15/21 15:48	75-35-4	
cis-1,2-Dichloroethene	**<0.28**	ug/m3	1.2	0.28	1.44		09/15/21 15:48	156-59-2	
trans-1,2-Dichloroethene	**0.73J**	ug/m3	1.2	0.24	1.44		09/15/21 15:48	156-60-5	
1,2-Dichloropropane	**<0.39**	ug/m3	1.4	0.39	1.44		09/15/21 15:48	78-87-5	
cis-1,3-Dichloropropene	**<0.37**	ug/m3	3.3	0.37	1.44		09/15/21 15:48	10061-01-5	
trans-1,3-Dichloropropene	**<0.78**	ug/m3	3.3	0.78	1.44		09/15/21 15:48	10061-02-6	
Dichlorotetrafluoroethane	**<0.29**	ug/m3	2.0	0.29	1.44		09/15/21 15:48	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.1**	ug/m3	10.6	1.1	1.44		09/15/21 15:48	123-91-1	
Ethanol	**545**	ug/m3	2.8	0.85	1.44		09/15/21 15:48	64-17-5	
Ethyl acetate	**8.5**	ug/m3	1.1	0.19	1.44		09/15/21 15:48	141-78-6	
Ethylbenzene	**0.74J**	ug/m3	1.3	0.44	1.44		09/15/21 15:48	100-41-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH APT. 420 **Lab ID: 10578413003** Collected: 09/08/21 09:10 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
4-Ethyltoluene	**<0.68**	ug/m3	3.6	0.68	1.44		09/15/21 15:48	622-96-8	
n-Heptane	**<0.26**	ug/m3	1.2	0.26	1.44		09/15/21 15:48	142-82-5	
Hexachloro-1,3-butadiene	**<1.8**	ug/m3	7.8	1.8	1.44		09/15/21 15:48	87-68-3	
n-Hexane	**3.2**	ug/m3	1.0	0.28	1.44		09/15/21 15:48	110-54-3	
2-Hexanone	**<0.64**	ug/m3	6.0	0.64	1.44		09/15/21 15:48	591-78-6	
Methylene Chloride	**<0.85**	ug/m3	5.1	0.85	1.44		09/15/21 15:48	75-09-2	
4-Methyl-2-pentanone (MIBK)	**3.1J**	ug/m3	6.0	0.46	1.44		09/15/21 15:48	108-10-1	
Methyl-tert-butyl ether	**<0.18**	ug/m3	5.3	0.18	1.44		09/15/21 15:48	1634-04-4	
Naphthalene	**<3.1**	ug/m3	3.8	3.1	1.44		09/15/21 15:48	91-20-3	
2-Propanol	**58.7**	ug/m3	3.6	0.73	1.44		09/15/21 15:48	67-63-0	
Propylene	**<0.19**	ug/m3	1.3	0.19	1.44		09/15/21 15:48	115-07-1	
Styrene	**1.8**	ug/m3	1.2	0.55	1.44		09/15/21 15:48	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.54**	ug/m3	2.0	0.54	1.44		09/15/21 15:48	79-34-5	
Tetrachloroethene	**<0.42**	ug/m3	0.99	0.42	1.44		09/15/21 15:48	127-18-4	
Tetrahydrofuran	**4.3**	ug/m3	0.86	0.26	1.44		09/15/21 15:48	109-99-9	
Toluene	**9.0**	ug/m3	1.1	0.35	1.44		09/15/21 15:48	108-88-3	
1,2,4-Trichlorobenzene	**<7.0**	ug/m3	10.9	7.0	1.44		09/15/21 15:48	120-82-1	
1,1,1-Trichloroethane	**<0.27**	ug/m3	1.6	0.27	1.44		09/15/21 15:48	71-55-6	
1,1,2-Trichloroethane	**<0.28**	ug/m3	0.80	0.28	1.44		09/15/21 15:48	79-00-5	
Trichloroethene	**1.8**	ug/m3	1.6	0.28	1.44		09/15/21 15:48	79-01-6	
Trichlorofluoromethane	**1.3J**	ug/m3	1.6	0.34	1.44		09/15/21 15:48	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.71J**	ug/m3	2.2	0.42	1.44		09/15/21 15:48	76-13-1	
1,2,4-Trimethylbenzene	**0.85J**	ug/m3	1.4	0.51	1.44		09/15/21 15:48	95-63-6	
1,3,5-Trimethylbenzene	**<0.42**	ug/m3	1.4	0.42	1.44		09/15/21 15:48	108-67-8	
Vinyl acetate	**<0.30**	ug/m3	1.0	0.30	1.44		09/15/21 15:48	108-05-4	
Vinyl chloride	**<0.12**	ug/m3	0.37	0.12	1.44		09/15/21 15:48	75-01-4	
m&p-Xylene	**2.6**	ug/m3	2.5	0.92	1.44		09/15/21 15:48	179601-23-1	
o-Xylene	**0.86J**	ug/m3	1.3	0.39	1.44		09/15/21 15:48	95-47-6	

Sample: BUILDING N - SOUTH APT. 449 **Lab ID: 10578413004** Collected: 09/08/21 09:00 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
Acetone	**57.9**	ug/m3	9.0	2.7	1.49		09/15/21 19:41	67-64-1	
Benzene	**0.71**	ug/m3	0.48	0.17	1.49		09/15/21 19:41	71-43-2	
Benzyl chloride	**<1.3**	ug/m3	3.9	1.3	1.49		09/15/21 19:41	100-44-7	
Bromodichloromethane	**<0.35**	ug/m3	2.0	0.35	1.49		09/15/21 19:41	75-27-4	
Bromoform	**<2.4**	ug/m3	7.8	2.4	1.49		09/15/21 19:41	75-25-2	
Bromomethane	**0.43J**	ug/m3	1.2	0.22	1.49		09/15/21 19:41	74-83-9	
1,3-Butadiene	**<0.18**	ug/m3	0.67	0.18	1.49		09/15/21 19:41	106-99-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH APT. 449 **Lab ID: 10578413004** Collected: 09/08/21 09:00 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
2-Butanone (MEK)	**1.1J**	ug/m3	4.5	0.69	1.49		09/15/21 19:41	78-93-3	
Carbon disulfide	**0.54J**	ug/m3	0.94	0.19	1.49		09/15/21 19:41	75-15-0	
Carbon tetrachloride	**0.43J**	ug/m3	1.9	0.42	1.49		09/15/21 19:41	56-23-5	
Chlorobenzene	**<0.23**	ug/m3	1.4	0.23	1.49		09/15/21 19:41	108-90-7	
Chloroethane	**<0.33**	ug/m3	0.80	0.33	1.49		09/15/21 19:41	75-00-3	
Chloroform	**0.89**	ug/m3	0.74	0.27	1.49		09/15/21 19:41	67-66-3	
Chloromethane	**<0.13**	ug/m3	0.63	0.13	1.49		09/15/21 19:41	74-87-3	
Cyclohexane	**0.80J**	ug/m3	2.6	0.33	1.49		09/15/21 19:41	110-82-7	
Dibromochloromethane	**<0.77**	ug/m3	2.6	0.77	1.49		09/15/21 19:41	124-48-1	
1,2-Dibromoethane (EDB)	**<0.45**	ug/m3	1.2	0.45	1.49		09/15/21 19:41	106-93-4	
1,2-Dichlorobenzene	**<0.60**	ug/m3	4.6	0.60	1.49		09/15/21 19:41	95-50-1	
1,3-Dichlorobenzene	**<0.76**	ug/m3	4.6	0.76	1.49		09/15/21 19:41	541-73-1	
1,4-Dichlorobenzene	**<1.3**	ug/m3	4.6	1.3	1.49		09/15/21 19:41	106-46-7	
Dichlorodifluoromethane	**2.3**	ug/m3	1.5	0.28	1.49		09/15/21 19:41	75-71-8	
1,1-Dichloroethane	**<0.25**	ug/m3	1.2	0.25	1.49		09/15/21 19:41	75-34-3	
1,2-Dichloroethane	**<0.29**	ug/m3	1.2	0.29	1.49		09/15/21 19:41	107-06-2	
1,1-Dichloroethene	**<0.21**	ug/m3	1.2	0.21	1.49		09/15/21 19:41	75-35-4	
cis-1,2-Dichloroethene	**<0.29**	ug/m3	1.2	0.29	1.49		09/15/21 19:41	156-59-2	
trans-1,2-Dichloroethene	**<0.25**	ug/m3	1.2	0.25	1.49		09/15/21 19:41	156-60-5	
1,2-Dichloropropane	**<0.40**	ug/m3	1.4	0.40	1.49		09/15/21 19:41	78-87-5	
cis-1,3-Dichloropropene	**<0.38**	ug/m3	3.4	0.38	1.49		09/15/21 19:41	10061-01-5	
trans-1,3-Dichloropropene	**<0.81**	ug/m3	3.4	0.81	1.49		09/15/21 19:41	10061-02-6	
Dichlorotetrafluoroethane	**<0.30**	ug/m3	2.1	0.30	1.49		09/15/21 19:41	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.1**	ug/m3	10.9	1.1	1.49		09/15/21 19:41	123-91-1	
Ethanol	**10.8**	ug/m3	2.9	0.88	1.49		09/15/21 19:41	64-17-5	
Ethyl acetate	**1.9**	ug/m3	1.1	0.20	1.49		09/15/21 19:41	141-78-6	
Ethylbenzene	**<0.46**	ug/m3	1.3	0.46	1.49		09/15/21 19:41	100-41-4	
4-Ethyltoluene	**<0.70**	ug/m3	3.7	0.70	1.49		09/15/21 19:41	622-96-8	
n-Heptane	**<0.27**	ug/m3	1.2	0.27	1.49		09/15/21 19:41	142-82-5	
Hexachloro-1,3-butadiene	**<1.8**	ug/m3	8.1	1.8	1.49		09/15/21 19:41	87-68-3	
n-Hexane	**0.93J**	ug/m3	1.1	0.28	1.49		09/15/21 19:41	110-54-3	
2-Hexanone	**<0.66**	ug/m3	6.2	0.66	1.49		09/15/21 19:41	591-78-6	
Methylene Chloride	**<0.88**	ug/m3	5.3	0.88	1.49		09/15/21 19:41	75-09-2	
4-Methyl-2-pentanone (MIBK)	**1.5J**	ug/m3	6.2	0.48	1.49		09/15/21 19:41	108-10-1	
Methyl-tert-butyl ether	**<0.19**	ug/m3	5.5	0.19	1.49		09/15/21 19:41	1634-04-4	
Naphthalene	**<3.2**	ug/m3	4.0	3.2	1.49		09/15/21 19:41	91-20-3	
2-Propanol	**18.4**	ug/m3	3.7	0.76	1.49		09/15/21 19:41	67-63-0	
Propylene	**<0.19**	ug/m3	1.3	0.19	1.49		09/15/21 19:41	115-07-1	
Styrene	**1.1J**	ug/m3	1.3	0.57	1.49		09/15/21 19:41	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.55**	ug/m3	2.1	0.55	1.49		09/15/21 19:41	79-34-5	
Tetrachloroethene	**<0.44**	ug/m3	1.0	0.44	1.49		09/15/21 19:41	127-18-4	
Tetrahydrofuran	**<0.27**	ug/m3	0.89	0.27	1.49		09/15/21 19:41	109-99-9	
Toluene	**1.6**	ug/m3	1.1	0.36	1.49		09/15/21 19:41	108-88-3	
1,2,4-Trichlorobenzene	**<7.3**	ug/m3	11.2	7.3	1.49		09/15/21 19:41	120-82-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH APT. 449 **Lab ID: 10578413004** Collected: 09/08/21 09:00 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
1,1,1-Trichloroethane	**<0.28**	ug/m3	1.7	0.28	1.49		09/15/21 19:41	71-55-6	
1,1,2-Trichloroethane	**<0.29**	ug/m3	0.83	0.29	1.49		09/15/21 19:41	79-00-5	
Trichloroethene	**<0.29**	ug/m3	1.6	0.29	1.49		09/15/21 19:41	79-01-6	
Trichlorofluoromethane	**1.3J**	ug/m3	1.7	0.35	1.49		09/15/21 19:41	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.75J**	ug/m3	2.3	0.43	1.49		09/15/21 19:41	76-13-1	
1,2,4-Trimethylbenzene	**<0.53**	ug/m3	1.5	0.53	1.49		09/15/21 19:41	95-63-6	
1,3,5-Trimethylbenzene	**<0.43**	ug/m3	1.5	0.43	1.49		09/15/21 19:41	108-67-8	
Vinyl acetate	**<0.31**	ug/m3	1.1	0.31	1.49		09/15/21 19:41	108-05-4	
Vinyl chloride	**<0.13**	ug/m3	0.39	0.13	1.49		09/15/21 19:41	75-01-4	
m&p-Xylene	**1.0J**	ug/m3	2.6	0.96	1.49		09/15/21 19:41	179601-23-1	
o-Xylene	**0.48J**	ug/m3	1.3	0.40	1.49		09/15/21 19:41	95-47-6	

Sample: BUILDING N - SOUTH COMMON AREA **Lab ID: 10578413005** Collected: 09/08/21 09:18 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Acetone	**25.1**	ug/m3	9.4	2.8	1.55		09/15/21 20:10	67-64-1	
Benzene	**0.42J**	ug/m3	0.50	0.18	1.55		09/15/21 20:10	71-43-2	
Benzyl chloride	**<1.4**	ug/m3	4.1	1.4	1.55		09/15/21 20:10	100-44-7	
Bromodichloromethane	**<0.37**	ug/m3	2.1	0.37	1.55		09/15/21 20:10	75-27-4	
Bromoform	**<2.5**	ug/m3	8.1	2.5	1.55		09/15/21 20:10	75-25-2	
Bromomethane	**<0.23**	ug/m3	1.2	0.23	1.55		09/15/21 20:10	74-83-9	
1,3-Butadiene	**<0.19**	ug/m3	0.70	0.19	1.55		09/15/21 20:10	106-99-0	
2-Butanone (MEK)	**2.1J**	ug/m3	4.6	0.72	1.55		09/15/21 20:10	78-93-3	
Carbon disulfide	**<0.20**	ug/m3	0.98	0.20	1.55		09/15/21 20:10	75-15-0	
Carbon tetrachloride	**<0.43**	ug/m3	2.0	0.43	1.55		09/15/21 20:10	56-23-5	
Chlorobenzene	**<0.24**	ug/m3	1.5	0.24	1.55		09/15/21 20:10	108-90-7	
Chloroethane	**<0.35**	ug/m3	0.83	0.35	1.55		09/15/21 20:10	75-00-3	
Chloroform	**<0.28**	ug/m3	0.77	0.28	1.55		09/15/21 20:10	67-66-3	
Chloromethane	**2.8**	ug/m3	0.65	0.13	1.55		09/15/21 20:10	74-87-3	
Cyclohexane	**1.7J**	ug/m3	2.7	0.34	1.55		09/15/21 20:10	110-82-7	
Dibromochloromethane	**<0.80**	ug/m3	2.7	0.80	1.55		09/15/21 20:10	124-48-1	
1,2-Dibromoethane (EDB)	**<0.46**	ug/m3	1.2	0.46	1.55		09/15/21 20:10	106-93-4	
1,2-Dichlorobenzene	**<0.63**	ug/m3	4.7	0.63	1.55		09/15/21 20:10	95-50-1	
1,3-Dichlorobenzene	**<0.79**	ug/m3	4.7	0.79	1.55		09/15/21 20:10	541-73-1	
1,4-Dichlorobenzene	**<1.4**	ug/m3	4.7	1.4	1.55		09/15/21 20:10	106-46-7	
Dichlorodifluoromethane	**2.2**	ug/m3	1.6	0.29	1.55		09/15/21 20:10	75-71-8	
1,1-Dichloroethane	**<0.26**	ug/m3	1.3	0.26	1.55		09/15/21 20:10	75-34-3	
1,2-Dichloroethane	**<0.30**	ug/m3	1.3	0.30	1.55		09/15/21 20:10	107-06-2	
1,1-Dichloroethene	**<0.21**	ug/m3	1.2	0.21	1.55		09/15/21 20:10	75-35-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH COMMON AREA **Lab ID: 10578413005** Collected: 09/08/21 09:18 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
cis-1,2-Dichloroethene	**<0.30**	ug/m3	1.2	0.30	1.55		09/15/21 20:10	156-59-2	
trans-1,2-Dichloroethene	**0.43J**	ug/m3	1.2	0.26	1.55		09/15/21 20:10	156-60-5	
1,2-Dichloropropane	**<0.42**	ug/m3	1.5	0.42	1.55		09/15/21 20:10	78-87-5	
cis-1,3-Dichloropropene	**<0.40**	ug/m3	3.6	0.40	1.55		09/15/21 20:10	10061-01-5	
trans-1,3-Dichloropropene	**<0.84**	ug/m3	3.6	0.84	1.55		09/15/21 20:10	10061-02-6	
Dichlorotetrafluoroethane	**<0.31**	ug/m3	2.2	0.31	1.55		09/15/21 20:10	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.2**	ug/m3	11.4	1.2	1.55		09/15/21 20:10	123-91-1	
Ethanol	**498**	ug/m3	3.0	0.92	1.55		09/15/21 20:10	64-17-5	
Ethyl acetate	**<0.20**	ug/m3	1.1	0.20	1.55		09/15/21 20:10	141-78-6	
Ethylbenzene	**<0.48**	ug/m3	1.4	0.48	1.55		09/15/21 20:10	100-41-4	
4-Ethyltoluene	**<0.73**	ug/m3	3.9	0.73	1.55		09/15/21 20:10	622-96-8	
n-Heptane	**2.6**	ug/m3	1.3	0.28	1.55		09/15/21 20:10	142-82-5	
Hexachloro-1,3-butadiene	**<1.9**	ug/m3	8.4	1.9	1.55		09/15/21 20:10	87-68-3	
n-Hexane	**0.94J**	ug/m3	1.1	0.30	1.55		09/15/21 20:10	110-54-3	
2-Hexanone	**<0.69**	ug/m3	6.4	0.69	1.55		09/15/21 20:10	591-78-6	
Methylene Chloride	**<0.92**	ug/m3	5.5	0.92	1.55		09/15/21 20:10	75-09-2	
4-Methyl-2-pentanone (MIBK)	**<0.50**	ug/m3	6.4	0.50	1.55		09/15/21 20:10	108-10-1	
Methyl-tert-butyl ether	**<0.20**	ug/m3	5.7	0.20	1.55		09/15/21 20:10	1634-04-4	
Naphthalene	**<3.4**	ug/m3	4.1	3.4	1.55		09/15/21 20:10	91-20-3	
2-Propanol	**303**	ug/m3	3.9	0.79	1.55		09/15/21 20:10	67-63-0	
Propylene	**<0.20**	ug/m3	1.4	0.20	1.55		09/15/21 20:10	115-07-1	
Styrene	**1.1J**	ug/m3	1.3	0.60	1.55		09/15/21 20:10	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.58**	ug/m3	2.2	0.58	1.55		09/15/21 20:10	79-34-5	
Tetrachloroethene	**<0.45**	ug/m3	1.1	0.45	1.55		09/15/21 20:10	127-18-4	
Tetrahydrofuran	**<0.28**	ug/m3	0.93	0.28	1.55		09/15/21 20:10	109-99-9	
Toluene	**2.4**	ug/m3	1.2	0.38	1.55		09/15/21 20:10	108-88-3	
1,2,4-Trichlorobenzene	**<7.6**	ug/m3	11.7	7.6	1.55		09/15/21 20:10	120-82-1	
1,1,1-Trichloroethane	**<0.29**	ug/m3	1.7	0.29	1.55		09/15/21 20:10	71-55-6	
1,1,2-Trichloroethane	**<0.31**	ug/m3	0.86	0.31	1.55		09/15/21 20:10	79-00-5	
Trichloroethene	**<0.30**	ug/m3	1.7	0.30	1.55		09/15/21 20:10	79-01-6	
Trichlorofluoromethane	**1.6J**	ug/m3	1.8	0.36	1.55		09/15/21 20:10	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.65J**	ug/m3	2.4	0.45	1.55		09/15/21 20:10	76-13-1	
1,2,4-Trimethylbenzene	**<0.55**	ug/m3	1.5	0.55	1.55		09/15/21 20:10	95-63-6	
1,3,5-Trimethylbenzene	**<0.45**	ug/m3	1.5	0.45	1.55		09/15/21 20:10	108-67-8	
Vinyl acetate	**<0.32**	ug/m3	1.1	0.32	1.55		09/15/21 20:10	108-05-4	
Vinyl chloride	**<0.13**	ug/m3	0.40	0.13	1.55		09/15/21 20:10	75-01-4	
m&p-Xylene	**1.1J**	ug/m3	2.7	1.0	1.55		09/15/21 20:10	179601-23-1	
o-Xylene	**0.50J**	ug/m3	1.4	0.42	1.55		09/15/21 20:10	95-47-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - BACKGROUND **Lab ID: 10578413006** Collected: 09/08/21 09:21 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
Acetone	**7.9J**	ug/m3	8.8	2.6	1.46		09/15/21 20:39	67-64-1	
Benzene	**0.17J**	ug/m3	0.47	0.17	1.46		09/15/21 20:39	71-43-2	
Benzyl chloride	**<1.3**	ug/m3	3.8	1.3	1.46		09/15/21 20:39	100-44-7	
Bromodichloromethane	**<0.35**	ug/m3	2.0	0.35	1.46		09/15/21 20:39	75-27-4	
Bromoform	**<2.4**	ug/m3	7.7	2.4	1.46		09/15/21 20:39	75-25-2	
Bromomethane	**<0.22**	ug/m3	1.2	0.22	1.46		09/15/21 20:39	74-83-9	
1,3-Butadiene	**<0.18**	ug/m3	0.66	0.18	1.46		09/15/21 20:39	106-99-0	
2-Butanone (MEK)	**1.1J**	ug/m3	4.4	0.68	1.46		09/15/21 20:39	78-93-3	
Carbon disulfide	**<0.19**	ug/m3	0.92	0.19	1.46		09/15/21 20:39	75-15-0	
Carbon tetrachloride	**<0.41**	ug/m3	1.9	0.41	1.46		09/15/21 20:39	56-23-5	
Chlorobenzene	**<0.23**	ug/m3	1.4	0.23	1.46		09/15/21 20:39	108-90-7	
Chloroethane	**<0.33**	ug/m3	0.78	0.33	1.46		09/15/21 20:39	75-00-3	
Chloroform	**<0.27**	ug/m3	0.72	0.27	1.46		09/15/21 20:39	67-66-3	
Chloromethane	**0.59J**	ug/m3	0.61	0.12	1.46		09/15/21 20:39	74-87-3	
Cyclohexane	**0.51J**	ug/m3	2.6	0.32	1.46		09/15/21 20:39	110-82-7	
Dibromochloromethane	**<0.75**	ug/m3	2.5	0.75	1.46		09/15/21 20:39	124-48-1	
1,2-Dibromoethane (EDB)	**<0.44**	ug/m3	1.1	0.44	1.46		09/15/21 20:39	106-93-4	
1,2-Dichlorobenzene	**<0.59**	ug/m3	4.5	0.59	1.46		09/15/21 20:39	95-50-1	
1,3-Dichlorobenzene	**<0.74**	ug/m3	4.5	0.74	1.46		09/15/21 20:39	541-73-1	
1,4-Dichlorobenzene	**<1.3**	ug/m3	4.5	1.3	1.46		09/15/21 20:39	106-46-7	
Dichlorodifluoromethane	**2.2**	ug/m3	1.5	0.27	1.46		09/15/21 20:39	75-71-8	
1,1-Dichloroethane	**<0.24**	ug/m3	1.2	0.24	1.46		09/15/21 20:39	75-34-3	
1,2-Dichloroethane	**<0.28**	ug/m3	1.2	0.28	1.46		09/15/21 20:39	107-06-2	
1,1-Dichloroethene	**<0.20**	ug/m3	1.2	0.20	1.46		09/15/21 20:39	75-35-4	
cis-1,2-Dichloroethene	**<0.28**	ug/m3	1.2	0.28	1.46		09/15/21 20:39	156-59-2	
trans-1,2-Dichloroethene	**<0.25**	ug/m3	1.2	0.25	1.46		09/15/21 20:39	156-60-5	
1,2-Dichloropropane	**<0.39**	ug/m3	1.4	0.39	1.46		09/15/21 20:39	78-87-5	
cis-1,3-Dichloropropene	**<0.37**	ug/m3	3.4	0.37	1.46		09/15/21 20:39	10061-01-5	
trans-1,3-Dichloropropene	**<0.79**	ug/m3	3.4	0.79	1.46		09/15/21 20:39	10061-02-6	
Dichlorotetrafluoroethane	**<0.29**	ug/m3	2.1	0.29	1.46		09/15/21 20:39	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.1**	ug/m3	10.7	1.1	1.46		09/15/21 20:39	123-91-1	
Ethanol	**7.1**	ug/m3	2.8	0.86	1.46		09/15/21 20:39	64-17-5	
Ethyl acetate	**<0.19**	ug/m3	1.1	0.19	1.46		09/15/21 20:39	141-78-6	
Ethylbenzene	**<0.45**	ug/m3	1.3	0.45	1.46		09/15/21 20:39	100-41-4	
4-Ethyltoluene	**<0.69**	ug/m3	3.6	0.69	1.46		09/15/21 20:39	622-96-8	
n-Heptane	**0.32J**	ug/m3	1.2	0.26	1.46		09/15/21 20:39	142-82-5	
Hexachloro-1,3-butadiene	**<1.8**	ug/m3	7.9	1.8	1.46		09/15/21 20:39	87-68-3	
n-Hexane	**0.51J**	ug/m3	1.0	0.28	1.46		09/15/21 20:39	110-54-3	
2-Hexanone	**<0.65**	ug/m3	6.1	0.65	1.46		09/15/21 20:39	591-78-6	
Methylene Chloride	**<0.87**	ug/m3	5.2	0.87	1.46		09/15/21 20:39	75-09-2	
4-Methyl-2-pentanone (MIBK)	**<0.47**	ug/m3	6.1	0.47	1.46		09/15/21 20:39	108-10-1	
Methyl-tert-butyl ether	**<0.18**	ug/m3	5.3	0.18	1.46		09/15/21 20:39	1634-04-4	
Naphthalene	**<3.2**	ug/m3	3.9	3.2	1.46		09/15/21 20:39	91-20-3	
2-Propanol	**1.8J**	ug/m3	3.6	0.74	1.46		09/15/21 20:39	67-63-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - BACKGROUND **Lab ID: 10578413006** Collected: 09/08/21 09:21 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
Propylene	**<0.19**	ug/m3	1.3	0.19	1.46		09/15/21 20:39	115-07-1	
Styrene	**<0.56**	ug/m3	1.3	0.56	1.46		09/15/21 20:39	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.54**	ug/m3	2.0	0.54	1.46		09/15/21 20:39	79-34-5	
Tetrachloroethene	**<0.43**	ug/m3	1.0	0.43	1.46		09/15/21 20:39	127-18-4	
Tetrahydrofuran	**<0.26**	ug/m3	0.88	0.26	1.46		09/15/21 20:39	109-99-9	
Toluene	**0.71J**	ug/m3	1.1	0.36	1.46		09/15/21 20:39	108-88-3	
1,2,4-Trichlorobenzene	**<7.1**	ug/m3	11.0	7.1	1.46		09/15/21 20:39	120-82-1	
1,1,1-Trichloroethane	**<0.27**	ug/m3	1.6	0.27	1.46		09/15/21 20:39	71-55-6	
1,1,2-Trichloroethane	**<0.29**	ug/m3	0.81	0.29	1.46		09/15/21 20:39	79-00-5	
Trichloroethene	**<0.29**	ug/m3	1.6	0.29	1.46		09/15/21 20:39	79-01-6	
Trichlorofluoromethane	**1.3J**	ug/m3	1.7	0.34	1.46		09/15/21 20:39	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.81J**	ug/m3	2.3	0.42	1.46		09/15/21 20:39	76-13-1	
1,2,4-Trimethylbenzene	**<0.52**	ug/m3	1.5	0.52	1.46		09/15/21 20:39	95-63-6	
1,3,5-Trimethylbenzene	**<0.42**	ug/m3	1.5	0.42	1.46		09/15/21 20:39	108-67-8	
Vinyl acetate	**<0.30**	ug/m3	1.0	0.30	1.46		09/15/21 20:39	108-05-4	
Vinyl chloride	**<0.13**	ug/m3	0.38	0.13	1.46		09/15/21 20:39	75-01-4	
m&p-Xylene	**<0.94**	ug/m3	2.6	0.94	1.46		09/15/21 20:39	179601-23-1	
o-Xylene	**<0.40**	ug/m3	1.3	0.40	1.46		09/15/21 20:39	95-47-6	

Sample: BUILDING N - NORTH - 1 SS **Lab ID: 10578413007** Collected: 09/08/21 12:15 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
Acetone	**4.5J**	ug/m3	8.4	2.5	1.39		09/15/21 17:34	67-64-1	
Benzene	**<0.16**	ug/m3	0.45	0.16	1.39		09/15/21 17:34	71-43-2	
Benzyl chloride	**<1.2**	ug/m3	3.7	1.2	1.39		09/15/21 17:34	100-44-7	
Bromodichloromethane	**3.4**	ug/m3	1.9	0.33	1.39		09/15/21 17:34	75-27-4	
Bromoform	**<2.3**	ug/m3	7.3	2.3	1.39		09/15/21 17:34	75-25-2	
Bromomethane	**<0.21**	ug/m3	1.1	0.21	1.39		09/15/21 17:34	74-83-9	
1,3-Butadiene	**<0.17**	ug/m3	0.63	0.17	1.39		09/15/21 17:34	106-99-0	
2-Butanone (MEK)	**1.3J**	ug/m3	4.2	0.65	1.39		09/15/21 17:34	78-93-3	
Carbon disulfide	**0.58J**	ug/m3	0.88	0.18	1.39		09/15/21 17:34	75-15-0	
Carbon tetrachloride	**9.1**	ug/m3	1.8	0.39	1.39		09/15/21 17:34	56-23-5	
Chlorobenzene	**<0.22**	ug/m3	1.3	0.22	1.39		09/15/21 17:34	108-90-7	
Chloroethane	**<0.31**	ug/m3	0.75	0.31	1.39		09/15/21 17:34	75-00-3	
Chloroform	**146**	ug/m3	0.69	0.25	1.39		09/15/21 17:34	67-66-3	
Chloromethane	**<0.12**	ug/m3	0.58	0.12	1.39		09/15/21 17:34	74-87-3	
Cyclohexane	**1.2J**	ug/m3	2.4	0.31	1.39		09/15/21 17:34	110-82-7	
Dibromochloromethane	**<0.72**	ug/m3	2.4	0.72	1.39		09/15/21 17:34	124-48-1	
1,2-Dibromoethane (EDB)	**<0.42**	ug/m3	1.1	0.42	1.39		09/15/21 17:34	106-93-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH - 1 SS **Lab ID: 10578413007** Collected: 09/08/21 12:15 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
1,2-Dichlorobenzene	**<0.56**	ug/m3	4.3	0.56	1.39		09/15/21 17:34	95-50-1	
1,3-Dichlorobenzene	**<0.71**	ug/m3	4.3	0.71	1.39		09/15/21 17:34	541-73-1	
1,4-Dichlorobenzene	**<1.2**	ug/m3	4.3	1.2	1.39		09/15/21 17:34	106-46-7	
Dichlorodifluoromethane	**2.3**	ug/m3	1.4	0.26	1.39		09/15/21 17:34	75-71-8	
1,1-Dichloroethane	**<0.23**	ug/m3	1.1	0.23	1.39		09/15/21 17:34	75-34-3	
1,2-Dichloroethane	**<0.27**	ug/m3	1.1	0.27	1.39		09/15/21 17:34	107-06-2	
1,1-Dichloroethene	**<0.19**	ug/m3	1.1	0.19	1.39		09/15/21 17:34	75-35-4	
cis-1,2-Dichloroethene	**8.4**	ug/m3	1.1	0.27	1.39		09/15/21 17:34	156-59-2	
trans-1,2-Dichloroethene	**4.4**	ug/m3	1.1	0.23	1.39		09/15/21 17:34	156-60-5	
1,2-Dichloropropane	**<0.37**	ug/m3	1.3	0.37	1.39		09/15/21 17:34	78-87-5	
cis-1,3-Dichloropropene	**<0.35**	ug/m3	3.2	0.35	1.39		09/15/21 17:34	10061-01-5	
trans-1,3-Dichloropropene	**<0.76**	ug/m3	3.2	0.76	1.39		09/15/21 17:34	10061-02-6	
Dichlorotetrafluoroethane	**<0.28**	ug/m3	2.0	0.28	1.39		09/15/21 17:34	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.0**	ug/m3	10.2	1.0	1.39		09/15/21 17:34	123-91-1	
Ethanol	**30.6**	ug/m3	2.7	0.82	1.39		09/15/21 17:34	64-17-5	
Ethyl acetate	**<0.18**	ug/m3	1.0	0.18	1.39		09/15/21 17:34	141-78-6	
Ethylbenzene	**0.50J**	ug/m3	1.2	0.43	1.39		09/15/21 17:34	100-41-4	
4-Ethyltoluene	**0.89J**	ug/m3	3.5	0.66	1.39		09/15/21 17:34	622-96-8	
n-Heptane	**<0.25**	ug/m3	1.2	0.25	1.39		09/15/21 17:34	142-82-5	
Hexachloro-1,3-butadiene	**<1.7**	ug/m3	7.5	1.7	1.39		09/15/21 17:34	87-68-3	
n-Hexane	**0.63J**	ug/m3	1.0	0.27	1.39		09/15/21 17:34	110-54-3	
2-Hexanone	**<0.61**	ug/m3	5.8	0.61	1.39		09/15/21 17:34	591-78-6	
Methylene Chloride	**<0.82**	ug/m3	4.9	0.82	1.39		09/15/21 17:34	75-09-2	
4-Methyl-2-pentanone (MIBK)	**<0.45**	ug/m3	5.8	0.45	1.39		09/15/21 17:34	108-10-1	
Methyl-tert-butyl ether	**<0.18**	ug/m3	5.1	0.18	1.39		09/15/21 17:34	1634-04-4	
Naphthalene	**<3.0**	ug/m3	3.7	3.0	1.39		09/15/21 17:34	91-20-3	
2-Propanol	**<0.71**	ug/m3	3.5	0.71	1.39		09/15/21 17:34	67-63-0	
Propylene	**<0.18**	ug/m3	1.2	0.18	1.39		09/15/21 17:34	115-07-1	
Styrene	**1.1J**	ug/m3	1.2	0.54	1.39		09/15/21 17:34	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.52**	ug/m3	1.9	0.52	1.39		09/15/21 17:34	79-34-5	
Tetrachloroethene	**<0.41**	ug/m3	0.96	0.41	1.39		09/15/21 17:34	127-18-4	
Tetrahydrofuran	**<0.25**	ug/m3	0.83	0.25	1.39		09/15/21 17:34	109-99-9	
Toluene	**1.3**	ug/m3	1.1	0.34	1.39		09/15/21 17:34	108-88-3	
1,2,4-Trichlorobenzene	**<6.8**	ug/m3	10.5	6.8	1.39		09/15/21 17:34	120-82-1	
1,1,1-Trichloroethane	**<0.26**	ug/m3	1.5	0.26	1.39		09/15/21 17:34	71-55-6	
1,1,2-Trichloroethane	**<0.27**	ug/m3	0.77	0.27	1.39		09/15/21 17:34	79-00-5	
Trichloroethene	**127**	ug/m3	0.76	0.27	1.39		09/15/21 17:34	79-01-6	
Trichlorofluoromethane	**1.5J**	ug/m3	1.6	0.32	1.39		09/15/21 17:34	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.44J**	ug/m3	2.2	0.40	1.39		09/15/21 17:34	76-13-1	
1,2,4-Trimethylbenzene	**3.7**	ug/m3	1.4	0.49	1.39		09/15/21 17:34	95-63-6	
1,3,5-Trimethylbenzene	**0.98J**	ug/m3	1.4	0.40	1.39		09/15/21 17:34	108-67-8	
Vinyl acetate	**<0.29**	ug/m3	1.0	0.29	1.39		09/15/21 17:34	108-05-4	
Vinyl chloride	**<0.12**	ug/m3	0.36	0.12	1.39		09/15/21 17:34	75-01-4	
m&p-Xylene	**1.8J**	ug/m3	2.5	0.89	1.39		09/15/21 17:34	179601-23-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH - 1 SS **Lab ID: 10578413007** Collected: 09/08/21 12:15 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
o-Xylene	**1.1J**	ug/m3	1.2	0.38	1.39		09/15/21 17:34	95-47-6	

Sample: BUILDING N - NORTH - 3 SS **Lab ID: 10578413008** Collected: 09/08/21 13:15 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Acetone	**7.8J**	ug/m3	8.4	2.5	1.39		09/15/21 18:31	67-64-1	
Benzene	**0.25J**	ug/m3	0.45	0.16	1.39		09/15/21 18:31	71-43-2	
Benzyl chloride	**<1.2**	ug/m3	3.7	1.2	1.39		09/15/21 18:31	100-44-7	
Bromodichloromethane	**<0.33**	ug/m3	1.9	0.33	1.39		09/15/21 18:31	75-27-4	
Bromoform	**<2.3**	ug/m3	7.3	2.3	1.39		09/15/21 18:31	75-25-2	
Bromomethane	**<0.21**	ug/m3	1.1	0.21	1.39		09/15/21 18:31	74-83-9	
1,3-Butadiene	**<0.17**	ug/m3	0.63	0.17	1.39		09/15/21 18:31	106-99-0	
2-Butanone (MEK)	**2.2J**	ug/m3	4.2	0.65	1.39		09/15/21 18:31	78-93-3	
Carbon disulfide	**1.3**	ug/m3	0.88	0.18	1.39		09/15/21 18:31	75-15-0	
Carbon tetrachloride	**0.44J**	ug/m3	1.8	0.39	1.39		09/15/21 18:31	56-23-5	
Chlorobenzene	**<0.22**	ug/m3	1.3	0.22	1.39		09/15/21 18:31	108-90-7	
Chloroethane	**<0.31**	ug/m3	0.75	0.31	1.39		09/15/21 18:31	75-00-3	
Chloroform	**15.6**	ug/m3	0.69	0.25	1.39		09/15/21 18:31	67-66-3	
Chloromethane	**<0.12**	ug/m3	0.58	0.12	1.39		09/15/21 18:31	74-87-3	
Cyclohexane	**0.44J**	ug/m3	2.4	0.31	1.39		09/15/21 18:31	110-82-7	
Dibromochloromethane	**<0.72**	ug/m3	2.4	0.72	1.39		09/15/21 18:31	124-48-1	
1,2-Dibromoethane (EDB)	**<0.42**	ug/m3	1.1	0.42	1.39		09/15/21 18:31	106-93-4	
1,2-Dichlorobenzene	**<0.56**	ug/m3	4.3	0.56	1.39		09/15/21 18:31	95-50-1	
1,3-Dichlorobenzene	**<0.71**	ug/m3	4.3	0.71	1.39		09/15/21 18:31	541-73-1	
1,4-Dichlorobenzene	**1.3J**	ug/m3	4.3	1.2	1.39		09/15/21 18:31	106-46-7	
Dichlorodifluoromethane	**2.2**	ug/m3	1.4	0.26	1.39		09/15/21 18:31	75-71-8	
1,1-Dichloroethane	**<0.23**	ug/m3	1.1	0.23	1.39		09/15/21 18:31	75-34-3	
1,2-Dichloroethane	**<0.27**	ug/m3	1.1	0.27	1.39		09/15/21 18:31	107-06-2	
1,1-Dichloroethene	**<0.19**	ug/m3	1.1	0.19	1.39		09/15/21 18:31	75-35-4	
cis-1,2-Dichloroethene	**<0.27**	ug/m3	1.1	0.27	1.39		09/15/21 18:31	156-59-2	
trans-1,2-Dichloroethene	**<0.23**	ug/m3	1.1	0.23	1.39		09/15/21 18:31	156-60-5	
1,2-Dichloropropane	**<0.37**	ug/m3	1.3	0.37	1.39		09/15/21 18:31	78-87-5	
cis-1,3-Dichloropropene	**<0.35**	ug/m3	3.2	0.35	1.39		09/15/21 18:31	10061-01-5	
trans-1,3-Dichloropropene	**<0.76**	ug/m3	3.2	0.76	1.39		09/15/21 18:31	10061-02-6	
Dichlorotetrafluoroethane	**<0.28**	ug/m3	2.0	0.28	1.39		09/15/21 18:31	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.0**	ug/m3	10.2	1.0	1.39		09/15/21 18:31	123-91-1	
Ethanol	**32.6**	ug/m3	2.7	0.82	1.39		09/15/21 18:31	64-17-5	
Ethyl acetate	**<0.18**	ug/m3	1.0	0.18	1.39		09/15/21 18:31	141-78-6	
Ethylbenzene	**0.76J**	ug/m3	1.2	0.43	1.39		09/15/21 18:31	100-41-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - NORTH - 3 SS **Lab ID: 10578413008** Collected: 09/08/21 13:15 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
4-Ethyltoluene	**1.2J**	ug/m3	3.5	0.66	1.39		09/15/21 18:31	622-96-8	
n-Heptane	**0.36J**	ug/m3	1.2	0.25	1.39		09/15/21 18:31	142-82-5	
Hexachloro-1,3-butadiene	**<1.7**	ug/m3	7.5	1.7	1.39		09/15/21 18:31	87-68-3	
n-Hexane	**0.70J**	ug/m3	1.0	0.27	1.39		09/15/21 18:31	110-54-3	
2-Hexanone	**0.81J**	ug/m3	5.8	0.61	1.39		09/15/21 18:31	591-78-6	
Methylene Chloride	**<0.82**	ug/m3	4.9	0.82	1.39		09/15/21 18:31	75-09-2	
4-Methyl-2-pentanone (MIBK)	**<0.45**	ug/m3	5.8	0.45	1.39		09/15/21 18:31	108-10-1	
Methyl-tert-butyl ether	**<0.18**	ug/m3	5.1	0.18	1.39		09/15/21 18:31	1634-04-4	
Naphthalene	**3.3J**	ug/m3	3.7	3.0	1.39		09/15/21 18:31	91-20-3	
2-Propanol	**1.6J**	ug/m3	3.5	0.71	1.39		09/15/21 18:31	67-63-0	
Propylene	**<0.18**	ug/m3	1.2	0.18	1.39		09/15/21 18:31	115-07-1	
Styrene	**1.5**	ug/m3	1.2	0.54	1.39		09/15/21 18:31	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.52**	ug/m3	1.9	0.52	1.39		09/15/21 18:31	79-34-5	
Tetrachloroethene	**<0.41**	ug/m3	0.96	0.41	1.39		09/15/21 18:31	127-18-4	
Tetrahydrofuran	**1.8**	ug/m3	0.83	0.25	1.39		09/15/21 18:31	109-99-9	
Toluene	**1.4**	ug/m3	1.1	0.34	1.39		09/15/21 18:31	108-88-3	
1,2,4-Trichlorobenzene	**<6.8**	ug/m3	10.5	6.8	1.39		09/15/21 18:31	120-82-1	
1,1,1-Trichloroethane	**<0.26**	ug/m3	1.5	0.26	1.39		09/15/21 18:31	71-55-6	
1,1,2-Trichloroethane	**<0.27**	ug/m3	0.77	0.27	1.39		09/15/21 18:31	79-00-5	
Trichloroethene	**1.9**	ug/m3	0.76	0.27	1.39		09/15/21 18:31	79-01-6	
Trichlorofluoromethane	**1.2J**	ug/m3	1.6	0.32	1.39		09/15/21 18:31	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.65J**	ug/m3	2.2	0.40	1.39		09/15/21 18:31	76-13-1	
1,2,4-Trimethylbenzene	**5.3**	ug/m3	1.4	0.49	1.39		09/15/21 18:31	95-63-6	
1,3,5-Trimethylbenzene	**1.4J**	ug/m3	1.4	0.40	1.39		09/15/21 18:31	108-67-8	
Vinyl acetate	**<0.29**	ug/m3	1.0	0.29	1.39		09/15/21 18:31	108-05-4	
Vinyl chloride	**<0.12**	ug/m3	0.36	0.12	1.39		09/15/21 18:31	75-01-4	
m&p-Xylene	**2.7**	ug/m3	2.5	0.89	1.39		09/15/21 18:31	179601-23-1	
o-Xylene	**1.5**	ug/m3	1.2	0.38	1.39		09/15/21 18:31	95-47-6	

Sample: BUILDING N - SOUTH - 1 SS **Lab ID: 10578413009** Collected: 09/08/21 13:41 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
Acetone	**377**	ug/m3	8.4	2.5	1.39		09/15/21 19:28	67-64-1	
Benzene	**2.7**	ug/m3	0.45	0.16	1.39		09/15/21 19:28	71-43-2	
Benzyl chloride	**<1.2**	ug/m3	3.7	1.2	1.39		09/15/21 19:28	100-44-7	
Bromodichloromethane	**1.7J**	ug/m3	1.9	0.33	1.39		09/15/21 19:28	75-27-4	
Bromoform	**<2.3**	ug/m3	7.3	2.3	1.39		09/15/21 19:28	75-25-2	
Bromomethane	**<0.21**	ug/m3	1.1	0.21	1.39		09/15/21 19:28	74-83-9	
1,3-Butadiene	**<0.17**	ug/m3	0.63	0.17	1.39		09/15/21 19:28	106-99-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH - 1 SS **Lab ID: 10578413009** Collected: 09/08/21 13:41 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
2-Butanone (MEK)	**16.4**	ug/m3	4.2	0.65	1.39		09/15/21 19:28	78-93-3	
Carbon disulfide	**0.86J**	ug/m3	0.88	0.18	1.39		09/15/21 19:28	75-15-0	
Carbon tetrachloride	**3.6**	ug/m3	1.8	0.39	1.39		09/15/21 19:28	56-23-5	
Chlorobenzene	**<0.22**	ug/m3	1.3	0.22	1.39		09/15/21 19:28	108-90-7	
Chloroethane	**0.86**	ug/m3	0.75	0.31	1.39		09/15/21 19:28	75-00-3	
Chloroform	**2040**	ug/m3	20.7	7.6	41.7		09/16/21 10:33	67-66-3	
Chloromethane	**0.80**	ug/m3	0.58	0.12	1.39		09/15/21 19:28	74-87-3	
Cyclohexane	**<0.31**	ug/m3	2.4	0.31	1.39		09/15/21 19:28	110-82-7	
Dibromochloromethane	**0.93J**	ug/m3	2.4	0.72	1.39		09/15/21 19:28	124-48-1	
1,2-Dibromoethane (EDB)	**<0.42**	ug/m3	1.1	0.42	1.39		09/15/21 19:28	106-93-4	
1,2-Dichlorobenzene	**<0.56**	ug/m3	4.3	0.56	1.39		09/15/21 19:28	95-50-1	
1,3-Dichlorobenzene	**<0.71**	ug/m3	4.3	0.71	1.39		09/15/21 19:28	541-73-1	
1,4-Dichlorobenzene	**<1.2**	ug/m3	4.3	1.2	1.39		09/15/21 19:28	106-46-7	
Dichlorodifluoromethane	**1.9**	ug/m3	1.4	0.26	1.39		09/15/21 19:28	75-71-8	
1,1-Dichloroethane	**0.72J**	ug/m3	1.1	0.23	1.39		09/15/21 19:28	75-34-3	
1,2-Dichloroethane	**<0.27**	ug/m3	1.1	0.27	1.39		09/15/21 19:28	107-06-2	
1,1-Dichloroethene	**<0.19**	ug/m3	1.1	0.19	1.39		09/15/21 19:28	75-35-4	
cis-1,2-Dichloroethene	**0.85J**	ug/m3	1.1	0.27	1.39		09/15/21 19:28	156-59-2	
trans-1,2-Dichloroethene	**<0.23**	ug/m3	1.1	0.23	1.39		09/15/21 19:28	156-60-5	
1,2-Dichloropropane	**<0.37**	ug/m3	1.3	0.37	1.39		09/15/21 19:28	78-87-5	
cis-1,3-Dichloropropene	**<0.35**	ug/m3	3.2	0.35	1.39		09/15/21 19:28	10061-01-5	
trans-1,3-Dichloropropene	**<0.76**	ug/m3	3.2	0.76	1.39		09/15/21 19:28	10061-02-6	
Dichlorotetrafluoroethane	**<0.28**	ug/m3	2.0	0.28	1.39		09/15/21 19:28	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.0**	ug/m3	10.2	1.0	1.39		09/15/21 19:28	123-91-1	
Ethanol	**2190**	ug/m3	80.1	24.7	41.7		09/16/21 10:33	64-17-5	
Ethyl acetate	**<0.18**	ug/m3	1.0	0.18	1.39		09/15/21 19:28	141-78-6	
Ethylbenzene	**1.6**	ug/m3	1.2	0.43	1.39		09/15/21 19:28	100-41-4	
4-Ethyltoluene	**0.95J**	ug/m3	3.5	0.66	1.39		09/15/21 19:28	622-96-8	
n-Heptane	**6.4**	ug/m3	1.2	0.25	1.39		09/15/21 19:28	142-82-5	
Hexachloro-1,3-butadiene	**<1.7**	ug/m3	7.5	1.7	1.39		09/15/21 19:28	87-68-3	
n-Hexane	**6.2**	ug/m3	1.0	0.27	1.39		09/15/21 19:28	110-54-3	
2-Hexanone	**7.9**	ug/m3	5.8	0.61	1.39		09/15/21 19:28	591-78-6	
Methylene Chloride	**1.2J**	ug/m3	4.9	0.82	1.39		09/15/21 19:28	75-09-2	
4-Methyl-2-pentanone (MIBK)	**45.8**	ug/m3	5.8	0.45	1.39		09/15/21 19:28	108-10-1	
Methyl-tert-butyl ether	**<0.18**	ug/m3	5.1	0.18	1.39		09/15/21 19:28	1634-04-4	
Naphthalene	**<3.0**	ug/m3	3.7	3.0	1.39		09/15/21 19:28	91-20-3	
2-Propanol	**476**	ug/m3	3.5	0.71	1.39		09/15/21 19:28	67-63-0	
Propylene	**<0.18**	ug/m3	1.2	0.18	1.39		09/15/21 19:28	115-07-1	
Styrene	**2.0**	ug/m3	1.2	0.54	1.39		09/15/21 19:28	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.52**	ug/m3	1.9	0.52	1.39		09/15/21 19:28	79-34-5	
Tetrachloroethene	**<0.41**	ug/m3	0.96	0.41	1.39		09/15/21 19:28	127-18-4	
Tetrahydrofuran	**1020**	ug/m3	25.0	7.5	41.7		09/16/21 10:33	109-99-9	
Toluene	**2.2**	ug/m3	1.1	0.34	1.39		09/15/21 19:28	108-88-3	
1,2,4-Trichlorobenzene	**<6.8**	ug/m3	10.5	6.8	1.39		09/15/21 19:28	120-82-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH - 1 SS **Lab ID: 10578413009** Collected: 09/08/21 13:41 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
1,1,1-Trichloroethane	**<0.26**	ug/m3	1.5	0.26	1.39		09/15/21 19:28	71-55-6	
1,1,2-Trichloroethane	**<0.27**	ug/m3	0.77	0.27	1.39		09/15/21 19:28	79-00-5	
Trichloroethene	**4.4**	ug/m3	0.76	0.27	1.39		09/15/21 19:28	79-01-6	
Trichlorofluoromethane	**1.0J**	ug/m3	1.6	0.32	1.39		09/15/21 19:28	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.40J**	ug/m3	2.2	0.40	1.39		09/15/21 19:28	76-13-1	
1,2,4-Trimethylbenzene	**2.7**	ug/m3	1.4	0.49	1.39		09/15/21 19:28	95-63-6	
1,3,5-Trimethylbenzene	**0.88J**	ug/m3	1.4	0.40	1.39		09/15/21 19:28	108-67-8	
Vinyl acetate	**<0.29**	ug/m3	1.0	0.29	1.39		09/15/21 19:28	108-05-4	
Vinyl chloride	**<0.12**	ug/m3	0.36	0.12	1.39		09/15/21 19:28	75-01-4	
m&p-Xylene	**5.8**	ug/m3	2.5	0.89	1.39		09/15/21 19:28	179601-23-1	
o-Xylene	**2.7**	ug/m3	1.2	0.38	1.39		09/15/21 19:28	95-47-6	

Sample: BUILDING N - SOUTH - 2 SS **Lab ID: 10578413010** Collected: 09/08/21 14:07 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Acetone	**31.1**	ug/m3	8.4	2.5	1.39		09/15/21 19:57	67-64-1	
Benzene	**0.87**	ug/m3	0.45	0.16	1.39		09/15/21 19:57	71-43-2	
Benzyl chloride	**<1.2**	ug/m3	3.7	1.2	1.39		09/15/21 19:57	100-44-7	
Bromodichloromethane	**<0.33**	ug/m3	1.9	0.33	1.39		09/15/21 19:57	75-27-4	
Bromoform	**<2.3**	ug/m3	7.3	2.3	1.39		09/15/21 19:57	75-25-2	
Bromomethane	**<0.21**	ug/m3	1.1	0.21	1.39		09/15/21 19:57	74-83-9	
1,3-Butadiene	**<0.17**	ug/m3	0.63	0.17	1.39		09/15/21 19:57	106-99-0	
2-Butanone (MEK)	**3.4J**	ug/m3	4.2	0.65	1.39		09/15/21 19:57	78-93-3	
Carbon disulfide	**1.0**	ug/m3	0.88	0.18	1.39		09/15/21 19:57	75-15-0	
Carbon tetrachloride	**<0.39**	ug/m3	1.8	0.39	1.39		09/15/21 19:57	56-23-5	
Chlorobenzene	**<0.22**	ug/m3	1.3	0.22	1.39		09/15/21 19:57	108-90-7	
Chloroethane	**<0.31**	ug/m3	0.75	0.31	1.39		09/15/21 19:57	75-00-3	
Chloroform	**2.7**	ug/m3	0.69	0.25	1.39		09/15/21 19:57	67-66-3	
Chloromethane	**<0.12**	ug/m3	0.58	0.12	1.39		09/15/21 19:57	74-87-3	
Cyclohexane	**0.70J**	ug/m3	2.4	0.31	1.39		09/15/21 19:57	110-82-7	
Dibromochloromethane	**<0.72**	ug/m3	2.4	0.72	1.39		09/15/21 19:57	124-48-1	
1,2-Dibromoethane (EDB)	**<0.42**	ug/m3	1.1	0.42	1.39		09/15/21 19:57	106-93-4	
1,2-Dichlorobenzene	**<0.56**	ug/m3	4.3	0.56	1.39		09/15/21 19:57	95-50-1	
1,3-Dichlorobenzene	**<0.71**	ug/m3	4.3	0.71	1.39		09/15/21 19:57	541-73-1	
1,4-Dichlorobenzene	**<1.2**	ug/m3	4.3	1.2	1.39		09/15/21 19:57	106-46-7	
Dichlorodifluoromethane	**<0.26**	ug/m3	1.4	0.26	1.39		09/15/21 19:57	75-71-8	
1,1-Dichloroethane	**<0.23**	ug/m3	1.1	0.23	1.39		09/15/21 19:57	75-34-3	
1,2-Dichloroethane	**<0.27**	ug/m3	1.1	0.27	1.39		09/15/21 19:57	107-06-2	
1,1-Dichloroethene	**<0.19**	ug/m3	1.1	0.19	1.39		09/15/21 19:57	75-35-4	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH - 2 SS **Lab ID: 10578413010** Collected: 09/08/21 14:07 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
cis-1,2-Dichloroethene	**2.8**	ug/m3	1.1	0.27	1.39		09/15/21 19:57	156-59-2	
trans-1,2-Dichloroethene	**0.96J**	ug/m3	1.1	0.23	1.39		09/15/21 19:57	156-60-5	
1,2-Dichloropropane	**<0.37**	ug/m3	1.3	0.37	1.39		09/15/21 19:57	78-87-5	
cis-1,3-Dichloropropene	**<0.35**	ug/m3	3.2	0.35	1.39		09/15/21 19:57	10061-01-5	
trans-1,3-Dichloropropene	**<0.76**	ug/m3	3.2	0.76	1.39		09/15/21 19:57	10061-02-6	
Dichlorotetrafluoroethane	**<0.28**	ug/m3	2.0	0.28	1.39		09/15/21 19:57	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.0**	ug/m3	10.2	1.0	1.39		09/15/21 19:57	123-91-1	
Ethanol	**205**	ug/m3	2.7	0.82	1.39		09/15/21 19:57	64-17-5	
Ethyl acetate	**<0.18**	ug/m3	1.0	0.18	1.39		09/15/21 19:57	141-78-6	
Ethylbenzene	**2.0**	ug/m3	1.2	0.43	1.39		09/15/21 19:57	100-41-4	
4-Ethyltoluene	**1.2J**	ug/m3	3.5	0.66	1.39		09/15/21 19:57	622-96-8	
n-Heptane	**1.1J**	ug/m3	1.2	0.25	1.39		09/15/21 19:57	142-82-5	
Hexachloro-1,3-butadiene	**<1.7**	ug/m3	7.5	1.7	1.39		09/15/21 19:57	87-68-3	
n-Hexane	**0.91J**	ug/m3	1.0	0.27	1.39		09/15/21 19:57	110-54-3	
2-Hexanone	**<0.61**	ug/m3	5.8	0.61	1.39		09/15/21 19:57	591-78-6	
Methylene Chloride	**<0.82**	ug/m3	4.9	0.82	1.39		09/15/21 19:57	75-09-2	
4-Methyl-2-pentanone (MIBK)	**0.46J**	ug/m3	5.8	0.45	1.39		09/15/21 19:57	108-10-1	
Methyl-tert-butyl ether	**<0.18**	ug/m3	5.1	0.18	1.39		09/15/21 19:57	1634-04-4	
Naphthalene	**<3.0**	ug/m3	3.7	3.0	1.39		09/15/21 19:57	91-20-3	
2-Propanol	**16.9**	ug/m3	3.5	0.71	1.39		09/15/21 19:57	67-63-0	
Propylene	**<0.18**	ug/m3	1.2	0.18	1.39		09/15/21 19:57	115-07-1	
Styrene	**1.3**	ug/m3	1.2	0.54	1.39		09/15/21 19:57	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.52**	ug/m3	1.9	0.52	1.39		09/15/21 19:57	79-34-5	
Tetrachloroethene	**14.8**	ug/m3	0.96	0.41	1.39		09/15/21 19:57	127-18-4	
Tetrahydrofuran	**1.8**	ug/m3	0.83	0.25	1.39		09/15/21 19:57	109-99-9	
Toluene	**3.6**	ug/m3	1.1	0.34	1.39		09/15/21 19:57	108-88-3	
1,2,4-Trichlorobenzene	**<6.8**	ug/m3	10.5	6.8	1.39		09/15/21 19:57	120-82-1	
1,1,1-Trichloroethane	**<0.26**	ug/m3	1.5	0.26	1.39		09/15/21 19:57	71-55-6	
1,1,2-Trichloroethane	**<0.27**	ug/m3	0.77	0.27	1.39		09/15/21 19:57	79-00-5	
Trichloroethene	**40.0**	ug/m3	0.76	0.27	1.39		09/15/21 19:57	79-01-6	
Trichlorofluoromethane	**1.1J**	ug/m3	1.6	0.32	1.39		09/15/21 19:57	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.99J**	ug/m3	2.2	0.40	1.39		09/15/21 19:57	76-13-1	
1,2,4-Trimethylbenzene	**5.4**	ug/m3	1.4	0.49	1.39		09/15/21 19:57	95-63-6	
1,3,5-Trimethylbenzene	**1.4**	ug/m3	1.4	0.40	1.39		09/15/21 19:57	108-67-8	
Vinyl acetate	**<0.29**	ug/m3	1.0	0.29	1.39		09/15/21 19:57	108-05-4	
Vinyl chloride	**<0.12**	ug/m3	0.36	0.12	1.39		09/15/21 19:57	75-01-4	
m&p-Xylene	**4.8**	ug/m3	2.5	0.89	1.39		09/15/21 19:57	179601-23-1	
o-Xylene	**2.2**	ug/m3	1.2	0.38	1.39		09/15/21 19:57	95-47-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH - 3 SS **Lab ID: 10578413011** Collected: 09/08/21 14:32 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15 Pace Analytical Services - Minneapolis								
Acetone	**36.2**	ug/m3	8.7	2.6	1.44		09/15/21 20:25	67-64-1	
Benzene	**0.58**	ug/m3	0.47	0.16	1.44		09/15/21 20:25	71-43-2	
Benzyl chloride	**<1.3**	ug/m3	3.8	1.3	1.44		09/15/21 20:25	100-44-7	
Bromodichloromethane	**<0.34**	ug/m3	2.0	0.34	1.44		09/15/21 20:25	75-27-4	
Bromoform	**<2.3**	ug/m3	7.6	2.3	1.44		09/15/21 20:25	75-25-2	
Bromomethane	**<0.22**	ug/m3	1.1	0.22	1.44		09/15/21 20:25	74-83-9	
1,3-Butadiene	**<0.17**	ug/m3	0.65	0.17	1.44		09/15/21 20:25	106-99-0	
2-Butanone (MEK)	**7.3**	ug/m3	4.3	0.67	1.44		09/15/21 20:25	78-93-3	
Carbon disulfide	**0.44J**	ug/m3	0.91	0.19	1.44		09/15/21 20:25	75-15-0	
Carbon tetrachloride	**<0.40**	ug/m3	1.8	0.40	1.44		09/15/21 20:25	56-23-5	
Chlorobenzene	**<0.22**	ug/m3	1.3	0.22	1.44		09/15/21 20:25	108-90-7	
Chloroethane	**<0.32**	ug/m3	0.77	0.32	1.44		09/15/21 20:25	75-00-3	
Chloroform	**1.6**	ug/m3	0.71	0.26	1.44		09/15/21 20:25	67-66-3	
Chloromethane	**0.16J**	ug/m3	0.60	0.12	1.44		09/15/21 20:25	74-87-3	
Cyclohexane	**0.81J**	ug/m3	2.5	0.32	1.44		09/15/21 20:25	110-82-7	
Dibromochloromethane	**<0.74**	ug/m3	2.5	0.74	1.44		09/15/21 20:25	124-48-1	
1,2-Dibromoethane (EDB)	**<0.43**	ug/m3	1.1	0.43	1.44		09/15/21 20:25	106-93-4	
1,2-Dichlorobenzene	**<0.58**	ug/m3	4.4	0.58	1.44		09/15/21 20:25	95-50-1	
1,3-Dichlorobenzene	**1.4J**	ug/m3	4.4	0.73	1.44		09/15/21 20:25	541-73-1	
1,4-Dichlorobenzene	**<1.3**	ug/m3	4.4	1.3	1.44		09/15/21 20:25	106-46-7	
Dichlorodifluoromethane	**2.0**	ug/m3	1.5	0.27	1.44		09/15/21 20:25	75-71-8	
1,1-Dichloroethane	**<0.24**	ug/m3	1.2	0.24	1.44		09/15/21 20:25	75-34-3	
1,2-Dichloroethane	**<0.28**	ug/m3	1.2	0.28	1.44		09/15/21 20:25	107-06-2	
1,1-Dichloroethene	**<0.20**	ug/m3	1.2	0.20	1.44		09/15/21 20:25	75-35-4	
cis-1,2-Dichloroethene	**4.6**	ug/m3	1.2	0.28	1.44		09/15/21 20:25	156-59-2	
trans-1,2-Dichloroethene	**1.2J**	ug/m3	1.2	0.24	1.44		09/15/21 20:25	156-60-5	
1,2-Dichloropropane	**<0.39**	ug/m3	1.4	0.39	1.44		09/15/21 20:25	78-87-5	
cis-1,3-Dichloropropene	**<0.37**	ug/m3	3.3	0.37	1.44		09/15/21 20:25	10061-01-5	
trans-1,3-Dichloropropene	**<0.78**	ug/m3	3.3	0.78	1.44		09/15/21 20:25	10061-02-6	
Dichlorotetrafluoroethane	**<0.29**	ug/m3	2.0	0.29	1.44		09/15/21 20:25	76-14-2	
1,4-Dioxane (p-Dioxane)	**<1.1**	ug/m3	10.6	1.1	1.44		09/15/21 20:25	123-91-1	
Ethanol	**195**	ug/m3	2.8	0.85	1.44		09/15/21 20:25	64-17-5	
Ethyl acetate	**2.0**	ug/m3	1.1	0.19	1.44		09/15/21 20:25	141-78-6	
Ethylbenzene	**1.3**	ug/m3	1.3	0.44	1.44		09/15/21 20:25	100-41-4	
4-Ethyltoluene	**1.5J**	ug/m3	3.6	0.68	1.44		09/15/21 20:25	622-96-8	
n-Heptane	**0.83J**	ug/m3	1.2	0.26	1.44		09/15/21 20:25	142-82-5	
Hexachloro-1,3-butadiene	**<1.8**	ug/m3	7.8	1.8	1.44		09/15/21 20:25	87-68-3	
n-Hexane	**0.68J**	ug/m3	1.0	0.28	1.44		09/15/21 20:25	110-54-3	
2-Hexanone	**2.0J**	ug/m3	6.0	0.64	1.44		09/15/21 20:25	591-78-6	
Methylene Chloride	**<0.85**	ug/m3	5.1	0.85	1.44		09/15/21 20:25	75-09-2	
4-Methyl-2-pentanone (MIBK)	**1.7J**	ug/m3	6.0	0.46	1.44		09/15/21 20:25	108-10-1	
Methyl-tert-butyl ether	**<0.18**	ug/m3	5.3	0.18	1.44		09/15/21 20:25	1634-04-4	
Naphthalene	**5.4**	ug/m3	3.8	3.1	1.44		09/15/21 20:25	91-20-3	
2-Propanol	**27.9**	ug/m3	3.6	0.73	1.44		09/15/21 20:25	67-63-0	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

ANALYTICAL RESULTS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Sample: BUILDING N - SOUTH - 3 SS **Lab ID: 10578413011** Collected: 09/08/21 14:32 Received: 09/10/21 16:00 Matrix: Air

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
TO15 MSV AIR	Analytical Method: TO-15								
	Pace Analytical Services - Minneapolis								
Propylene	**<0.19**	ug/m3	1.3	0.19	1.44		09/15/21 20:25	115-07-1	
Styrene	**1.3**	ug/m3	1.2	0.55	1.44		09/15/21 20:25	100-42-5	
1,1,2,2-Tetrachloroethane	**<0.54**	ug/m3	2.0	0.54	1.44		09/15/21 20:25	79-34-5	
Tetrachloroethene	**22.1**	ug/m3	0.99	0.42	1.44		09/15/21 20:25	127-18-4	
Tetrahydrofuran	**2.6**	ug/m3	0.86	0.26	1.44		09/15/21 20:25	109-99-9	
Toluene	**2.8**	ug/m3	1.1	0.35	1.44		09/15/21 20:25	108-88-3	
1,2,4-Trichlorobenzene	**<7.0**	ug/m3	10.9	7.0	1.44		09/15/21 20:25	120-82-1	
1,1,1-Trichloroethane	**<0.27**	ug/m3	1.6	0.27	1.44		09/15/21 20:25	71-55-6	
1,1,2-Trichloroethane	**<0.28**	ug/m3	0.80	0.28	1.44		09/15/21 20:25	79-00-5	
Trichloroethene	**34.5**	ug/m3	0.79	0.28	1.44		09/15/21 20:25	79-01-6	
Trichlorofluoromethane	**1.0J**	ug/m3	1.6	0.34	1.44		09/15/21 20:25	75-69-4	
1,1,2-Trichlorotrifluoroethane	**0.52J**	ug/m3	2.2	0.42	1.44		09/15/21 20:25	76-13-1	
1,2,4-Trimethylbenzene	**6.3**	ug/m3	1.4	0.51	1.44		09/15/21 20:25	95-63-6	
1,3,5-Trimethylbenzene	**1.6**	ug/m3	1.4	0.42	1.44		09/15/21 20:25	108-67-8	
Vinyl acetate	**<0.30**	ug/m3	1.0	0.30	1.44		09/15/21 20:25	108-05-4	
Vinyl chloride	**<0.12**	ug/m3	0.37	0.12	1.44		09/15/21 20:25	75-01-4	
m&p-Xylene	**4.4**	ug/m3	2.5	0.92	1.44		09/15/21 20:25	179601-23-1	
o-Xylene	**2.2**	ug/m3	1.3	0.39	1.44		09/15/21 20:25	95-47-6	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

QC Batch: 770320
QC Batch Method: TO-15
Analysis Method: TO-15
Analysis Description: TO15 MSV AIR Low Level
Laboratory: Pace Analytical Services - Minneapolis
Associated Lab Samples: 10578413001, 10578413002, 10578413003, 10578413004, 10578413005, 10578413006

METHOD BLANK: 4104311 Matrix: Air
Associated Lab Samples: 10578413001, 10578413002, 10578413003, 10578413004, 10578413005, 10578413006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
1,1,1-Trichloroethane	ug/m3	<0.093	0.56	09/15/21 10:45	
1,1,2,2-Tetrachloroethane	ug/m3	<0.19	0.70	09/15/21 10:45	
1,1,2-Trichloroethane	ug/m3	<0.098	0.28	09/15/21 10:45	
1,1,2-Trichlorotrifluoroethane	ug/m3	<0.14	0.78	09/15/21 10:45	
1,1-Dichloroethane	ug/m3	<0.082	0.41	09/15/21 10:45	
1,1-Dichloroethene	ug/m3	<0.069	0.40	09/15/21 10:45	
1,2,4-Trichlorobenzene	ug/m3	<2.4	3.8	09/15/21 10:45	
1,2,4-Trimethylbenzene	ug/m3	<0.18	0.50	09/15/21 10:45	
1,2-Dibromoethane (EDB)	ug/m3	<0.15	0.39	09/15/21 10:45	
1,2-Dichlorobenzene	ug/m3	<0.20	1.5	09/15/21 10:45	
1,2-Dichloroethane	ug/m3	<0.097	0.41	09/15/21 10:45	
1,2-Dichloropropane	ug/m3	<0.13	0.47	09/15/21 10:45	
1,3,5-Trimethylbenzene	ug/m3	<0.14	0.50	09/15/21 10:45	
1,3-Butadiene	ug/m3	<0.060	0.22	09/15/21 10:45	
1,3-Dichlorobenzene	ug/m3	<0.25	1.5	09/15/21 10:45	
1,4-Dichlorobenzene	ug/m3	<0.44	1.5	09/15/21 10:45	
1,4-Dioxane (p-Dioxane)	ug/m3	<0.38	3.7	09/15/21 10:45	
2-Butanone (MEK)	ug/m3	<0.23	1.5	09/15/21 10:45	
2-Hexanone	ug/m3	<0.22	2.1	09/15/21 10:45	
2-Propanol	ug/m3	<0.25	1.2	09/15/21 10:45	
4-Ethyltoluene	ug/m3	<0.24	1.2	09/15/21 10:45	
4-Methyl-2-pentanone (MIBK)	ug/m3	<0.16	2.1	09/15/21 10:45	
Acetone	ug/m3	<0.90	3.0	09/15/21 10:45	
Benzene	ug/m3	<0.057	0.16	09/15/21 10:45	
Benzyl chloride	ug/m3	<0.44	1.3	09/15/21 10:45	
Bromodichloromethane	ug/m3	<0.12	0.68	09/15/21 10:45	
Bromoform	ug/m3	<0.81	2.6	09/15/21 10:45	
Bromomethane	ug/m3	<0.075	0.39	09/15/21 10:45	
Carbon disulfide	ug/m3	<0.064	0.32	09/15/21 10:45	
Carbon tetrachloride	ug/m3	<0.14	0.64	09/15/21 10:45	
Chlorobenzene	ug/m3	<0.078	0.47	09/15/21 10:45	
Chloroethane	ug/m3	<0.11	0.27	09/15/21 10:45	
Chloroform	ug/m3	<0.092	0.25	09/15/21 10:45	
Chloromethane	ug/m3	<0.043	0.21	09/15/21 10:45	
cis-1,2-Dichloroethene	ug/m3	<0.098	0.40	09/15/21 10:45	
cis-1,3-Dichloropropene	ug/m3	<0.13	1.2	09/15/21 10:45	
Cyclohexane	ug/m3	<0.11	0.88	09/15/21 10:45	
Dibromochloromethane	ug/m3	<0.26	0.86	09/15/21 10:45	
Dichlorodifluoromethane	ug/m3	<0.094	0.50	09/15/21 10:45	
Dichlorotetrafluoroethane	ug/m3	<0.10	0.71	09/15/21 10:45	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

METHOD BLANK: 4104311 Matrix: Air
Associated Lab Samples: 10578413001, 10578413002, 10578413003, 10578413004, 10578413005, 10578413006

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Ethanol	ug/m3	<0.30	0.96	09/15/21 10:45	
Ethyl acetate	ug/m3	<0.066	0.37	09/15/21 10:45	
Ethylbenzene	ug/m3	<0.15	0.44	09/15/21 10:45	
Hexachloro-1,3-butadiene	ug/m3	<0.62	2.7	09/15/21 10:45	
m&p-Xylene	ug/m3	<0.32	0.88	09/15/21 10:45	
Methyl-tert-butyl ether	ug/m3	<0.063	1.8	09/15/21 10:45	
Methylene Chloride	ug/m3	<0.30	1.8	09/15/21 10:45	
n-Heptane	ug/m3	<0.090	0.42	09/15/21 10:45	
n-Hexane	ug/m3	<0.096	0.36	09/15/21 10:45	
Naphthalene	ug/m3	<1.1	1.3	09/15/21 10:45	
o-Xylene	ug/m3	<0.14	0.44	09/15/21 10:45	
Propylene	ug/m3	<0.065	0.44	09/15/21 10:45	
Styrene	ug/m3	<0.19	0.43	09/15/21 10:45	
Tetrachloroethene	ug/m3	<0.15	0.34	09/15/21 10:45	
Tetrahydrofuran	ug/m3	<0.090	0.30	09/15/21 10:45	
Toluene	ug/m3	<0.12	0.38	09/15/21 10:45	
trans-1,2-Dichloroethene	ug/m3	<0.084	0.40	09/15/21 10:45	
trans-1,3-Dichloropropene	ug/m3	<0.27	1.2	09/15/21 10:45	
Trichloroethene	ug/m3	<0.098	0.55	09/15/21 10:45	
Trichlorofluoromethane	ug/m3	<0.12	0.57	09/15/21 10:45	
Vinyl acetate	ug/m3	<0.10	0.36	09/15/21 10:45	
Vinyl chloride	ug/m3	<0.043	0.13	09/15/21 10:45	

LABORATORY CONTROL SAMPLE: 4104312

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
1,1,1-Trichloroethane	ug/m3	59.3	55.8	94	70-130	
1,1,2,2-Tetrachloroethane	ug/m3	75.4	80.1	106	70-132	
1,1,2-Trichloroethane	ug/m3	59.6	61.6	103	70-134	
1,1,2-Trichlorotrifluoroethane	ug/m3	83.6	77.2	92	70-130	
1,1-Dichloroethane	ug/m3	43.9	41.7	95	70-133	
1,1-Dichloroethene	ug/m3	43.5	41.0	94	70-130	
1,2,4-Trichlorobenzene	ug/m3	177	191	108	69-132	
1,2,4-Trimethylbenzene	ug/m3	54	63.8	118	70-142	
1,2-Dibromoethane (EDB)	ug/m3	82.5	87.8	106	70-138	
1,2-Dichlorobenzene	ug/m3	66.2	78.2	118	70-146	
1,2-Dichloroethane	ug/m3	44.4	46.9	106	70-132	
1,2-Dichloropropane	ug/m3	50.6	51.4	102	70-134	
1,3,5-Trimethylbenzene	ug/m3	53.7	60.9	113	70-143	
1,3-Butadiene	ug/m3	24.2	25.5	105	70-136	
1,3-Dichlorobenzene	ug/m3	66.3	84.0	127	70-145	
1,4-Dichlorobenzene	ug/m3	66.3	85.5	129	70-140	
1,4-Dioxane (p-Dioxane)	ug/m3	98.2	112	114	70-130	
2-Butanone (MEK)	ug/m3	32.3	37.5	116	50-139	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

LABORATORY CONTROL SAMPLE: 4104312

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
2-Hexanone	ug/m3	44.8	50.2	112	70-148	
2-Propanol	ug/m3	149	142	95	67-135	
4-Ethyltoluene	ug/m3	53.7	65.5	122	70-145	
4-Methyl-2-pentanone (MIBK)	ug/m3	44.9	51.2	114	70-139	
Acetone	ug/m3	128	137	107	64-130	
Benzene	ug/m3	34.8	38.3	110	70-131	
Benzyl chloride	ug/m3	57.6	59.2	103	70-130	
Bromodichloromethane	ug/m3	73.1	73.8	101	70-133	
Bromoform	ug/m3	114	131	115	70-137	
Bromomethane	ug/m3	42.5	40.4	95	64-134	
Carbon disulfide	ug/m3	34.4	32.8	95	70-131	
Carbon tetrachloride	ug/m3	69.4	67.5	97	70-131	
Chlorobenzene	ug/m3	50.2	50.0	100	70-130	
Chloroethane	ug/m3	28.8	31.3	108	69-141	
Chloroform	ug/m3	52.4	58.4	111	70-130	
Chloromethane	ug/m3	22.6	22.3	99	70-130	
cis-1,2-Dichloroethene	ug/m3	43.4	43.7	101	70-137	
cis-1,3-Dichloropropene	ug/m3	49.4	55.1	112	70-144	
Cyclohexane	ug/m3	37.4	37.6	101	70-137	
Dibromochloromethane	ug/m3	93.2	96.1	103	70-132	
Dichlorodifluoromethane	ug/m3	54.6	51.0	93	70-130	
Dichlorotetrafluoroethane	ug/m3	71.2	67.8	95	70-130	
Ethanol	ug/m3	124	125	101	63-133	
Ethyl acetate	ug/m3	38.9	40.0	103	70-136	
Ethylbenzene	ug/m3	47.8	51.7	108	70-142	
Hexachloro-1,3-butadiene	ug/m3	133	138	104	70-135	
m&p-Xylene	ug/m3	95.4	104	109	70-141	
Methyl-tert-butyl ether	ug/m3	39.6	35.2	89	70-143	
Methylene Chloride	ug/m3	190	180	94	70-130	
n-Heptane	ug/m3	44.6	45.4	102	70-137	
n-Hexane	ug/m3	38	37.8	100	70-135	
Naphthalene	ug/m3	65.2	67.9	104	67-132	
o-Xylene	ug/m3	47.6	52.1	110	70-141	
Propylene	ug/m3	18.9	18.3	97	70-130	
Styrene	ug/m3	47	50.6	108	70-142	
Tetrachloroethene	ug/m3	73.4	81.7	111	70-130	
Tetrahydrofuran	ug/m3	32.1	35.3	110	70-136	
Toluene	ug/m3	41.6	43.5	105	70-138	
trans-1,2-Dichloroethene	ug/m3	43.6	42.1	97	70-130	
trans-1,3-Dichloropropene	ug/m3	50.5	60.2	119	70-145	
Trichloroethene	ug/m3	58.4	63.2	108	70-130	
Trichlorofluoromethane	ug/m3	62	59.9	97	69-135	
Vinyl acetate	ug/m3	46.4	49.3	106	70-146	
Vinyl chloride	ug/m3	28	28.5	102	70-137	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

SAMPLE DUPLICATE: 4106409

Parameter	Units	10578413003 Result	Dup Result	RPD	Max RPD	Qualifiers
1,1,1-Trichloroethane	ug/m3	<0.27	<0.27		25	
1,1,2,2-Tetrachloroethane	ug/m3	<0.54	<0.54		25	
1,1,2-Trichloroethane	ug/m3	<0.28	<0.28		25	
1,1,2-Trichlorotrifluoroethane	ug/m3	0.71J	0.72J		25	
1,1-Dichloroethane	ug/m3	<0.24	<0.24		25	
1,1-Dichloroethene	ug/m3	<0.20	<0.20		25	
1,2,4-Trichlorobenzene	ug/m3	<7.0	<7.0		25	
1,2,4-Trimethylbenzene	ug/m3	0.85J	0.85J		25	
1,2-Dibromoethane (EDB)	ug/m3	<0.43	<0.43		25	
1,2-Dichlorobenzene	ug/m3	<0.58	<0.58		25	
1,2-Dichloroethane	ug/m3	0.42J	0.46J		25	
1,2-Dichloropropane	ug/m3	<0.39	<0.39		25	
1,3,5-Trimethylbenzene	ug/m3	<0.42	<0.42		25	
1,3-Butadiene	ug/m3	<0.17	<0.17		25	
1,3-Dichlorobenzene	ug/m3	1.2J	1.2J		25	
1,4-Dichlorobenzene	ug/m3	<1.3	<1.3		25	
1,4-Dioxane (p-Dioxane)	ug/m3	<1.1	<1.1		25	
2-Butanone (MEK)	ug/m3	22.3	23.6	6	25	
2-Hexanone	ug/m3	<0.64	<0.64		25	
2-Propanol	ug/m3	58.7	62.1	6	25	
4-Ethyltoluene	ug/m3	<0.68	<0.68		25	
4-Methyl-2-pentanone (MIBK)	ug/m3	3.1J	3.4J		25	
Acetone	ug/m3	137	148	8	25	
Benzene	ug/m3	0.63	0.66	5	25	
Benzyl chloride	ug/m3	<1.3	<1.3		25	
Bromodichloromethane	ug/m3	<0.34	<0.34		25	
Bromoform	ug/m3	<2.3	<2.3		25	
Bromomethane	ug/m3	<0.22	<0.22		25	
Carbon disulfide	ug/m3	0.30J	0.33J		25	
Carbon tetrachloride	ug/m3	<0.40	<0.40		25	
Chlorobenzene	ug/m3	<0.22	<0.22		25	
Chloroethane	ug/m3	<0.32	<0.32		25	
Chloroform	ug/m3	0.78	0.86	10	25	
Chloromethane	ug/m3	1.5	1.8	21	25	
cis-1,2-Dichloroethene	ug/m3	<0.28	<0.28		25	
cis-1,3-Dichloropropene	ug/m3	<0.37	<0.37		25	
Cyclohexane	ug/m3	1.3J	1.4J		25	
Dibromochloromethane	ug/m3	<0.74	<0.74		25	
Dichlorodifluoromethane	ug/m3	4.2	4.5	7	25	
Dichlorotetrafluoroethane	ug/m3	<0.29	<0.29		25	
Ethanol	ug/m3	545	596	9	25	E
Ethyl acetate	ug/m3	8.5	9.1	8	25	
Ethylbenzene	ug/m3	0.74J	0.67J		25	
Hexachloro-1,3-butadiene	ug/m3	<1.8	<1.8		25	
m&p-Xylene	ug/m3	2.6	2.4J		25	
Methyl-tert-butyl ether	ug/m3	<0.18	<0.18		25	
Methylene Chloride	ug/m3	<0.85	<0.85		25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

SAMPLE DUPLICATE: 4106409

Parameter	Units	10578413003 Result	Dup Result	RPD	Max RPD	Qualifiers
n-Heptane	ug/m3	<0.26	<0.26		25	
n-Hexane	ug/m3	3.2	3.4	5	25	
Naphthalene	ug/m3	<3.1	<3.1		25	
o-Xylene	ug/m3	0.86J	0.91J		25	
Propylene	ug/m3	<0.19	<0.19		25	
Styrene	ug/m3	1.8	1.8	1	25	
Tetrachloroethene	ug/m3	<0.42	<0.42		25	
Tetrahydrofuran	ug/m3	4.3	4.6	6	25	
Toluene	ug/m3	9.0	9.5	5	25	
trans-1,2-Dichloroethene	ug/m3	0.73J	0.85J		25	
trans-1,3-Dichloropropene	ug/m3	<0.78	<0.78		25	
Trichloroethene	ug/m3	1.8	1.8	1	25	
Trichlorofluoromethane	ug/m3	1.3J	1.3J		25	
Vinyl acetate	ug/m3	<0.30	<0.30		25	
Vinyl chloride	ug/m3	<0.12	<0.12		25	

SAMPLE DUPLICATE: 4106412

Parameter	Units	10577367005 Result	Dup Result	RPD	Max RPD	Qualifiers
1,1,1-Trichloroethane	ug/m3	ND	<0.28		25	
1,1,2,2-Tetrachloroethane	ug/m3	ND	<0.55		25	
1,1,2-Trichloroethane	ug/m3	ND	<0.29		25	
1,1,2-Trichlorotrifluoroethane	ug/m3	ND	0.95J		25	
1,1-Dichloroethane	ug/m3	ND	<0.25		25	
1,1-Dichloroethene	ug/m3	ND	<0.21		25	
1,2,4-Trichlorobenzene	ug/m3	ND	<7.3		25	
1,2,4-Trimethylbenzene	ug/m3	ND	1.1J		25	
1,2-Dibromoethane (EDB)	ug/m3	ND	<0.45		25	
1,2-Dichlorobenzene	ug/m3	ND	<0.60		25	
1,2-Dichloroethane	ug/m3	ND	<0.29		25	
1,2-Dichloropropane	ug/m3	ND	<0.40		25	
1,3,5-Trimethylbenzene	ug/m3	ND	<0.43		25	
1,3-Butadiene	ug/m3	ND	<0.18		25	
1,3-Dichlorobenzene	ug/m3	ND	<0.76		25	
1,4-Dichlorobenzene	ug/m3	ND	<1.3		25	
1,4-Dioxane (p-Dioxane)	ug/m3	ND	<1.1		25	
2-Butanone (MEK)	ug/m3	ND	2.7J		25	
2-Hexanone	ug/m3	ND	<0.66		25	
2-Propanol	ug/m3	13.2	13.1	1	25	
4-Ethyltoluene	ug/m3	ND	<0.70		25	
4-Methyl-2-pentanone (MIBK)	ug/m3	ND	0.74J		25	
Acetone	ug/m3	39.4	37.9	4	25	
Benzene	ug/m3	0.62	0.52	17	25	
Benzyl chloride	ug/m3	ND	<1.3		25	
Bromodichloromethane	ug/m3	ND	<0.35		25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

SAMPLE DUPLICATE: 4106412

Parameter	Units	10577367005 Result	Dup Result	RPD	Max RPD	Qualifiers
Bromoform	ug/m3	ND	<2.4		25	
Bromomethane	ug/m3	ND	<0.22		25	
Carbon disulfide	ug/m3	ND	<0.19		25	
Carbon tetrachloride	ug/m3	ND	0.52J		25	
Chlorobenzene	ug/m3	ND	<0.23		25	
Chloroethane	ug/m3	ND	<0.33		25	
Chloroform	ug/m3	ND	<0.27		25	
Chloromethane	ug/m3	0.91	0.91	0	25	
cis-1,2-Dichloroethene	ug/m3	ND	<0.29		25	
cis-1,3-Dichloropropene	ug/m3	ND	<0.38		25	
Cyclohexane	ug/m3	ND	1.0J		25	
Dibromochloromethane	ug/m3	ND	<0.77		25	
Dichlorodifluoromethane	ug/m3	2.3	2.5	11	25	
Dichlorotetrafluoroethane	ug/m3	ND	<0.30		25	
Ethanol	ug/m3	269	306	13	25	
Ethyl acetate	ug/m3	ND	<0.20		25	
Ethylbenzene	ug/m3	ND	0.50J		25	
Hexachloro-1,3-butadiene	ug/m3	ND	<1.8		25	
m&p-Xylene	ug/m3	ND	1.6J		25	
Methyl-tert-butyl ether	ug/m3	ND	<0.19		25	
Methylene Chloride	ug/m3	ND	<0.88		25	
n-Heptane	ug/m3	ND	<0.27		25	
n-Hexane	ug/m3	1.5	1.5	2	25	
Naphthalene	ug/m3	ND	<3.2		25	
o-Xylene	ug/m3	ND	0.61J		25	
Propylene	ug/m3	ND	<0.19		25	
Styrene	ug/m3	ND	1.1J		25	
Tetrachloroethene	ug/m3	ND	<0.44		25	
Tetrahydrofuran	ug/m3	ND	<0.27		25	
Toluene	ug/m3	2.8	2.8	1	25	
trans-1,2-Dichloroethene	ug/m3	ND	<0.25		25	
trans-1,3-Dichloropropene	ug/m3	ND	<0.81		25	
Trichloroethene	ug/m3	ND	<0.29		25	
Trichlorofluoromethane	ug/m3	ND	1.2J		25	
Vinyl acetate	ug/m3	ND	<0.31		25	
Vinyl chloride	ug/m3	ND	<0.13		25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

QC Batch: 770404
QC Batch Method: TO-15
Analysis Method: TO-15
Analysis Description: TO15 MSV AIR Low Level
Laboratory: Pace Analytical Services - Minneapolis
Associated Lab Samples: 10578413007, 10578413008, 10578413009, 10578413010, 10578413011

METHOD BLANK: 4104676 Matrix: Air
Associated Lab Samples: 10578413007, 10578413008, 10578413009, 10578413010, 10578413011

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
1,1,1-Trichloroethane	ug/m3	<0.093	0.56	09/15/21 13:50	
1,1,2,2-Tetrachloroethane	ug/m3	<0.19	0.70	09/15/21 13:50	
1,1,2-Trichloroethane	ug/m3	<0.098	0.28	09/15/21 13:50	
1,1,2-Trichlorotrifluoroethane	ug/m3	<0.14	0.78	09/15/21 13:50	
1,1-Dichloroethane	ug/m3	<0.082	0.41	09/15/21 13:50	
1,1-Dichloroethene	ug/m3	<0.069	0.40	09/15/21 13:50	
1,2,4-Trichlorobenzene	ug/m3	<2.4	3.8	09/15/21 13:50	
1,2,4-Trimethylbenzene	ug/m3	<0.18	0.50	09/15/21 13:50	
1,2-Dibromoethane (EDB)	ug/m3	<0.15	0.39	09/15/21 13:50	
1,2-Dichlorobenzene	ug/m3	<0.20	1.5	09/15/21 13:50	
1,2-Dichloroethane	ug/m3	<0.097	0.41	09/15/21 13:50	
1,2-Dichloropropane	ug/m3	<0.13	0.47	09/15/21 13:50	
1,3,5-Trimethylbenzene	ug/m3	<0.14	0.50	09/15/21 13:50	
1,3-Butadiene	ug/m3	<0.060	0.22	09/15/21 13:50	
1,3-Dichlorobenzene	ug/m3	<0.25	1.5	09/15/21 13:50	
1,4-Dichlorobenzene	ug/m3	<0.44	1.5	09/15/21 13:50	
1,4-Dioxane (p-Dioxane)	ug/m3	<0.38	3.7	09/15/21 13:50	
2-Butanone (MEK)	ug/m3	<0.23	1.5	09/15/21 13:50	
2-Hexanone	ug/m3	<0.22	2.1	09/15/21 13:50	
2-Propanol	ug/m3	<0.25	1.2	09/15/21 13:50	
4-Ethyltoluene	ug/m3	<0.24	1.2	09/15/21 13:50	
4-Methyl-2-pentanone (MIBK)	ug/m3	<0.16	2.1	09/15/21 13:50	
Acetone	ug/m3	<0.90	3.0	09/15/21 13:50	
Benzene	ug/m3	<0.057	0.16	09/15/21 13:50	
Benzyl chloride	ug/m3	<0.44	1.3	09/15/21 13:50	
Bromodichloromethane	ug/m3	<0.12	0.68	09/15/21 13:50	
Bromoform	ug/m3	<0.81	2.6	09/15/21 13:50	
Bromomethane	ug/m3	<0.075	0.39	09/15/21 13:50	
Carbon disulfide	ug/m3	<0.064	0.32	09/15/21 13:50	
Carbon tetrachloride	ug/m3	<0.14	0.64	09/15/21 13:50	
Chlorobenzene	ug/m3	<0.078	0.47	09/15/21 13:50	
Chloroethane	ug/m3	<0.11	0.27	09/15/21 13:50	
Chloroform	ug/m3	<0.092	0.25	09/15/21 13:50	
Chloromethane	ug/m3	<0.043	0.21	09/15/21 13:50	
cis-1,2-Dichloroethene	ug/m3	<0.098	0.40	09/15/21 13:50	
cis-1,3-Dichloropropene	ug/m3	<0.13	1.2	09/15/21 13:50	
Cyclohexane	ug/m3	<0.11	0.88	09/15/21 13:50	
Dibromochloromethane	ug/m3	<0.26	0.86	09/15/21 13:50	
Dichlorodifluoromethane	ug/m3	<0.094	0.50	09/15/21 13:50	
Dichlorotetrafluoroethane	ug/m3	<0.10	0.71	09/15/21 13:50	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

METHOD BLANK: 4104676 Matrix: Air
Associated Lab Samples: 10578413007, 10578413008, 10578413009, 10578413010, 10578413011

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Ethanol	ug/m3	<0.30	0.96	09/15/21 13:50	
Ethyl acetate	ug/m3	<0.066	0.37	09/15/21 13:50	
Ethylbenzene	ug/m3	<0.15	0.44	09/15/21 13:50	
Hexachloro-1,3-butadiene	ug/m3	<0.62	2.7	09/15/21 13:50	
m&p-Xylene	ug/m3	<0.32	0.88	09/15/21 13:50	
Methyl-tert-butyl ether	ug/m3	<0.063	1.8	09/15/21 13:50	
Methylene Chloride	ug/m3	<0.30	1.8	09/15/21 13:50	
n-Heptane	ug/m3	<0.090	0.42	09/15/21 13:50	
n-Hexane	ug/m3	<0.096	0.36	09/15/21 13:50	
Naphthalene	ug/m3	<1.1	1.3	09/15/21 13:50	
o-Xylene	ug/m3	<0.14	0.44	09/15/21 13:50	
Propylene	ug/m3	<0.065	0.44	09/15/21 13:50	
Styrene	ug/m3	<0.19	0.43	09/15/21 13:50	
Tetrachloroethene	ug/m3	<0.15	0.34	09/15/21 13:50	
Tetrahydrofuran	ug/m3	<0.090	0.30	09/15/21 13:50	
Toluene	ug/m3	<0.12	0.38	09/15/21 13:50	
trans-1,2-Dichloroethene	ug/m3	<0.084	0.40	09/15/21 13:50	
trans-1,3-Dichloropropene	ug/m3	<0.27	1.2	09/15/21 13:50	
Trichloroethene	ug/m3	<0.098	0.27	09/15/21 13:50	
Trichlorofluoromethane	ug/m3	<0.12	0.57	09/15/21 13:50	
Vinyl acetate	ug/m3	<0.10	0.36	09/15/21 13:50	
Vinyl chloride	ug/m3	<0.043	0.13	09/15/21 13:50	

LABORATORY CONTROL SAMPLE: 4104677

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
1,1,1-Trichloroethane	ug/m3	55.2	56.3	102	70-130	
1,1,2,2-Tetrachloroethane	ug/m3	72.5	78.2	108	70-132	
1,1,2-Trichloroethane	ug/m3	56.3	58.8	104	70-134	
1,1,2-Trichlorotrifluoroethane	ug/m3	77.9	78.0	100	70-130	
1,1-Dichloroethane	ug/m3	42.1	41.0	97	70-133	
1,1-Dichloroethene	ug/m3	41.5	40.2	97	70-130	
1,2,4-Trichlorobenzene	ug/m3	82	88.1	107	69-132	
1,2,4-Trimethylbenzene	ug/m3	51.9	55.4	107	70-142	
1,2-Dibromoethane (EDB)	ug/m3	80.4	86.1	107	70-138	
1,2-Dichlorobenzene	ug/m3	66	67.6	103	70-146	
1,2-Dichloroethane	ug/m3	42.1	41.5	98	70-132	
1,2-Dichloropropane	ug/m3	47.1	48.2	102	70-134	
1,3,5-Trimethylbenzene	ug/m3	51.4	56.5	110	70-143	
1,3-Butadiene	ug/m3	23	22.2	97	70-136	
1,3-Dichlorobenzene	ug/m3	63	68.1	108	70-145	
1,4-Dichlorobenzene	ug/m3	65.5	69.2	106	70-140	
1,4-Dioxane (p-Dioxane)	ug/m3	37.6	42.5	113	70-130	
2-Butanone (MEK)	ug/m3	32.4	30.2	93	50-139	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

LABORATORY CONTROL SAMPLE: 4104677

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
2-Hexanone	ug/m3	41.4	47.6	115	70-148	
2-Propanol	ug/m3	27.4	29.1	106	67-135	
4-Ethyltoluene	ug/m3	51.7	55.5	107	70-145	
4-Methyl-2-pentanone (MIBK)	ug/m3	42.4	47.7	113	70-139	
Acetone	ug/m3	24.6	23.1	94	64-130	
Benzene	ug/m3	32.9	32.7	100	70-131	
Benzyl chloride	ug/m3	57.3	59.1	103	70-130	
Bromodichloromethane	ug/m3	69.7	73.1	105	70-133	
Bromoform	ug/m3	110	118	107	70-137	
Bromomethane	ug/m3	39.9	39.7	99	64-134	
Carbon disulfide	ug/m3	33.4	33.8	101	70-131	
Carbon tetrachloride	ug/m3	65	66.8	103	70-131	
Chlorobenzene	ug/m3	48.3	48.5	100	70-130	
Chloroethane	ug/m3	26.9	28.1	105	69-141	
Chloroform	ug/m3	48.5	48.2	99	70-130	
Chloromethane	ug/m3	21.1	20.2	96	70-130	
cis-1,2-Dichloroethene	ug/m3	41	43.2	105	70-137	
cis-1,3-Dichloropropene	ug/m3	46.9	54.2	115	70-144	
Cyclohexane	ug/m3	35.2	38.0	108	70-137	
Dibromochloromethane	ug/m3	87.3	96.2	110	70-132	
Dichlorodifluoromethane	ug/m3	51.3	49.4	96	70-130	
Dichlorotetrafluoroethane	ug/m3	65.1	64.6	99	70-130	
Ethanol	ug/m3	19.2	23.3	122	63-133	
Ethyl acetate	ug/m3	35.9	37.5	104	70-136	
Ethylbenzene	ug/m3	45.6	49.3	108	70-142	
Hexachloro-1,3-butadiene	ug/m3	117	126	108	70-135	
m&p-Xylene	ug/m3	45.9	48.2	105	70-141	
Methyl-tert-butyl ether	ug/m3	36.9	38.7	105	70-143	
Methylene Chloride	ug/m3	37.8	38.1	101	70-130	
n-Heptane	ug/m3	41.7	42.2	101	70-137	
n-Hexane	ug/m3	35.1	35.3	101	70-135	
Naphthalene	ug/m3	58.1	65.7	113	67-132	
o-Xylene	ug/m3	46	48.9	106	70-141	
Propylene	ug/m3	17.9	16.7	93	70-130	
Styrene	ug/m3	45.3	47.7	105	70-142	
Tetrachloroethene	ug/m3	69.9	70.5	101	70-130	
Tetrahydrofuran	ug/m3	30.1	32.3	107	70-136	
Toluene	ug/m3	39.4	40.1	102	70-138	
trans-1,2-Dichloroethene	ug/m3	40.8	42.4	104	70-130	
trans-1,3-Dichloropropene	ug/m3	48.2	54.8	114	70-145	
Trichloroethene	ug/m3	55.7	55.3	99	70-130	
Trichlorofluoromethane	ug/m3	56.5	55.6	98	69-135	
Vinyl acetate	ug/m3	38.1	48.1	126	70-146	
Vinyl chloride	ug/m3	26.6	26.3	99	70-137	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

SAMPLE DUPLICATE: 4106320

Parameter	Units	10578413007 Result	Dup Result	RPD	Max RPD	Qualifiers
1,1,1-Trichloroethane	ug/m3	<0.26	<0.26		25	
1,1,2,2-Tetrachloroethane	ug/m3	<0.52	<0.52		25	
1,1,2-Trichloroethane	ug/m3	<0.27	<0.27		25	
1,1,2-Trichlorotrifluoroethane	ug/m3	0.44J	0.41J		25	
1,1-Dichloroethane	ug/m3	<0.23	<0.23		25	
1,1-Dichloroethene	ug/m3	<0.19	<0.19		25	
1,2,4-Trichlorobenzene	ug/m3	<6.8	<6.8		25	
1,2,4-Trimethylbenzene	ug/m3	3.7	3.8	0	25	
1,2-Dibromoethane (EDB)	ug/m3	<0.42	<0.42		25	
1,2-Dichlorobenzene	ug/m3	<0.56	<0.56		25	
1,2-Dichloroethane	ug/m3	<0.27	<0.27		25	
1,2-Dichloropropane	ug/m3	<0.37	<0.37		25	
1,3,5-Trimethylbenzene	ug/m3	0.98J	0.93J		25	
1,3-Butadiene	ug/m3	<0.17	<0.17		25	
1,3-Dichlorobenzene	ug/m3	<0.71	<0.71		25	
1,4-Dichlorobenzene	ug/m3	<1.2	<1.2		25	
1,4-Dioxane (p-Dioxane)	ug/m3	<1.0	<1.0		25	
2-Butanone (MEK)	ug/m3	1.3J	1.4J		25	
2-Hexanone	ug/m3	<0.61	<0.61		25	
2-Propanol	ug/m3	<0.71	1.3J		25	
4-Ethyltoluene	ug/m3	0.89J	0.78J		25	
4-Methyl-2-pentanone (MIBK)	ug/m3	<0.45	<0.45		25	
Acetone	ug/m3	4.5J	6.8J		25	
Benzene	ug/m3	<0.16	<0.16		25	
Benzyl chloride	ug/m3	<1.2	<1.2		25	
Bromodichloromethane	ug/m3	3.4	3.5	3	25	
Bromoform	ug/m3	<2.3	<2.3		25	
Bromomethane	ug/m3	<0.21	<0.21		25	
Carbon disulfide	ug/m3	0.58J	0.60J		25	
Carbon tetrachloride	ug/m3	9.1	9.1	0	25	
Chlorobenzene	ug/m3	<0.22	<0.22		25	
Chloroethane	ug/m3	<0.31	<0.31		25	
Chloroform	ug/m3	146	147	0	25	
Chloromethane	ug/m3	<0.12	<0.12		25	
cis-1,2-Dichloroethene	ug/m3	8.4	8.6	3	25	
cis-1,3-Dichloropropene	ug/m3	<0.35	<0.35		25	
Cyclohexane	ug/m3	1.2J	1.3J		25	
Dibromochloromethane	ug/m3	<0.72	<0.72		25	
Dichlorodifluoromethane	ug/m3	2.3	2.6	10	25	
Dichlorotetrafluoroethane	ug/m3	<0.28	<0.28		25	
Ethanol	ug/m3	30.6	27.1	12	25	
Ethyl acetate	ug/m3	<0.18	<0.18		25	
Ethylbenzene	ug/m3	0.50J	0.50J		25	
Hexachloro-1,3-butadiene	ug/m3	<1.7	<1.7		25	
m&p-Xylene	ug/m3	1.8J	1.8J		25	
Methyl-tert-butyl ether	ug/m3	<0.18	<0.18		25	
Methylene Chloride	ug/m3	<0.82	<0.82		25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

SAMPLE DUPLICATE: 4106320

Parameter	Units	10578413007 Result	Dup Result	RPD	Max RPD	Qualifiers
n-Heptane	ug/m3	<0.25	<0.25		25	
n-Hexane	ug/m3	0.63J	0.64J		25	
Naphthalene	ug/m3	<3.0	<3.0		25	
o-Xylene	ug/m3	1.1J	1.0J		25	
Propylene	ug/m3	<0.18	<0.18		25	
Styrene	ug/m3	1.1J	1.1J		25	
Tetrachloroethene	ug/m3	<0.41	<0.41		25	
Tetrahydrofuran	ug/m3	<0.25	<0.25		25	
Toluene	ug/m3	1.3	1.3	0	25	
trans-1,2-Dichloroethene	ug/m3	4.4	4.4	0	25	
trans-1,3-Dichloropropene	ug/m3	<0.76	<0.76		25	
Trichloroethene	ug/m3	127	129	1	25	
Trichlorofluoromethane	ug/m3	1.5J	1.6		25	
Vinyl acetate	ug/m3	<0.29	<0.29		25	
Vinyl chloride	ug/m3	<0.12	<0.12		25	

SAMPLE DUPLICATE: 4106321

Parameter	Units	10578413008 Result	Dup Result	RPD	Max RPD	Qualifiers
1,1,1-Trichloroethane	ug/m3	<0.26	<0.26		25	
1,1,2,2-Tetrachloroethane	ug/m3	<0.52	<0.52		25	
1,1,2-Trichloroethane	ug/m3	<0.27	<0.27		25	
1,1,2-Trichlorotrifluoroethane	ug/m3	0.65J	0.58J		25	
1,1-Dichloroethane	ug/m3	<0.23	<0.23		25	
1,1-Dichloroethene	ug/m3	<0.19	<0.19		25	
1,2,4-Trichlorobenzene	ug/m3	<6.8	<6.8		25	
1,2,4-Trimethylbenzene	ug/m3	5.3	5.3	1	25	
1,2-Dibromoethane (EDB)	ug/m3	<0.42	<0.42		25	
1,2-Dichlorobenzene	ug/m3	<0.56	<0.56		25	
1,2-Dichloroethane	ug/m3	<0.27	<0.27		25	
1,2-Dichloropropane	ug/m3	<0.37	<0.37		25	
1,3,5-Trimethylbenzene	ug/m3	1.4J	1.4		25	
1,3-Butadiene	ug/m3	<0.17	<0.17		25	
1,3-Dichlorobenzene	ug/m3	<0.71	<0.71		25	
1,4-Dichlorobenzene	ug/m3	1.3J	1.3J		25	
1,4-Dioxane (p-Dioxane)	ug/m3	<1.0	<1.0		25	
2-Butanone (MEK)	ug/m3	2.2J	2.5J		25	
2-Hexanone	ug/m3	0.81J	0.79J		25	
2-Propanol	ug/m3	1.6J	1.6J		25	
4-Ethyltoluene	ug/m3	1.2J	1.2J		25	
4-Methyl-2-pentanone (MIBK)	ug/m3	<0.45	<0.45		25	
Acetone	ug/m3	7.8J	7.6J		25	
Benzene	ug/m3	0.25J	0.25J		25	
Benzyl chloride	ug/m3	<1.2	<1.2		25	
Bromodichloromethane	ug/m3	<0.33	<0.33		25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

SAMPLE DUPLICATE: 4106321

Parameter	Units	10578413008 Result	Dup Result	RPD	Max RPD	Qualifiers
Bromoform	ug/m3	<2.3	<2.3		25	
Bromomethane	ug/m3	<0.21	<0.21		25	
Carbon disulfide	ug/m3	1.3	1.3	0	25	
Carbon tetrachloride	ug/m3	0.44J	0.45J		25	
Chlorobenzene	ug/m3	<0.22	<0.22		25	
Chloroethane	ug/m3	<0.31	<0.31		25	
Chloroform	ug/m3	15.6	15.6	0	25	
Chloromethane	ug/m3	<0.12	<0.12		25	
cis-1,2-Dichloroethene	ug/m3	<0.27	<0.27		25	
cis-1,3-Dichloropropene	ug/m3	<0.35	<0.35		25	
Cyclohexane	ug/m3	0.44J	0.41J		25	
Dibromochloromethane	ug/m3	<0.72	<0.72		25	
Dichlorodifluoromethane	ug/m3	2.2	2.1	2	25	
Dichlorotetrafluoroethane	ug/m3	<0.28	<0.28		25	
Ethanol	ug/m3	32.6	31.9	2	25	
Ethyl acetate	ug/m3	<0.18	<0.18		25	
Ethylbenzene	ug/m3	0.76J	0.72J		25	
Hexachloro-1,3-butadiene	ug/m3	<1.7	<1.7		25	
m&p-Xylene	ug/m3	2.7	2.8	3	25	
Methyl-tert-butyl ether	ug/m3	<0.18	<0.18		25	
Methylene Chloride	ug/m3	<0.82	<0.82		25	
n-Heptane	ug/m3	0.36J	0.37J		25	
n-Hexane	ug/m3	0.70J	0.70J		25	
Naphthalene	ug/m3	3.3J	3.2J		25	
o-Xylene	ug/m3	1.5	1.5	2	25	
Propylene	ug/m3	<0.18	<0.18		25	
Styrene	ug/m3	1.5	1.5	2	25	
Tetrachloroethene	ug/m3	<0.41	<0.41		25	
Tetrahydrofuran	ug/m3	1.8	1.8	3	25	
Toluene	ug/m3	1.4	1.4	1	25	
trans-1,2-Dichloroethene	ug/m3	<0.23	<0.23		25	
trans-1,3-Dichloropropene	ug/m3	<0.76	<0.76		25	
Trichloroethene	ug/m3	1.9	1.9	2	25	
Trichlorofluoromethane	ug/m3	1.2J	1.1J		25	
Vinyl acetate	ug/m3	<0.29	<0.29		25	
Vinyl chloride	ug/m3	<0.12	<0.12		25	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALIFIERS

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

E Analyte concentration exceeded the calibration range. The reported result is estimated.

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1700 Elm Street
Minneapolis, MN 55414
(612)607-1700

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: 20.0150985.17 BAYSHORETOWN C
Pace Project No.: 10578413

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
10578413001	**BUILDING N - NORTH COMMON AREA**	TO-15	770320		
10578413002	**BUILDING N - NORTH APT. 411**	TO-15	770320		
10578413003	**BUILDING N - NORTH APT. 420**	TO-15	770320		
10578413004	**BUILDING N - SOUTH APT. 449**	TO-15	770320		
10578413005	**BUILDING N - SOUTH COMMON AREA**	TO-15	770320		
10578413006	**BUILDING N - BACKGROUND**	TO-15	770320		
10578413007	**BUILDING N - NORTH - 1 SS**	TO-15	770404		
10578413008	**BUILDING N - NORTH - 3 SS**	TO-15	770404		
10578413009	**BUILDING N - SOUTH - 1 SS**	TO-15	770404		
10578413010	**BUILDING N - SOUTH - 2 SS**	TO-15	770404		
10578413011	**BUILDING N - SOUTH - 3 SS**	TO-15	770404		

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical®
www.pacelabs.com

AIR: CHAIN-

The Chain-of-Custody is a LE

ment

WO# : 10578413

10578413

51651

Page: 1 of 1

Section A
Required Client Information:

Company: GZA GEOENVIRONMENTAL INC.
Address: 17975 W. SARAH LN STE 100
BROOKFIELD, WI 53045
Email To: HEIDI.WOELFEL@GZA.COM
Phone: 262-754-2560 Fax:
Requested Due Date/TAT:

Section B
Required Project Information:

Report To: GZA
Copy To:
Purchase Order No.:
Project Name: BAYSTATE TOWN CENTER
Project Number: 20.0150985.17

Section C
Invoice Information:

Attention: HEIDI WOELFEL
Company Name: GZA
Address:
Pace Quote Reference:
Pace Project Manager/Sales Rep.
Pace Profile #: 39601

Program
☐ UST ☐ Superfund ☐ Emissions ☐ Clean Air Act
☐ Voluntary Clean Up ☐ Dry Clean ☐ RCRA ☐ Other

Location of Sampling by State: WI

Reporting Units
µg/m³ ___ mg/m³ ___
PPBV ___ PPMV ___
Other ___

Report Level II.___ III.___ IV.___ Other___

'Section D Required Client Information

AIR SAMPLE ID
Sample IDs MUST BE UNIQUE

Valid Media Codes

MEDIA	CODE
Tedlar Bag	TB
1 Liter Summa Can	1LC
6 Liter Summa Can	6LC
Low Volume Puff	LVP
High Volume Puff	HVP
Other	PM10

ITEM #	AIR SAMPLE ID	MEDIA CODE	PID Reading (Client only)	COLLECTED COMPOSITE START DATE	COMPOSITE START TIME	COMPOSITE - END/GRAB DATE	COMPOSITE - END/GRAB TIME	Canister Pressure (Initial Field - in Hg)	Canister Pressure (Final Field - in Hg)	Summa Can Number	Flow Control Number	Method: PM10	3C - Fixed Gas (%)	TO-3 BTEX	TO-3M (Methane)	TO-14	TO-15 Full List VOCs	TO-15 Short List BTEX	TO-15 Short List Chlorinated	TO-15 Short List (other)	Pace Lab ID	
1	BUILDING N - NORTH COMMON AREA	6LC		9/7/21	0844	9/8/21	0847	-29	-3	10561	14591					X					001	-3
2	BUILDING N - NORTH APT. 411	6LC			0853		0856	-31	-5	02910	34601					X					002	-5
3	BUILDING N - NORTH APT. 420	6LC			0901		0910	-29.5	-3	26641	19301					X					003	-3
4	BUILDING N - ~~NORTH~~ SOUTH APT. 449	6LC			0910		0900	-27	-6	27610	31501					X					004	-6
5	BUILDING N - SOUTH COMMON AREA	6LC			0921		0918	-29	-4	27590	23801					X					005	
6	BUILDING N - BACKGROUND	6LC			0928		0921	-30	-2	35981	38501					X					006	
7	BUILDING N - North - 1 SS	6LC		9/8/21	1133		1215	-30	-1	23420	11801					X					007	
8	BUILDING N - North - 3 SS	6LC			1229		1315	-29	0	17091	18251					X					008	
9	BUILDING N - South - 1 SS	6LC			1259		1341	-29	-1.5	21601	17181					X					009	
10	BUILDING N - South - 2 SS	6LC			1320		1407	-30	-1	16900	07271					X					010	
11	BUILDING N - South - 3 SS	6LC			1345		1432	-29.5	-2	01980	08431					X					011	
12																						

Comments :

PLEASE ANALYZE: TO-15
METHANE
1,4-DIOXANE

RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME
	9/8/21	1545	FEDEX		
			PACE	9/10/21	1600

SAMPLE CONDITIONS

	Y/N	Y/N	Y/N
	Y/N	Y/N	Y/N
	Y/N	Y/N	Y/N
Temp in °C	Received on Ice Y/N	Custody Sealed Cooler Y/N	Samples Intact Y/N

SAMPLER NAME AND SIGNATURE

PRINT Name of SAMPLER: CHRIS HOWSWORTH
SIGNATURE of SAMPLER:
DATE Signed (MM / DD / YY)

ORIGINAL

Pace Analytical®	Document Name: Sample Condition Upon Receipt (SCUR) - Air	Document Revised: 24Mar2020 Page 1 of 1
	Document No.: ENV-FRM-MIN4-0113 Rev.00	Pace Analytical Services - Minneapolis

Air Sample Condition Upon Receipt **Client Name:** GZA **Project #:**

WO#: 10578413
PM: MR2 Due Date: 09/17/21
CLIENT: GZA GEOENV

Courier: [X] Fed Ex [ ] UPS [ ] USPS [ ] Client [ ] Pace [ ] SpeeDee [ ] Commercial **See Exception** [ ]

Tracking Number: 9753 8445 4303

Custody Seal on Cooler/Box Present? [X] Yes [ ] No **Seals Intact?** [X] Yes [ ] No

Packing Material: [ ] Bubble Wrap [ ] Bubble Bags [X] Foam [ ] None [ ] Tin Can [ ] Other: _____ **Temp Blank rec:** [ ] Yes [X] No

Temp. (TO17 and TO13 samples only) (°C): — **Corrected Temp (°C):** —

Thermometer Used: [ ] G87A9170600254 [ ] G87A9155100842

Temp should be above freezing to 6°C **Correction Factor:** —

Date & Initials of Person Examining Contents: CLG 9/11/21

Type of ice Received [ ] Blue [ ] Wet [X] None

		Comments:
Chain of Custody Present?	[X] Yes [ ] No	1.
Chain of Custody Filled Out?	[X] Yes [ ] No	2.
Chain of Custody Relinquished?	[X] Yes [ ] No	3.
Sampler Name and/or Signature on COC?	[X] Yes [ ] No [ ] N/A	4.
Samples Arrived within Hold Time?	[X] Yes [ ] No	5.
Short Hold Time Analysis (<72 hr)?	[ ] Yes [X] No	6.
Rush Turn Around Time Requested?	[ ] Yes [X] No	7.
Sufficient Volume?	[X] Yes [ ] No	8.
Correct Containers Used? **(Tedlar bags not acceptable container for TO-14, TO-15 or APH)** -Pace Containers Used?	[X] Yes [ ] No [X] Yes [ ] No	9.
Containers Intact? **(visual inspection/no leaks when pressurized)**	[X] Yes [ ] No	10.
Media: Air Can Airbag Filter TDT Passive		11. Individually Certified Cans Y / N (list which samples)
Is sufficient information available to reconcile samples to the COC?	[X] Yes [ ] No	12.
Do cans need to be pressurized? **(DO NOT PRESSURIZE 3C or ASTM 1946!!!)**	[X] Yes [ ] No	13.

Gauge # [ ] 10AIR26 [X] 10AIR34 [ ] 10AIR35 [ ] 4097

Canisters					ORG 9/11/21 Canisters				
Sample Number	Can ID	Flow Controller	Initial Pressure	Final Pressure	Sample Number	Can ID	Flow Controller	Initial Pressure	Final Pressure
North Area	1056	1459	-4	+5	S-155	2160	1718	-1	+5
" 411	291	340	-3.5	"	255	1690	727	-1	"
" 420	2664	1930	-2	"	355	198	843	-2	"
" 449	2761	315	-3	"	unused FC's		1020		
South	2759	238	-4	"	"		377		
Background	3598	1385	-2.5	"	"		1070		
N 155	2342	1180	-1	"	"		329		
" 355	1709	1825	-1	"	"		457		

CLIENT NOTIFICATION/RESOLUTION **Field Data Required?** [ ] Yes [ ] No

Person Contacted: _____ Date/Time: _____

Comments/Resolution: _____

Project Manager Review: Matt Ray **Date:** 09/13/21

Note: Whenever there is a discrepancy affecting North Carolina compliance samples, a copy of this form will be sent to the North Carolina DEHNR Certification Office (i.e out of hold, incorrect preservative, out of temp, incorrect containers)