Wisconsin Public Service Corporation
700 North Adams Street
P.O. Box 19001
Green Bay, WI 54307-9001
www.wisconsinpublicservice.com

November 23, 2021

Mr. Matt Schneider
Director, Facilities and Procurement
Mid-State Technical College
1001 Center Point Drive
Stevens Point, Wisconsin, 54481

RE: Recent Sampling Results Stevens Point Former Manufactured Gas Plant
1111 Crosby Avenue, Stevens Point, Wisconsin 54481 WDNR BRRTS# 02-50-000079

Dear Mr. Schneider:

WEC Business Services, LLC (WBS), managing the Wisconsin Public Service Corporation (WPSC) former manufactured gas plant site at 1111 Crosby Ave is providing sample results of groundwater samples (OW14, OW23, and PZ14B) in October 2021 as part of routine, semi-annual monitoring. Wisconsin Administrative Code Chapter NR716.14 requires responsible parties (WPSC for the above mentioned site) to report sampling results to the property owner, and occupant, as applicable.

Results of the sampling are summarized in the attached. This includes a summary table of the results compared to State guidance values. Copies of the associated laboratory reports and figures showing the locations of samples collected on your property are also included.

We appreciate your cooperation as sampling progresses. If you need additional information, please contact Matt Vitale from the WDNR at 715-839-3760 or myself at 414-221-2156.

Sincerely,

Frank Dombrowski
Principal Environmental Consultant

Enc: Figure 1. Mid-State Technical College
Table 1. October 2021 Groundwater Analytical Results for Mid-State Technical College
Laboratory Report 40235062

CC: USEPA RPM – Stephanie Ross
WDNR PM – Matt Vitale

FIGURE

DRAWN BY: DMD DATE: 04/04/16
CHECKED BY: AGC DATE: 02/08/17
APPROVED BY: KRM DATE: 02/08/17
DRAWING NO: Fig 1_Mid-State Tech College
REFERENCE: .

MID-STATE TECHNICAL COLLEGE

RECENT SAMPLING RESULTS
FORMER STEVENS POINT MANUFACTURED GAS PLANT
WISCONSIN PUBLIC SERVICE CORPORATION
STEVENS POINT, WISCONSIN
BRRTS# 02-50-000079

RAMBOLL

PROJECT NO.
67846

FIGURE NO.
1

Jan 02, 2020 2:51pm PLOTTED BY: CAWRSEAG SAVED BY: CawrseAG
Y:\ACAData\Projects\11\1177\STPT\20-1\Figure 1_Mid-State Technical College.dwg Layout
IMAGES: Y:\ACAData\Projects\11\1177\STPT\20-1\Reference\ESRI Aerial 032516.jpg;
XREFS:

TABLE

Table 1. October 2021 Groundwater Analytical Results for Mid-State Technical College

October 2021 Groundwater Analytical Results
Wisconsin Public Service Corporation
Former Stevens Point Manufactured Gas Plant Site
1111 Crosby Avenue, Stevens Point, Wisconsin
USEPA ID #WIN000509983 / BRRTS #02-50-000079 / FID # 750081200

			VOC	PAH	PAH	PAH	PAH	PAH	PAH	PAH	PAH	PAH	PAH	Metal	Metal	Metal	Inorganic	Inorganic	Inorganic	Organic
9-digit Code	Sample Location	Sample Date	Benzene	Benzo(a)anthracene	Benzo(a)pyrene	Benzo(b)fluoranthene	Benzo(k)fluoranthene	Chrysene	Dibenz(a,h)anthracene	Fluoranthene	Indeno(1,2,3-cd)pyrene	Naphthalene	Pyrene	Iron, Dissolved	Iron, Total	Manganese, Dissolved	Alkalinity, Total	Nitrogen, NO2 + NO3, Total	Sulfate, Total	Methane
Reporting Units:			µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L	µg/L
			Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag	Result Flag
WI Groundwater PAL:			0.5	NS	0.02	0.02	NS	0.02	NS	80	NS	10	50	150	150	60	NS	2,000	125,000	NS
WI Groundwater ES:			**5**	**NS**	**0.2**	**0.2**	**NS**	**0.2**	**NS**	**400**	**NS**	**100**	**250**	**300**	**300**	**300**	**NS**	**10,000**	**250,000**	**NS**
101121002	OW14	10/11/2021	1.5	1.9	**5.4**	**10.5**	4.6	**9.6**	0.72	21.4	4.8	8.0	13.4	**5,940**	**6,200**	**568**	196,000	59 U	9,400 J	871
101121001	OW23	10/11/2021	0.30 U	0.64	**0.43** J	**0.64**	0.21 U	**1.4**	0.17 U	3.5	0.15 U	16.7	2.8	56.7 U	194	56.7	208,000	2,400	19,500	9.4
101121003	PZ14B	10/11/2021	0.30 U	0.014 U	0.027 J	0.045 J	0.030 J	0.052 J	0.019 U	0.077	0.024 J	0.057	0.050 J	56.7 U	56.7 U	--	--	--	--	--

[O:MGP 11/7/2021, ECB 11/8/2021, KN 11/18/21]

Sorted by Sample Location
Analyte concentration attains or exceeds the standard for:

Underlined	WI Groundwater PAL
Bold	**WI Groundwater ES**

Results & Flags:
-- = Analysis not performed
J = Estimated Concentration
U = Concentration was not detected above the reported limit

Acronyms:
µg/L = micrograms per liter
BRRTS = Bureau for Remediation and Redevelopment Tracking System
Dup = Quality Control Field Duplicate Sample
EPA = Environmental Protection Agency
ES = Enforcement Standard
FID = facility identification number
MGP = Manufactured Gas Plant
NO2 + NO3 = nitrite plus nitrate
NS = A groundwater quality standard has not been established.
PAH = Polycyclic Aromatic Hydrocarbon
PAL = Preventive Action Limit
USEPA ID = United States Environmental Protection Agency site identification number
VOC = Volatile Organic Compound
WDNR = Wisconsin Department of Natural Resources

Standards:
PAL and ES from WI Administrative Code NR 140 groundwater quality standard revised effective January 2020. Results that attain or exceed the PAL are considered to be in exceedance.
Lab comments, additional data qualifiers and definitions can be found in associated laboratory reports.

LABORATORY DATA REPORTS

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

October 27, 2021

Andrew Cawrse
Ramboll Americas
234 W Florida St
Milwaukee, WI 53204

RE: Project: STEVENS POINT MGP
Pace Project No.: 40235062

Dear Andrew Cawrse:

Enclosed are the analytical results for sample(s) received by the laboratory on October 13, 2021. The results relate only to the samples included in this report. Results reported herein conform to the applicable TNI/NELAC Standards and the laboratory's Quality Manual, where applicable, unless otherwise noted in the body of the report.

The test results provided in this final report were generated by each of the following laboratories within the Pace Network:

- Pace Analytical Services - Green Bay

If you have any questions concerning this report, please feel free to contact me.

Sincerely,

Brian Basten
brian.basten@pacelabs.com
(920)469-2436
Project Manager

Enclosures

cc: NRT Data, Ramboll
Steve Wiskes, Ramboll

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

CERTIFICATIONS

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Pace Analytical Services Green Bay
1241 Bellevue Street, Green Bay, WI 54302
Florida/NELAP Certification #: E87948
Illinois Certification #: 200050
Kentucky UST Certification #: 82
Louisiana Certification #: 04168
Minnesota Certification #: 055-999-334
New York Certification #: 12064
North Dakota Certification #: R-150
Virginia VELAP ID: 460263
South Carolina Certification #: 83006001
Texas Certification #: T104704529-14-1
Wisconsin Certification #: 405132750
Wisconsin DATCP Certification #: 105-444
USDA Soil Permit #: P330-16-00157
Federal Fish & Wildlife Permit #: LE51774A-0

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

SAMPLE SUMMARY

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Lab ID	Sample ID	Matrix	Date Collected	Date Received
40235062001	**101121002**	Water	10/11/21 14:52	10/13/21 12:15
40235062002	**101121003**	Water	10/11/21 15:33	10/13/21 12:15
40235060001	**101121001**	Water	10/11/21 14:06	10/13/21 12:15

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

SAMPLE ANALYTE COUNT

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Lab ID	Sample ID	Method	Analysts	Analytes Reported
40235062001	**101121002**	EPA 8015B Modified	ALD	1
		EPA 6010D	TXW	1
		EPA 6010D	TXW	2
		EPA 8270E by SIM	RJN	12
		EPA 8260	JAV	4
		EPA 300.0	HMB	1
		EPA 310.2	DAW	1
		EPA 353.2	DAW	1
40235062002	**101121003**	EPA 6010D	TXW	1
		EPA 6010D	TXW	1
		EPA 8270E by SIM	RJN	12
		EPA 8260	JAV	4
40235060001	**101121001**	EPA 8015B Modified	ALD	1
		EPA 6010D	TXW	1
		EPA 6010D	TXW	2
		EPA 8270E by SIM	RJN	12
		EPA 8260	LAP	4
		EPA 300.0	HMB	1
		EPA 310.2	DAW	1
		EPA 353.2	DAW	1

PASI-G = Pace Analytical Services - Green Bay

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 8015B Modified**
Description: Methane, Ethane, Ethene GCV
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
2 samples were analyzed for EPA 8015B Modified by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):
All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:
All criteria were within method requirements with any exceptions noted below.

Surrogates:
All surrogates were within QC limits with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

QC Batch: 399359

A matrix spike and/or matrix spike duplicate (MS/MSD) were performed on the following sample(s): 40235061009

M1: Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

- MS (Lab ID: 2305700)
  - Methane
- MSD (Lab ID: 2305701)
  - Methane

Additional Comments:

Analyte Comments:

QC Batch: 399359

E: Analyte concentration exceeded the calibration range. The reported result is estimated.

- MS (Lab ID: 2305700)
  - Methane
- MSD (Lab ID: 2305701)
  - Methane

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 6010D**
Description: 6010D MET ICP
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
3 samples were analyzed for EPA 6010D by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:
The samples were prepared in accordance with EPA 3010A with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):
All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:
All criteria were within method requirements with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 6010D**
Description: 6010D MET ICP, Dissolved
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
3 samples were analyzed for EPA 6010D by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:
The samples were prepared in accordance with EPA 3010A with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):
All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:
All criteria were within method requirements with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 8270E by SIM**
Description: 8270E MSSV PAH
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
3 samples were analyzed for EPA 8270E by SIM by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Sample Preparation:
The samples were prepared in accordance with EPA 3510 with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):
All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:
All criteria were within method requirements with any exceptions noted below.

Internal Standards:
All internal standards were within QC limits with any exceptions noted below.

Surrogates:
All surrogates were within QC limits with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

QC Batch: 398843

B: Analyte was detected in the associated method blank.

- BLANK for HBN 398843 [OEXT/498 (Lab ID: 2302902)
  - Naphthalene

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

QC Batch: 398843

A matrix spike and/or matrix spike duplicate (MS/MSD) were performed on the following sample(s): 40235061009

M1: Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.

- MSD (Lab ID: 2302905)
  - Fluoranthene

Additional Comments:

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 8260**
Description: 8260 MSV UST
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
3 samples were analyzed for EPA 8260 by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Initial Calibrations (including MS Tune as applicable):
All criteria were within method requirements with any exceptions noted below.

Continuing Calibration:
All criteria were within method requirements with any exceptions noted below.

Internal Standards:
All internal standards were within QC limits with any exceptions noted below.

Surrogates:
All surrogates were within QC limits with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 300.0**
Description: 300.0 IC Anions
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
2 samples were analyzed for EPA 300.0 by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

Analyte Comments:

QC Batch: 399529

D3: Sample was diluted due to the presence of high levels of non-target analytes or other matrix interference.

- 101121002 (Lab ID: 40235062001)
  - Sulfate

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 310.2**
Description: 310.2 Alkalinity
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
2 samples were analyzed for EPA 310.2 by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

Additional Comments:

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

PROJECT NARRATIVE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Method: **EPA 353.2**
Description: 353.2 Nitrogen, NO2/NO3 pres.
Client: O'Brien & Gere Engineers, Inc Integrys WI
Date: October 27, 2021

General Information:
2 samples were analyzed for EPA 353.2 by Pace Analytical Services Green Bay. All samples were received in acceptable condition with any exceptions noted below or on the chain-of custody and/or the sample condition upon receipt form (SCUR) attached at the end of this report.

Hold Time:
The samples were analyzed within the method required hold times with any exceptions noted below.

Method Blank:
All analytes were below the report limit in the method blank, where applicable, with any exceptions noted below.

Laboratory Control Spike:
All laboratory control spike compounds were within QC limits with any exceptions noted below.

Matrix Spikes:
All percent recoveries and relative percent differences (RPDs) were within acceptance criteria with any exceptions noted below.

QC Batch: 398960

A matrix spike and/or matrix spike duplicate (MS/MSD) were performed on the following sample(s): 40234954002,40235061005

M0: Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

- MS (Lab ID: 2303684)
  - Nitrogen, NO2 plus NO3
- MS (Lab ID: 2303686)
  - Nitrogen, NO2 plus NO3
- MSD (Lab ID: 2303685)
  - Nitrogen, NO2 plus NO3
- MSD (Lab ID: 2303687)
  - Nitrogen, NO2 plus NO3

QC Batch: 398961

A matrix spike and/or matrix spike duplicate (MS/MSD) were performed on the following sample(s): 40235061009

M0: Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.

- MS (Lab ID: 2303691)
  - Nitrogen, NO2 plus NO3
- MSD (Lab ID: 2303692)
  - Nitrogen, NO2 plus NO3

Additional Comments:

This data package has been reviewed for quality and completeness and is approved for release.

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

ANALYTICAL RESULTS

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Sample: 101121002 **Lab ID: 40235062001** Collected: 10/11/21 14:52 Received: 10/13/21 12:15 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
Methane, Ethane, Ethene GCV	Analytical Method: EPA 8015B Modified Pace Analytical Services - Green Bay								
Methane	**871**	ug/L	28.0	5.8	10		10/22/21 17:43	74-82-8	
6010D MET ICP	Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Green Bay								
Iron	**6200**	ug/L	100	56.7	1	10/18/21 13:41	10/20/21 00:45	7439-89-6	
6010D MET ICP, Dissolved	Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Green Bay								
Iron, Dissolved	**5940**	ug/L	100	56.7	1	10/18/21 13:40	10/20/21 01:40	7439-89-6	
Manganese, Dissolved	**568**	ug/L	5.0	1.5	1	10/18/21 13:40	10/20/21 01:40	7439-96-5	
8270E MSSV PAH	Analytical Method: EPA 8270E by SIM Preparation Method: EPA 3510 Pace Analytical Services - Green Bay								
Benzo(a)anthracene	**1.9**	ug/L	0.25	0.069	5	10/18/21 13:44	10/21/21 11:57	56-55-3	
Benzo(a)pyrene	**5.4**	ug/L	0.25	0.10	5	10/18/21 13:44	10/21/21 11:57	50-32-8	
Benzo(b)fluoranthene	**10.5**	ug/L	0.25	0.099	5	10/18/21 13:44	10/21/21 11:57	205-99-2	
Benzo(k)fluoranthene	**4.6**	ug/L	0.25	0.11	5	10/18/21 13:44	10/21/21 11:57	207-08-9	
Chrysene	**9.6**	ug/L	0.25	0.14	5	10/18/21 13:44	10/21/21 11:57	218-01-9	
Dibenz(a,h)anthracene	**0.72**	ug/L	0.25	0.091	5	10/18/21 13:44	10/21/21 11:57	53-70-3	
Fluoranthene	**21.4**	ug/L	0.25	0.13	5	10/18/21 13:44	10/21/21 11:57	206-44-0	
Indeno(1,2,3-cd)pyrene	**4.8**	ug/L	0.25	0.079	5	10/18/21 13:44	10/21/21 11:57	193-39-5	
Naphthalene	**8.0**	ug/L	0.25	0.10	5	10/18/21 13:44	10/21/21 11:57	91-20-3	
Pyrene	**13.4**	ug/L	0.25	0.11	5	10/18/21 13:44	10/21/21 11:57	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	69	%	10-113		5	10/18/21 13:44	10/21/21 11:57	321-60-8	
Terphenyl-d14 (S)	71	%	28-124		5	10/18/21 13:44	10/21/21 11:57	1718-51-0	
8260 MSV UST	Analytical Method: EPA 8260 Pace Analytical Services - Green Bay								
Benzene	**1.5**	ug/L	1.0	0.30	1		10/19/21 01:05	71-43-2	
Surrogates									
Toluene-d8 (S)	104	%	70-130		1		10/19/21 01:05	2037-26-5	
4-Bromofluorobenzene (S)	108	%	70-130		1		10/19/21 01:05	460-00-4	
1,2-Dichlorobenzene-d4 (S)	108	%	70-130		1		10/19/21 01:05	2199-69-1	
300.0 IC Anions	Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay								
Sulfate	**9.4J**	mg/L	10.0	2.2	5		10/25/21 22:51	14808-79-8	D3
310.2 Alkalinity	Analytical Method: EPA 310.2 Pace Analytical Services - Green Bay								
Alkalinity, Total as CaCO3	**196**	mg/L	124	37.2	5		10/25/21 14:26		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

ANALYTICAL RESULTS

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Sample: 101121002 **Lab ID: 40235062001** Collected: 10/11/21 14:52 Received: 10/13/21 12:15 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
353.2 Nitrogen, NO2/NO3 pres.	Analytical Method: EPA 353.2 Pace Analytical Services - Green Bay								
Nitrogen, NO2 plus NO3	**<0.059**	mg/L	0.25	0.059	1		10/19/21 14:35		

Sample: 101121003 **Lab ID: 40235062002** Collected: 10/11/21 15:33 Received: 10/13/21 12:15 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
6010D MET ICP	Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Green Bay								
Iron	**<56.7**	ug/L	100	56.7	1	10/18/21 13:41	10/20/21 00:48	7439-89-6	
6010D MET ICP, Dissolved	Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Green Bay								
Iron, Dissolved	**<56.7**	ug/L	100	56.7	1	10/18/21 13:40	10/20/21 01:43	7439-89-6	
8270E MSSV PAH	Analytical Method: EPA 8270E by SIM Preparation Method: EPA 3510 Pace Analytical Services - Green Bay								
Benzo(a)anthracene	**<0.014**	ug/L	0.052	0.014	1	10/18/21 13:44	10/21/21 12:15	56-55-3	
Benzo(a)pyrene	**0.027J**	ug/L	0.052	0.020	1	10/18/21 13:44	10/21/21 12:15	50-32-8	
Benzo(b)fluoranthene	**0.045J**	ug/L	0.052	0.020	1	10/18/21 13:44	10/21/21 12:15	205-99-2	
Benzo(k)fluoranthene	**0.030J**	ug/L	0.052	0.023	1	10/18/21 13:44	10/21/21 12:15	207-08-9	
Chrysene	**0.052J**	ug/L	0.052	0.028	1	10/18/21 13:44	10/21/21 12:15	218-01-9	
Dibenz(a,h)anthracene	**<0.019**	ug/L	0.052	0.019	1	10/18/21 13:44	10/21/21 12:15	53-70-3	
Fluoranthene	**0.077**	ug/L	0.052	0.027	1	10/18/21 13:44	10/21/21 12:15	206-44-0	
Indeno(1,2,3-cd)pyrene	**0.024J**	ug/L	0.052	0.016	1	10/18/21 13:44	10/21/21 12:15	193-39-5	
Naphthalene	**0.057**	ug/L	0.052	0.021	1	10/18/21 13:44	10/21/21 12:15	91-20-3	B
Pyrene	**0.050J**	ug/L	0.052	0.024	1	10/18/21 13:44	10/21/21 12:15	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	78	%	10-113		1	10/18/21 13:44	10/21/21 12:15	321-60-8	
Terphenyl-d14 (S)	74	%	28-124		1	10/18/21 13:44	10/21/21 12:15	1718-51-0	
8260 MSV UST	Analytical Method: EPA 8260 Pace Analytical Services - Green Bay								
Benzene	**<0.30**	ug/L	1.0	0.30	1		10/19/21 01:26	71-43-2	
Surrogates									
Toluene-d8 (S)	110	%	70-130		1		10/19/21 01:26	2037-26-5	
4-Bromofluorobenzene (S)	110	%	70-130		1		10/19/21 01:26	460-00-4	
1,2-Dichlorobenzene-d4 (S)	105	%	70-130		1		10/19/21 01:26	2199-69-1	

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

ANALYTICAL RESULTS

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Sample: 101121001 **Lab ID: 40235060001** Collected: 10/11/21 14:06 Received: 10/13/21 12:15 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
Methane, Ethane, Ethene GCV	Analytical Method: EPA 8015B Modified Pace Analytical Services - Green Bay								
Methane	**9.4**	ug/L	2.8	0.58	1		10/22/21 10:09	74-82-8	
6010D MET ICP	Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Green Bay								
Iron	**194**	ug/L	100	56.7	1	10/15/21 05:27	10/15/21 23:28	7439-89-6	
6010D MET ICP, Dissolved	Analytical Method: EPA 6010D Preparation Method: EPA 3010A Pace Analytical Services - Green Bay								
Iron, Dissolved	**<56.7**	ug/L	100	56.7	1	10/15/21 05:17	10/16/21 00:26	7439-89-6	
Manganese, Dissolved	**56.7**	ug/L	5.0	1.5	1	10/15/21 05:17	10/16/21 00:26	7439-96-5	
8270E MSSV PAH	Analytical Method: EPA 8270E by SIM Preparation Method: EPA 3510 Pace Analytical Services - Green Bay								
Benzo(a)anthracene	**0.64**	ug/L	0.47	0.13	1	10/18/21 13:44	10/19/21 16:40	56-55-3	
Benzo(a)pyrene	**0.43J**	ug/L	0.47	0.18	1	10/18/21 13:44	10/19/21 16:40	50-32-8	
Benzo(b)fluoranthene	**0.64**	ug/L	0.47	0.18	1	10/18/21 13:44	10/19/21 16:40	205-99-2	
Benzo(k)fluoranthene	**<0.21**	ug/L	0.47	0.21	1	10/18/21 13:44	10/19/21 16:40	207-08-9	
Chrysene	**1.4**	ug/L	0.47	0.25	1	10/18/21 13:44	10/19/21 16:40	218-01-9	
Dibenz(a,h)anthracene	**<0.17**	ug/L	0.47	0.17	1	10/18/21 13:44	10/19/21 16:40	53-70-3	
Fluoranthene	**3.5**	ug/L	0.47	0.25	1	10/18/21 13:44	10/19/21 16:40	206-44-0	
Indeno(1,2,3-cd)pyrene	**<0.15**	ug/L	0.47	0.15	1	10/18/21 13:44	10/19/21 16:40	193-39-5	
Naphthalene	**16.7**	ug/L	0.47	0.19	1	10/18/21 13:44	10/19/21 16:40	91-20-3	
Pyrene	**2.8**	ug/L	0.47	0.21	1	10/18/21 13:44	10/19/21 16:40	129-00-0	
Surrogates									
2-Fluorobiphenyl (S)	59	%	10-113		1	10/18/21 13:44	10/19/21 16:40	321-60-8	
Terphenyl-d14 (S)	67	%	28-124		1	10/18/21 13:44	10/19/21 16:40	1718-51-0	
8260 MSV UST	Analytical Method: EPA 8260 Pace Analytical Services - Green Bay								
Benzene	**<0.30**	ug/L	1.0	0.30	1		10/15/21 21:27	71-43-2	
Surrogates									
Toluene-d8 (S)	98	%	70-130		1		10/15/21 21:27	2037-26-5	
4-Bromofluorobenzene (S)	102	%	70-130		1		10/15/21 21:27	460-00-4	
1,2-Dichlorobenzene-d4 (S)	103	%	70-130		1		10/15/21 21:27	2199-69-1	
300.0 IC Anions	Analytical Method: EPA 300.0 Pace Analytical Services - Green Bay								
Sulfate	**19.5**	mg/L	2.0	0.44	1		10/25/21 17:48	14808-79-8	
310.2 Alkalinity	Analytical Method: EPA 310.2 Pace Analytical Services - Green Bay								
Alkalinity, Total as CaCO3	**208**	mg/L	24.8	7.4	1		10/25/21 14:24		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

ANALYTICAL RESULTS

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Sample: 101121001 **Lab ID: 40235060001** Collected: 10/11/21 14:06 Received: 10/13/21 12:15 Matrix: Water

Parameters	Results	Units	LOQ	LOD	DF	Prepared	Analyzed	CAS No.	Qual
353.2 Nitrogen, NO2/NO3 pres.	Analytical Method: EPA 353.2 Pace Analytical Services - Green Bay								
Nitrogen, NO2 plus NO3	**2.4**	mg/L	0.25	0.059	1		10/19/21 14:21		

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 399359
QC Batch Method: EPA 8015B Modified
Analysis Method: EPA 8015B Modified
Analysis Description: Methane, Ethane, Ethene GCV
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001, 40235062001

METHOD BLANK: 2305697 Matrix: Water
Associated Lab Samples: 40235060001, 40235062001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Methane	ug/L	<0.58	2.8	10/22/21 09:42	

LABORATORY CONTROL SAMPLE & LCSD: 2305698 2305699

Parameter	Units	Spike Conc.	LCS Result	LCSD Result	LCS % Rec	LCSD % Rec	% Rec Limits	RPD	Max RPD	Qualifiers
Methane	ug/L	28.6	32.7	32.1	115	112	80-121	2	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2305700 2305701

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Methane	ug/L	702	114	114	1170	1320	413	544	10-200	12	20	E,M1

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398605
QC Batch Method: EPA 3010A
Analysis Method: EPA 6010D
Analysis Description: 6010D MET
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001

METHOD BLANK: 2301165 Matrix: Water
Associated Lab Samples: 40235060001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Iron	ug/L	<56.7	100	10/15/21 23:14	

LABORATORY CONTROL SAMPLE: 2301166

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	ug/L	10000	9910	99	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2301167 2301168

Parameter	Units	40235060008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	ug/L	513	10000	10000	10200	10000	97	95	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398816
QC Batch Method: EPA 3010A
Analysis Method: EPA 6010D
Analysis Description: 6010D MET
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235062001, 40235062002

METHOD BLANK: 2302658 Matrix: Water
Associated Lab Samples: 40235062001, 40235062002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Iron	ug/L	<56.7	100	10/21/21 06:47	

LABORATORY CONTROL SAMPLE: 2302659

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron	ug/L	10000	10200	102	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2302660 2302661

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron	ug/L	21800	10000	10000	31600	32300	98	105	75-125	2	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398604
QC Batch Method: EPA 3010A
Analysis Method: EPA 6010D
Analysis Description: 6010D MET Dissolved
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001

METHOD BLANK: 2301161 Matrix: Water
Associated Lab Samples: 40235060001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Iron, Dissolved	ug/L	<56.7	100	10/16/21 00:12	
Manganese, Dissolved	ug/L	<1.5	5.0	10/16/21 00:12	

LABORATORY CONTROL SAMPLE: 2301162

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron, Dissolved	ug/L	10000	9760	98	80-120	
Manganese, Dissolved	ug/L	250	252	101	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2301163 2301164

Parameter	Units	40235060008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron, Dissolved	ug/L	<56.7	10000	10000	9780	9920	98	99	75-125	1	20	
Manganese, Dissolved	ug/L	4.1J	250	250	259	262	102	103	75-125	1	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398817
QC Batch Method: EPA 3010A
Analysis Method: EPA 6010D
Analysis Description: 6010D MET Dissolved
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235062001, 40235062002

METHOD BLANK: 2302670 Matrix: Water
Associated Lab Samples: 40235062001, 40235062002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Iron, Dissolved	ug/L	<56.7	100	10/20/21 00:50	
Manganese, Dissolved	ug/L	<1.5	5.0	10/20/21 00:50	

LABORATORY CONTROL SAMPLE: 2302671

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Iron, Dissolved	ug/L	10000	10100	101	80-120	
Manganese, Dissolved	ug/L	250	246	98	80-120	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2302672 2302673

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Iron, Dissolved	ug/L	19000	10000	10000	29300	29300	103	103	75-125	0	20	
Manganese, Dissolved	ug/L	1380	250	250	1520	1290	57	-36	75-125	17	20	P6

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398657
QC Batch Method: EPA 8260
Analysis Method: EPA 8260
Analysis Description: 8260 MSV UST-WATER
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001

METHOD BLANK: 2301589 Matrix: Water
Associated Lab Samples: 40235060001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Benzene	ug/L	<0.30	1.0	10/15/21 19:09	
1,2-Dichlorobenzene-d4 (S)	%	102	70-130	10/15/21 19:09	
4-Bromofluorobenzene (S)	%	104	70-130	10/15/21 19:09	
Toluene-d8 (S)	%	98	70-130	10/15/21 19:09	

LABORATORY CONTROL SAMPLE: 2301590

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Benzene	ug/L	50	56.1	112	70-132	
1,2-Dichlorobenzene-d4 (S)	%			99	70-130	
4-Bromofluorobenzene (S)	%			104	70-130	
Toluene-d8 (S)	%			99	70-130	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2301591 2301592

Parameter	Units	40235060008 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Benzene	ug/L	<0.30	50	50	55.4	55.7	111	111	70-132	1	20	
1,2-Dichlorobenzene-d4 (S)	%						99	100	70-130			
4-Bromofluorobenzene (S)	%						104	105	70-130			
Toluene-d8 (S)	%						100	99	70-130			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398658
QC Batch Method: EPA 8260
Analysis Method: EPA 8260
Analysis Description: 8260 MSV UST-WATER
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235062001, 40235062002

METHOD BLANK: 2301593 Matrix: Water
Associated Lab Samples: 40235062001, 40235062002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Benzene	ug/L	<0.30	1.0	10/18/21 18:32	
1,2-Dichlorobenzene-d4 (S)	%	104	70-130	10/18/21 18:32	
4-Bromofluorobenzene (S)	%	103	70-130	10/18/21 18:32	
Toluene-d8 (S)	%	109	70-130	10/18/21 18:32	

LABORATORY CONTROL SAMPLE: 2301594

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Benzene	ug/L	50	57.3	115	70-132	
1,2-Dichlorobenzene-d4 (S)	%			97	70-130	
4-Bromofluorobenzene (S)	%			110	70-130	
Toluene-d8 (S)	%			109	70-130	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2301595 2301596

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Benzene	ug/L	24.4	50	50	83.4	77.3	118	106	70-132	8	20	
1,2-Dichlorobenzene-d4 (S)	%						100	100	70-130			
4-Bromofluorobenzene (S)	%						109	110	70-130			
Toluene-d8 (S)	%						109	109	70-130			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398843
QC Batch Method: EPA 3510
Analysis Method: EPA 8270E by SIM
Analysis Description: 8270E Water PAH
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001, 40235062001, 40235062002

METHOD BLANK: 2302902 Matrix: Water
Associated Lab Samples: 40235060001, 40235062001, 40235062002

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Benzo(a)anthracene	ug/L	<0.014	0.050	10/19/21 09:01	
Benzo(a)pyrene	ug/L	<0.020	0.050	10/19/21 09:01	
Benzo(b)fluoranthene	ug/L	<0.020	0.050	10/19/21 09:01	
Benzo(k)fluoranthene	ug/L	<0.022	0.050	10/19/21 09:01	
Chrysene	ug/L	<0.027	0.050	10/19/21 09:01	
Dibenz(a,h)anthracene	ug/L	<0.018	0.050	10/19/21 09:01	
Fluoranthene	ug/L	<0.026	0.050	10/19/21 09:01	
Indeno(1,2,3-cd)pyrene	ug/L	<0.016	0.050	10/19/21 09:01	
Naphthalene	ug/L	0.027J	0.050	10/19/21 09:01	
Pyrene	ug/L	<0.023	0.050	10/19/21 09:01	
2-Fluorobiphenyl (S)	%	71	10-113	10/19/21 09:01	
Terphenyl-d14 (S)	%	67	28-124	10/19/21 09:01	

LABORATORY CONTROL SAMPLE: 2302903

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Benzo(a)anthracene	ug/L	2	1.5	73	52-92	
Benzo(a)pyrene	ug/L	2	1.7	83	61-105	
Benzo(b)fluoranthene	ug/L	2	1.4	68	57-102	
Benzo(k)fluoranthene	ug/L	2	1.7	86	70-122	
Chrysene	ug/L	2	1.8	91	71-122	
Dibenz(a,h)anthracene	ug/L	2	1.3	63	41-101	
Fluoranthene	ug/L	2	1.8	89	67-116	
Indeno(1,2,3-cd)pyrene	ug/L	2	1.4	71	59-120	
Naphthalene	ug/L	2	1.5	75	71-120	
Pyrene	ug/L	2	1.7	85	72-120	
2-Fluorobiphenyl (S)	%			70	10-113	
Terphenyl-d14 (S)	%			77	28-124	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2302904 2302905

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Benzo(a)anthracene	ug/L	<0.057	2	1.9	1.3	1.3	62	68	52-92	5	20	
Benzo(a)pyrene	ug/L	<0.082	2	1.9	1.6	1.6	76	81	61-105	1	20	
Benzo(b)fluoranthene	ug/L	<0.081	2	1.9	1.2	1.2	58	60	57-102	2	20	
Benzo(k)fluoranthene	ug/L	<0.093	2	1.9	1.5	1.6	74	80	70-122	4	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2302904 2302905

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Chrysene	ug/L	<0.11	2	1.9	2.1	1.9	101	97	71-122	9	20	
Dibenz(a,h)anthracene	ug/L	<0.074	2	1.9	1.4	1.3	70	70	41-101	5	20	
Fluoranthene	ug/L	1.4	2	1.9	3.5	3.7	103	117	67-116	5	20	M1
Indeno(1,2,3-cd)pyrene	ug/L	<0.065	2	1.9	1.3	1.3	64	67	59-120	0	20	
Naphthalene	ug/L	0.56	2	1.9	2.2	2.4	81	95	71-120	8	20	
Pyrene	ug/L	0.79	2	1.9	2.5	2.6	84	94	72-120	4	20	
2-Fluorobiphenyl (S)	%						68	77	10-113			
Terphenyl-d14 (S)	%						62	67	28-124			

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 399430
QC Batch Method: EPA 300.0
Analysis Method: EPA 300.0
Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001

METHOD BLANK: 2306437 Matrix: Water
Associated Lab Samples: 40235060001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Sulfate	mg/L	<0.44	2.0	10/25/21 11:07	

LABORATORY CONTROL SAMPLE: 2306438

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfate	mg/L	20	21.1	105	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2306439 2306440

Parameter	Units	40235024001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfate	mg/L	14.1	100	100	121	121	107	107	90-110	0	15	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2306441 2306442

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfate	mg/L	41.6	100	100	151	151	109	110	90-110	0	15	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 399529
QC Batch Method: EPA 300.0
Analysis Method: EPA 300.0
Analysis Description: 300.0 IC Anions
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235062001

METHOD BLANK: 2307025 Matrix: Water
Associated Lab Samples: 40235062001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Sulfate	mg/L	<0.44	2.0	10/25/21 22:21	

LABORATORY CONTROL SAMPLE: 2307026

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Sulfate	mg/L	20	21.4	107	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2307027 2307028

Parameter	Units	40235062001 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfate	mg/L	9.4J	100	100	119	118	109	109	90-110	0	15	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2307029 2307030

Parameter	Units	40235214003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Sulfate	mg/L	193	400	400	612	605	105	103	90-110	1	15	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 399414
QC Batch Method: EPA 310.2
Analysis Method: EPA 310.2
Analysis Description: 310.2 Alkalinity
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001, 40235062001

METHOD BLANK: 2306167 Matrix: Water
Associated Lab Samples: 40235060001, 40235062001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Alkalinity, Total as CaCO3	mg/L	<7.4	24.8	10/25/21 14:06	

LABORATORY CONTROL SAMPLE: 2306168

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Alkalinity, Total as CaCO3	mg/L	100	105	105	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2306169 2306170

Parameter	Units	40234943003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO3	mg/L	321	100	100	416	414	94	93	90-110	0	20	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2306171 2306172

Parameter	Units	40234992003 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Alkalinity, Total as CaCO3	mg/L	181	100	100	280	281	98	99	90-110	0	20	

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398960
QC Batch Method: EPA 353.2
Analysis Method: EPA 353.2
Analysis Description: 353.2 Nitrate + Nitrite, preserved
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235060001

METHOD BLANK: 2303682 Matrix: Water
Associated Lab Samples: 40235060001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrogen, NO2 plus NO3	mg/L	<0.059	0.25	10/19/21 14:04	

LABORATORY CONTROL SAMPLE: 2303683

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrogen, NO2 plus NO3	mg/L	2.5	2.3	91	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2303684 2303685

Parameter	Units	40234954002 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Nitrogen, NO2 plus NO3	mg/L	0.20J	2.5	2.5	2.4	2.4	89	89	90-110	0	20	M0

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2303686 2303687

Parameter	Units	40235061005 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Nitrogen, NO2 plus NO3	mg/L	<0.059	2.5	2.5	2.1	2.1	84	85	90-110	1	20	M0

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA

Project: STEVENS POINT MGP
Pace Project No.: 40235062

QC Batch: 398961
QC Batch Method: EPA 353.2
Analysis Method: EPA 353.2
Analysis Description: 353.2 Nitrate + Nitrite, preserved
Laboratory: Pace Analytical Services - Green Bay
Associated Lab Samples: 40235062001

METHOD BLANK: 2303689 Matrix: Water
Associated Lab Samples: 40235062001

Parameter	Units	Blank Result	Reporting Limit	Analyzed	Qualifiers
Nitrogen, NO2 plus NO3	mg/L	<0.059	0.25	10/19/21 14:25	

LABORATORY CONTROL SAMPLE: 2303690

Parameter	Units	Spike Conc.	LCS Result	LCS % Rec	% Rec Limits	Qualifiers
Nitrogen, NO2 plus NO3	mg/L	2.5	2.3	92	90-110	

MATRIX SPIKE & MATRIX SPIKE DUPLICATE: 2303691 2303692

Parameter	Units	40235061009 Result	MS Spike Conc.	MSD Spike Conc.	MS Result	MSD Result	MS % Rec	MSD % Rec	% Rec Limits	RPD	Max RPD	Qual
Nitrogen, NO2 plus NO3	mg/L	<0.059	2.5	2.5	2.2	2.2	88	88	90-110	0	20	M0

Results presented on this page are in the units indicated by the "Units" column except where an alternate unit is presented to the right of the result.

REPORT OF LABORATORY ANALYSIS

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALIFIERS

Project: STEVENS POINT MGP
Pace Project No.: 40235062

DEFINITIONS

DF - Dilution Factor, if reported, represents the factor applied to the reported data due to dilution of the sample aliquot.

ND - Not Detected at or above LOD.

J - Estimated concentration at or above the LOD and below the LOQ.

LOD - Limit of Detection adjusted for dilution factor, percent moisture, initial weight and final volume.

LOQ - Limit of Quantitation adjusted for dilution factor, percent moisture, initial weight and final volume.

S - Surrogate

1,2-Diphenylhydrazine decomposes to and cannot be separated from Azobenzene using Method 8270. The result for each analyte is a combined concentration.

Consistent with EPA guidelines, unrounded data are displayed and have been used to calculate % recovery and RPD values.

LCS(D) - Laboratory Control Sample (Duplicate)

MS(D) - Matrix Spike (Duplicate)

DUP - Sample Duplicate

RPD - Relative Percent Difference

NC - Not Calculable.

SG - Silica Gel - Clean-Up

U - Indicates the compound was analyzed for, but not detected at or above the adjusted LOD.

N-Nitrosodiphenylamine decomposes and cannot be separated from Diphenylamine using Method 8270. The result reported for each analyte is a combined concentration.

Pace Analytical is TNI accredited. Contact your Pace PM for the current list of accredited analytes.

TNI - The NELAC Institute.

ANALYTE QUALIFIERS

B	Analyte was detected in the associated method blank.
D3	Sample was diluted due to the presence of high levels of non-target analytes or other matrix interference.
E	Analyte concentration exceeded the calibration range. The reported result is estimated.
M0	Matrix spike recovery and/or matrix spike duplicate recovery was outside laboratory control limits.
M1	Matrix spike recovery exceeded QC limits. Batch accepted based on laboratory control sample (LCS) recovery.
P6	Matrix spike recovery was outside laboratory control limits due to a parent sample concentration notably higher than the spike level.

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical Services, LLC
1241 Bellevue Street - Suite 9
Green Bay, WI 54302
(920)469-2436

QUALITY CONTROL DATA CROSS REFERENCE TABLE

Project: STEVENS POINT MGP
Pace Project No.: 40235062

Lab ID	Sample ID	QC Batch Method	QC Batch	Analytical Method	Analytical Batch
40235060001	**101121001**	EPA 8015B Modified	399359		
40235062001	**101121002**	EPA 8015B Modified	399359		
40235060001	**101121001**	EPA 3010A	398605	EPA 6010D	398696
40235062001	**101121002**	EPA 3010A	398816	EPA 6010D	398998
40235062002	**101121003**	EPA 3010A	398816	EPA 6010D	398998
40235060001	**101121001**	EPA 3010A	398604	EPA 6010D	398698
40235062001	**101121002**	EPA 3010A	398817	EPA 6010D	398999
40235062002	**101121003**	EPA 3010A	398817	EPA 6010D	398999
40235060001	**101121001**	EPA 3510	398843	EPA 8270E by SIM	398884
40235062001	**101121002**	EPA 3510	398843	EPA 8270E by SIM	398884
40235062002	**101121003**	EPA 3510	398843	EPA 8270E by SIM	398884
40235060001	**101121001**	EPA 8260	398657		
40235062001	**101121002**	EPA 8260	398658		
40235062002	**101121003**	EPA 8260	398658		
40235060001	**101121001**	EPA 300.0	399430		
40235062001	**101121002**	EPA 300.0	399529		
40235060001	**101121001**	EPA 310.2	399414		
40235062001	**101121002**	EPA 310.2	399414		
40235060001	**101121001**	EPA 353.2	398960		
40235062001	**101121002**	EPA 353.2	398961		

This report shall not be reproduced, except in full,
without the written consent of Pace Analytical Services, LLC.

Pace Analytical
www.pacelabs.com

4 - coolers

CHAIN-OF-CUSTODY / Analytical Request Document

The Chain-of-Custody is a LEGAL DOCUMENT. All relevant fields must be completed accurately.

COC#: 00752-1021-001

QC: ABB 10/13/21

4023506 2

Page: 1 of 3

Section A Required Client Information:		Section B Required Project Information:		Section C Invoice Information:	
Company:	Ramboll	Report To:	GDSdata@ramboll.com	Attention:	Accounts Payable
Address:	234 W. Florida St	Copy To:	Andrew Cawrse	Company Name:	WEC Business Services, LLC
	Milwaukee, WI		Evvan.plank@ramboll.com	Address:	PO Box 19800, Green Bay, WI 54307
Email To:	GDSdata@ramboll.com	Purchase Order No.:	4700004930	Pace Quote Reference:	
Phone:	208-891-2838 Fax:	Project Name:	Stevens Point MGP	Pace Project Manager:	
Requested Due Date/TAT:	standard	Project Number:		Pace Profile #:	

REGULATORY AGENCY

☐ NPDES ☑ GROUND WATER ☐ DRINKING WATER

☐ UST ☐ RCRA ☐ OTHER

Site Location STATE: WI

Requested Analysis Filtered (Y/N)

ITEM #	Section D Required Client Information — SAMPLE ID (A-Z, 0-9 / ,-) Sample IDs MUST BE UNIQUE	Valid Matrix Codes: MATRIX / CODE — DRINKING WATER DW; WATER WT; WASTE WATER WW; PRODUCT P; SOIL/SOLID SL; OIL OL; WIPE WP; AIR AR; OTHER OT; TISSUE TS	MATRIX CODE (see valid codes to left)	SAMPLE TYPE (G=GRAB C=COMP)	COLLECTED: COMPOSITE START DATE	COMPOSITE START TIME	COMPOSITE END/GRAB DATE	COMPOSITE END/GRAB TIME	SAMPLE TEMP AT COLLECTION	# OF CONTAINERS	Preservatives: Unpreserved	H_2SO_4	HNO_3	HCl	NaOH	$Na_2S_2O_3$	Methanol	Other	Y/N	Analysis Test: Benzene (8260B)	*PAHs (8270-SIM)	Alkalinity (310.2)	Sulfate (300.0)	nitrate+nitrite (353.2)	Methane (8015B)	Dissolved Manganese (60	Iron dissolved(6010)	Iron Total(6010)	Residual Chlorine (Y/N)	Pace Project No./ Lab I.D.
																					N	N	N	N	N	N	Y	Y	N		
1	101121 001		WT	G			10/11/21	14:06		12	X	X	X	X							X	X	X	X	X	X	X	X	X		2
2	101121 002		WT	G				14:52		12	X	X	X	X							X	X	X	X	X	X	X	X	X		3
3	101121 003		WT	G				15:33		7	X		X	X							X	X						X	X		3
4	101121 004		WT	G				16:22		12	X	X	X	X							X	X	X	X	X	X	X	X	X		3
5	101121 005		WT	G				16:49		7	X		X	X							X	X						X	X		2
6	101121 006		WT	G				17:27		7	X		X	X							X	X						X	X		2
7	101121 007		WT	G				18:14		7	X		X	X							X	X						X	X		2
8	101121 008		WT	G				18:40		3	X			X							X										1
9	101221 009		WT	G			10/12/21	07:24		12	X	X	X	X							X	X	X	X	X	X	X	X	X		2
10	101221 010		WT	G				08:39		7	X		X	X							X	X						X	X		1
11	101221 011		WT	G				08:44		7	X		X	X							X	X						X	X		1
12	101221 012		WT	G				09:16		7	X		X	X							X	X						X	X		1

E&E 10/11/21

benzene only

001

002

ADDITIONAL COMMENTS	RELINQUISHED BY / AFFILIATION	DATE	TIME	ACCEPTED BY / AFFILIATION	DATE	TIME	SAMPLE CONDITIONS			
*PAHs include benzo[a]anthracene, benxo[a]pyrene, benzo[b]fluroanthene, benzo[k]fluoroanthene, chrysene, dibenzo[a,h]anthracene, fluoranthene, indeno[1,2,3],cd]pyrene, naphthalene, and pyrene	[signature] Thom Gill	10/13/21	12:10	Will Contract Pace	10/13/21	1215	3	Y	N	Y

SAMPLER NAME AND SIGNATURE			
PRINT Name of SAMPLER:	Evvan Plank		
SIGNATURE of SAMPLER:	[signature]	DATE Signed (MM/DD/YY):	10/13/21

Temp in °C	Received on Ice (Y/N)	Custody Sealed Cooler (Y/N)	Samples Intact (Y/N)

*Important Note: By signing this form you are accepting Pace's NET 30 day payment terms and agreeing to late charges of 1.5% per month for any invoices not paid within 30 days.

Pace Analytical Services, LLC
1241 Bellevue Street, Suite 9
Green Bay, WI 54302

Sample Preservation Receipt Form

Client Name: Ramboll Project # 40235062

All containers needing preservation have been checked and noted below: ☐Yes ☐No ☐N/A Initial when completed: DB Date/ Time:

Lab Lot# of pH paper: 10036604 Lab Std #ID of preservation (if pH adjusted):

Pace Lab #	Glass								Plastic					Vials						Jars				General			VOA Vials (>6mm) *	H2SO4 pH ≤2	NaOH+Zn Act pH ≥9	NaOH pH ≥12	HNO3 pH ≤2	pH after adjusted	Volume (mL)
	AG1U	BG1U	AG1H	AG4S	AG4U	AG5U	AG2S	BG3U	BP1U	BP3U	BP3B	BP3N	BP3S	VG9A	DG9T	VG9U	VG9H	VG9M	VG9D	JGFU	JG9U	WGFU	WPFU	SP5T	ZPLC	GN						
001						2				1		2	1				6											✓			✓		2.5 / 5 / 10
002						2						2					6														✓		2.5 / 5 / 10
003																																	2.5 / 5 / 10
004																																	2.5 / 5 / 10
005																																	2.5 / 5 / 10
006																																	2.5 / 5 / 10
007																																	2.5 / 5 / 10
008																																	2.5 / 5 / 10
009																																	2.5 / 5 / 10
010																																	2.5 / 5 / 10
011																																	2.5 / 5 / 10
012																																	2.5 / 5 / 10
013																																	2.5 / 5 / 10
014																																	2.5 / 5 / 10
015																																	2.5 / 5 / 10
016																																	2.5 / 5 / 10
017																																	2.5 / 5 / 10
018																																	2.5 / 5 / 10
019																																	2.5 / 5 / 10
020																																	2.5 / 5 / 10

CK's 10/14/24

Exceptions to preservation check: VOA, Coliform, TOC, TOX, TOH, O&G, WI DRO, Phenolics, Other:_____ Headspace in VOA Vials (>6mm) : ☐Yes ☐No ☐N/A ***If yes look in headspace column**

AG1U	1 liter amber glass
BG1U	1 liter clear glass
AG1H	1 liter amber glass HCL
AG4S	125 mL amber glass H2SO4
AG4U	120 mL amber glass unpres
AG5U	100 mL amber glass unpres
AG2S	500 mL amber glass H2SO4
BG3U	250 mL clear glass unpres

BP1U	1 liter plastic unpres
BP3U	250 mL plastic unpres
BP3B	250 mL plastic NaOH
BP3N	250 mL plastic HNO3
BP3S	250 mL plastic H2SO4

VG9A	40 mL clear ascorbic
DG9T	40 mL amber Na Thio
VG9U	40 mL clear vial unpres
VG9H	40 mL clear vial HCL
VG9M	40 mL clear vial MeOH
VG9D	40 mL clear vial DI

JGFU	4 oz amber jar unpres
JG9U	9 oz amber jar unpres
WGFU	4 oz clear jar unpres
WPFU	4 oz plastic jar unpres
SP5T	120 mL plastic Na Thiosulfate
ZPLC	ziploc bag
GN	

Pace Analytical® 1241 Bellevue Street, Green Bay, WI 54302	Document Name: **Sample Condition Upon Receipt (SCUR)**	Document Revised: 26Mar2020
	Document No.: **ENV-FRM-GBAY-0014-Rev.00**	Author: Pace Green Bay Quality Office

Sample Condition Upon Receipt Form (SCUR)

Project #:

WO# : 40235062

40235062

Client Name: Ramboll

Courier: ☐ CS Logistics ☐ Fed Ex ☐ Speedee ☐ UPS ☐ Waltco
☑ Client ☐ Pace Other: _____

Tracking #: _____

Custody Seal on Cooler/Box Present: ☐ yes ☑ no Seals intact: ☐ yes ☐ no

Custody Seal on Samples Present: ☐ yes ☑ no Seals intact: ☐ yes ☐ no

Packing Material: ☐ Bubble Wrap ☑ Bubble Bags ☐ None ☐ Other _____

Thermometer Used SR - 105 **Type of Ice:** (Wet) Blue Dry None ☑ Samples on ice, cooling process has begun

Cooler Temperature Uncorr: 3.5 /Corr: 3

Temp Blank Present: ☑ yes ☐ no **Biological Tissue is Frozen:** ☐ yes ☐ no

Person examining contents:
Date: 10/14/21 /Initials: DS
Labeled By Initials: SCW

Temp should be above freezing to 6°C.
Biota Samples may be received at ≤ 0°C if shipped on Dry Ice.

Chain of Custody Present:	☑Yes ☐No ☐N/A	1.
Chain of Custody Filled Out:	☐Yes ☑No ☐N/A	2. proj# DS 10/14/21
Chain of Custody Relinquished:	☑Yes ☐No ☐N/A	3.
Sampler Name & Signature on COC:	☑Yes ☐No ☐N/A	4.
Samples Arrived within Hold Time:	☑Yes ☐No	5.
- VOA Samples frozen upon receipt	☐Yes ☐No	Date/Time:
Short Hold Time Analysis (<72hr):	☑Yes ☐No	6.
Rush Turn Around Time Requested:	☐Yes ☑No	7.
Sufficient Volume: For Analysis: ☑Yes ☐No MS/MSD: ☐Yes ☑No ☐N/A		8.
Correct Containers Used:	☑Yes ☐No	9.
-Pace Containers Used:	☑Yes ☐No ☐N/A	
-Pace IR Containers Used:	☐Yes ☐No ☑N/A	
Containers Intact:	☑Yes ☐No	10.
Filtered volume received for Dissolved tests	☑Yes ☐No ☐N/A	11.
Sample Labels match COC:	☑Yes ☐No ☐N/A	12.
-Includes date/time/ID/Analysis Matrix: W		
Trip Blank Present:	☐Yes ☑No ☐N/A	13.
Trip Blank Custody Seals Present	☐Yes ☐No ☑N/A	
Pace Trip Blank Lot # (if purchased): _____		

Client Notification/ Resolution: If checked, see attached form for additional comments ☐

Person Contacted: _____ Date/Time: _____

Comments/ Resolution: _____

PM Review is documented electronically in LIMs. By releasing the project, the PM acknowledges they have reviewed the sample logi

Page 2 of 2