


*Original***CONSTRUCTION PLAN****Practice:** Manure Storage Pond-313, Animal Trail/Walkway 575, Manure Transfer 634**Landowner:** Ron Nerdrum**Address:** W11442 Pine Rd. Stanley, WI 54768**Owner Phone:** 715-644-2132 **County:** CLARK**Township:** Thorp **T** 29 **N** **R** 4W **Section** 20**Field Office:** Neillsville **Office Phone:** (715)-743-5103**DIGGERS  
HOTLINE****Call 3 work  
days before  
you dig****Toll Free**  
1-800-242-8511**TDD**  
1-800-542-2289

▲  
N  
Not to  
scale

**Notice to Landowners and Contractors Regarding Utilities**

No representation is made by the USDA Natural Resources Conservation Service or the Clark County Land Conservation Department as the existence or nonexistence of underground hazards. Prior to the start of construction the owners of utilities must be notified of the pending construction. You will be liable for damages resulting from construction activities.  
**CALL DIGGERS HOTLINE!**

**Construction Drawings and Specifications Acceptance**

I/we have reviewed and accept the attached plans. I/we agree to have this project constructed in accordance with these plans and specifications and to notify all affected utility companies.

Signed: <i>And W. Nerdum</i>	Date: <i>1/26/2012</i>
Designed by: <i>ATP</i>	Date: <i>1/26/2012</i>
Checked by:	Date:
Approved by: <i>Mary King</i>	Date: <i>1/26/2012</i>
Approved by: <i>Mary King - Per email/phone</i>	Date:
Job Approval Class: <i>11, Manure Storage, All, ATP, I, HUAP</i>	

**CONSTRUCTION INSPECTION PLAN  
WASTE STORAGE FACILITY/MANURE TRANSFER  
FOR RON NERDRUM**

**A. INSPECTORS**

The primary field inspectors for this project will be staff from the Clark County LCD office and DATCP. Inspectors will include: Cody Overgard, Engineering Technician II and Patrick Schultz of the DATCP. Inspections will occur at least one every day that the project is under construction. Frequency of inspections will depend on the practice each day. Inspections will occur during the placement of rebar, pouring of concrete, installation of transfer lines, compaction of berms, and other key components.

**B. GENERAL**

**Inspection Schedule**

- 1.) Contractor must inform Technician two days in advance prior to starting project
- 2.) Technician must be given 24 hours notice prior to the final placement of rebar or concrete pour.
- 3.) Contractor must supply Technician with the name of the concrete supplier to ensure the product delivered meets Wis. Const. Spec. 4. Failure to provide proper supplier mix and/or location of plant may result in rejection of concrete at site based on the conditions listed in Wis. Const. Spec. 4.
- 4.) Any and all changes or modifications must be brought to the attention of the inspector prior to any changes or deviations from the original construction plan provided. Failure to receive proper clearance for modifications will result in an unsatisfactory project and may not be approved for use based on the severity of the deviation(s).
- 5.) Contractor must provide Technician with a copy of the DNR Stormwater Permit and a valid and current Digger's Hotline Ticket number prior to starting the project.

The work to be completed on this project shall consist of the following items, with the pertinent construction specifications indicated. All construction specifications can be referenced at the back of the Construction Plan.

- |                                    |                       |
|------------------------------------|-----------------------|
| 1. Excavation                      | Wis. Const. Spec. 2   |
| 2. Earthfill                       | Wis. Const. Spec. 204 |
| 3. Mobilization and Demobilization | Wis. Const. Spec. 7   |
| 4. Critical Area Seeding           | Seeding Sheet 710     |
| 5. Concrete                        | Wis. Const. Spec. 4   |
| 6. Plastic Pipe Conduits           | Wis. Const. Spec. 15  |
| 10. Fencing                        | Wis. Const. Spec. 10  |

This project is designed according to 634, Waste Transfer This is a job class II for Pipe Size,, job class IV for Waste Storage Facility based on wall height, job class I, HUAP. The original plan and subsequent changes to the construction plan must be approved by Mary King, NRCS Engineer

This project will be installed to adhere to all design and implementation standards listed for the project and will be constructed to the best of my professional ability and knowledge. Job approval with be given by Mary King.

The presence or absence of any below ground utilities must be documented in written form by the contractor prior to construction.

### **C. PRECONSTRUCTION CONFERENCE**

A preconstruction conference may be held prior to providing any layout assistance. During the conference the construction plans, construction specifications, layout, required materials, required inspection, installation requirements, safety precautions, utilities, and any information needing clarification by the technical agencies will be discussed.

### **D. MATERIALS REQUIREMENTS**

- Area under tank shall be inspected to ensure proper placement of fill material and removal of all organic materials.
- Document that the earth fill materials are free from organics and are compacted properly.
- Document the final elevations of all excavated tank/tile areas.
- Document the final elevations of the constructed practice.
- Document the type, thickness, and quantities of the pipes to be used.
- Document the topsoil thickness and the proper seeding of disturbed areas.
- Document concrete requirements are met (mix design, rebar grade, curing compound, etc.)

### **E. GENERAL INSPECTION**

#### **1. EXCAVATION**

- a) Check lines and grades as they are constructed and document that the system is installed as planned.
- b) Make sure that oversized rock, and other undesirable materials are removed.
- c) See that adequate drainage is provided so that surface water does not enter pit.
- d) Take safety precautions when working around the trench for the pipe.
- e) Ensure that topsoil is stripped and temporary staked.
- f) Photo of bottom of clean abandoned manure storage

#### **2. EARTHFILL**

- a) Make certain that all organic matter is removed from areas receiving fill prior to placement.
- b) Inspect and document the adequacy of earth fill materials and compaction of the berm.
- c) Make sure that the thickness of the loose lift is within limits.
- d) Determine need for wetting, drying, or mixing of fill material to satisfy moisture requirements.
- e) Check lines and grades as they are constructed and document that the system is installed as planned.
- f) Photo of 6" lifts in berm construction of old and new storages.

3. TRANSFER PIPE

- a) Determine that the specified size, thickness and quality of all pipe sections and fittings have been delivered.
- b) See that trench excavations conform to lines and grades specified.
- c) Check that each section of pipe is prepared, placed, joined, sealed, and supported as specified.
- d) Take extra care to ensure that the trench through pond side is compacted properly and with good material for at a distance of ten feet from the inside face of the storage.
- e) Determine that the quality of the backfill material is adequate.
- f) Confirm proper cover is achieved with respect to freezing. Insulation may be needed if cover depth is less than 4'.

4. CONCRETE

- a) Make sure of location prior to placement
- b) Make sure that concrete meets Spec 4.
- c) Make sure proper curing compound is applied to concrete in a timely manner.
- d) Make sure rebar spacing is correct and of proper size.
- e) Make sure concrete is protected during freezing.
- f) Ensure ties for tank are break back and sealed with epoxy.
- g) Make sure White Curing Compound ASTM 309-C Type II is used for flatwork and tank.

5. VEGETATION

- a) Check that the placement of topsoil is adequate for a viable seedbed.
- b) Verify that the proper species and quantities of seed are applied.
- c) Check that the seed is planted at the proper time of the year and that mulch is applied.
- d) Verify that proper erosion control practices are installed
- e) The soils for seed base must be verified to ensure soils do not require the addition of lime or other fertilizer.

**F. CONSTRUCTION APPROVAL**

Construction approval will be provided by Mary King. Any changes must be approved by Mary King prior to construction in writing and documented fully.

## Emergency Action Plan-Ron Nerdrum

**In the event that the landowner's manure storage is above the MOL (El. 105.3) the following will occur.**

- 1.) Landowner will pump and remove manure and haul onto fields approved for hauling during that particular time of year. This is based on NMP planning.
- 2.) Landowner will develop long range action plan to remedy the situation.
- 3.) Landowner will not agitate pit to prevent a discharge.

**In the event that the landowner's manure storage is overflowing (El. 107.0) the following will occur.**

- 1.) Landowner will call Wisconsin DNR Hotline to report the discharge immediately.
- 2.) Landowner will contact Clark County Land Conservation Dept. immediately.
- 3.) Landowner will try to prevent overflow from reaching critical areas such as: wells, wetlands, streams, waterways, property lines, or road ditches. This can be done using straw or hay bales to block flow. Earthen berms may also be constructed in addition to some tillage methods.
- 4.) Landowner must remove some volume to ensure overtopping does not continue.
- 5.) Landowner should contact local farmers with storages to inquire about additions to their facility in an emergency situation.
- 6.) Landowner will list reasons for the overflow and work to correct the issue in a timely manner.
- 7.) Should a transfer line/pump break or malfunction the above shall be followed as well.

Landowner Signature \_\_\_\_\_ Date \_\_\_\_\_

Technician's Signature \_\_\_\_\_ Date \_\_\_\_\_

## Construction Quality Assurance Plan

1. No practice should be started that cannot be finished by November 1<sup>st</sup>.
2. All cost-shared practices will be surveyed, designed, constructed, and certified complete in accordance with the Natural Resources Conservation Service Field Office Technical Guide standards and specifications.
3. The LCD staff will inspect construction of all Land and Water Resource Management Program cost-shared practices. The job inspector will reject any materials and supplies that do not meet the standards or specification as stated in the Field Office Technical Guide.
4. It is the responsibility of the contractor to verify that materials and supplies used for installation of a cost shared practice meets Technical Guide standards and specifications. The contractor must provide sales slips, batch slips, invoices, specification tags, etc., that clearly show that the materials and supplies meet the Field Office Technical Guide standards and specifications.
5. Initial practice layout and staking of elevations will be done by LCD staff prior to the start of construction. Any further checking of practice layout or elevations will be performed by the contractor during construction. The accuracy of final grades prior to pouring concrete, setting pipe, etc., is the responsibility of the contractor. The LCD may perform further construction checks if necessary to determine adherence with the approved design plan.
6. Notification, location, and protection of public utilities such as buried phone lines and gas lines are the responsibility of the landowner. The landowner shall clearly mark the location of such utilities prior to the start of construction. The contractor is responsible for knowing the location of any utilities marked by the landowner and should take precautions when working near them.
7. Project will not be considered complete until all seeding, fertilizing and mulching is done.

### ADDITIONAL CONSIDERATIONS:

- Cattle must be removed from the construction site during stake out and construction.
- The landowner shall remove all fences before construction begins.
- The landowner shall remove manure piles from the work area before construction begins.
- The landowner shall provide areas to obtain material for fill and top-dressing.

\_\_\_\_\_ Landowner signature \_\_\_\_\_ Date

## Operation and Maintenance Plan Waste Storage Facility

Cooperator: \_\_\_\_\_

Date: \_\_\_\_\_

By: \_\_\_\_\_

Title: \_\_\_\_\_

Project Location: \_\_\_\_\_

I agree to the following for the next 15 years.

The facility is sized for:

Storage Duration:	213 Days
Animals:	
Lactating Cows:	32
Dry Cows:	_____
Young Stock:	10
Total Animal Units:	_____ A.U.s
Milkhouse Wastewater:	160 Gallons/Day
Barnyard/Feedlot:	0 Square Feet

1. Inspect the facility periodically.

A thorough inspection of concrete, clay or geosynthetic liners, and concrete sumps, pits, walls, ramps, slats, and floors often for separations and/or cracks which would indicate potential failure should be made each time the pond is emptied. Repairs should be made immediately.

2. Pipes, pumps, manure pumps, valves, gates, etc., should be inspected periodically (minimum of twice a year) to make sure they are functional, structurally sound, and not cracked, broken, and/or a safety hazard to the operator or livestock. Repair as needed.
3. Cut and remove weeds, shrubs, and trees from earthen structures. Control rodents. Mow the embankments a minimum of twice a year. Good vegetative cover should be maintained on earth embankments. If the vegetative cover is damaged, embankments should be re-vegetated as soon as possible. Keep machinery away from steep side slopes. Keep equipment operators informed of all potential hazards.
4. Maintain necessary safety features including proper fencing, warning signs, stop blocks, guard rails, covers, and similar items to provide warning and/or prevent unauthorized human or livestock entry.
5. Handling Manure

Do not allow human entry into any enclosed structure without safety equipment including ladders and breathing apparatus. The American Society Agricultural and Biological Engineers (ASABE) standard EP-470 states:

*"Do not enter an under-floor (underground) covered storage or pumping station without using the proper respirator equipment. In addition, these safety practices are needed: (a) Shut off any manure pumps, (b) ventilate storage or pumping station at the maximum rate, (c) test the storage or station air for O<sub>2</sub> level and toxic gas levels, (d) attach a safety harness and*

Wendrum 39 of 65

*rope to the working person with at least one person standing by to help with a mechanical retrieval device, and (e) have on hand an extra set of proper respirator equipment for the person standing by."*

A. Hopper/Tank

- 1) Avoid scraping dry or frozen manure into hopper.
- 2) Use only minimal amounts of bedding when pumps are used.
- 3) Maintain all lids, grates, and shields on openings to underground structures.

B. Storage

- 1) Begin filling facility early enough in fall to cover inlet pipe opening to avoid freezing.
- 2) Maintain the depth gauge that visually shows the following elevations
  - a. Temporary Benchmark description (TBM) Top of silo footing
  - b. TBM elevation 100.0
  - c. Maximum operating level (MOL) 105.3
  - d. Top of freeboard volume 106.3
- 3) Begin emptying or drawdown according to the schedule in the CNMP or sooner if the contents of the storage facility reach the maximum operating level (MOL)  
MOL description: 4in concrete bump in ramp.

C. Emptying

- 1) Immediately remove all foreign debris within the structure that may cause damage to pumps or agitators.
- 2) Agitate properly according to pump manufacturer's instructions.
- 3) Minimize odors by not mixing and spreading on humid days or upwind from nearby neighbors.
- 4) Periodically remove solid accumulation on bottom of pit.

D. Waste Utilization

- 1) Manure application must comply with state laws or local ordinances, and the nutrient management plan.

6. Inspect the outlet of any artificial drainage system installed to lower a perched seasonal high water table adjacent to the waste storage facility. The inspections should occur at least twice a year: once during the high water table season to ensure that water is flowing indicating the system is operation [not blocked] and once during the dry season to ensure there is no direct leakage from the storage facility into the drainage system that may be indicated by high flow rate, turbidity, discoloration, odors or other unusual characteristics of the flow. Immediately investigate any indication of blockage or leakage and consult a qualified individual for any corrective needed.

7. Additional Recommendations:

Cooperator's signature: \_\_\_\_\_

Date: \_\_\_\_\_

I have discussed the maintenance guidelines with the above cooperator.

Conservationist's signature: \_\_\_\_\_

Date: \_\_\_\_\_

*Verdrum 40 of 65*



## Operation and Maintenance Plan Manure Transfer

Cooperator: \_\_\_\_\_ Date: \_\_\_\_\_

By: \_\_\_\_\_ Title: \_\_\_\_\_

Project Location: \_\_\_\_\_

I agree to the following for the next 15 years.

1. Maintain all pumps, agitators, pipes, valves, electrical and mechanical equipment in good operating condition following the manufacturer's recommendations.
2. Make certain that all electrical equipment is properly grounded and wiring is in good working condition.
3. Maintain all safety shields on pumps, motors, electrical or mechanical equipment.
4. All fencing, railings, grates and/or warning signs shall be maintained to prevent unauthorized human or livestock entry.
5. Reception pits or hoppers should not be entered because they may contain noxious gases. When it becomes necessary for someone to enter one for repairs, follow ASABE Standard 470.
6. Immediately repair any vandalism, vehicular or livestock damage to the system.
7. Repair spalls, cracks and weathered areas in concrete surfaces.
8. Repair or replace rusted or damaged metal. Protect with paint.
9. Operate system in a manner that minimizes odor and air drift.
10. Additional Recommendations:

Cooperator's signature: \_\_\_\_\_ Date: \_\_\_\_\_

I have discussed the maintenance guidelines with the above cooperator.

Conservationist's signature: \_\_\_\_\_ Date: \_\_\_\_\_

## Operation and Maintenance Plan Animal Trails and Walkways

Cooperator: \_\_\_\_\_ Date: \_\_\_\_\_

By: \_\_\_\_\_ Title: \_\_\_\_\_

Project Location: \_\_\_\_\_

I agree to the following for the next 15 years.

1. Inspect annually and after significant storm events. Maintain the surface in a good condition, which includes periodic grading or repair of the surface and resurface with new material as needed.
2. Prevent ponding by grading to remove depressions and allowing surface water to drain off the travel area of the trail or walkway. Fill low areas and re-grade, as needed, to maintain trail cross section.
3. Limit livestock usage to periods that minimize damage.
4. If fences are installed, they shall be maintained to contain livestock on travel lane. If portable fence is used, be sure to take proper winterization steps.
5. Eradicate or otherwise remove all burrowing animals. Immediately repair any damage caused by their activity.
6. Remove debris from bridge and culvert openings to prevent blockage of stream crossings.
7. Immediately repair any damage to any earth or gravel fills, culverts, diversion, water-bars, or other appurtenances.
8. Remove manure or organic accumulation and re-grade the surface at least twice per year.
9. Periodically mow vegetation adjacent to walkway to prevent establishment of woody vegetation. Reseed areas where vegetation has been damaged or destroyed.
- 10 Additional Recommendations:

Cooperator's signature: \_\_\_\_\_ Date: \_\_\_\_\_

I have discussed the maintenance guidelines with the above cooperator.

Conservationist's signature: \_\_\_\_\_ Date: \_\_\_\_\_

Top of Pit --- El.107.0  
 Bottom of Pit -- El.97.0  
 Top Dimensions -- 80'x50'  
 Bottom Dimensions-- 80'x50'  
 Pit Depth --- 10.0'  
 Berm Width --- Varies  
 Designed Capacity -- 24,440 cu.ft.  
 Designed Storage -- 213 days  
 Outside Slopes --- 1:1-3:1

50' x 80' x 10' Vertical  
 Wall Concrete Manure Pit  
 w/ramp. Capacity to MOL  
 224,115 gal.

The concrete storage wall will consist of a 10'  
 T-wall design.

A county variance will be required due to the  
 300' stream setback prior to the start of  
 construction.



Concrete floor of waste storage facility shall be  
 8" thick with #4 rebar 18" OC

O&M will address the cleaning of the animal  
 trail and walkway.


- LEGEND**
- Temporary Bench Mark-----
  - Soil Test Pit-----
  - Center Line-----
  - Property Line-----
  - Setback Line-----
  - Fence, existing-----
  - Fence, to be installed-----
  - Fence, to be removed-----
  - Concrete, existing-----
  - Concrete, to be installed-----
  - Finished Grade Line-----
  - Contour Line-----
  - Well-----
  - Station Pt.-----
  - Tile Line-----
  - Power Pole-----
  - Giddings Soil Boring -----

Construct earthen ramp to be 20ft wide and at  
 6:1 away from the berm.  
 Side slopes are to be 3:1 or less.

TBM 1= Located on the silo footing EL. 100.0



**GRAPHIC SCALE**




Seeding will occur within  
 2 days after construction  
 is complete

WASTE STORAGE POND Ron Nerdrum T.26N. R.1E. Sec.25 Township of Thorp, Clark Co, WI.			
Clark County		Land Conservation Department	
Designed By	Date	Approved By	Date
Drawn		Title	
Checked		Sheet No.	Drawing No.

Nerdrum 43 of 65



### Cross Section A-A'




Concrete	4,000	psi	for	walls
Concrete	4,000	psi	for	flatwork

WASTE STORAGE POND  
Ron Nerdrum  
T.26N. R.1E. Sec.25  
Township of Thorp, Clark Co, Wi.

Clark County Land Conservation  
Department

Designed <u>cau</u>	Date _____	Approved By _____	Date _____
Drawn _____	_____	Title _____	_____
Checked _____	_____	Title _____	_____
Sheet No. _____		Drawing No. _____	

# Cross Section B-B'




Concrete 4,000 psi for walls  
Concrete 4,000 psi for flatwork


WASTE STORAGE POND Ron Nerdrum T.26N. R.1E. Sec.25 Township of Thorp, Clark Co, Wi.			
Clark County		Land Conservation Department	
Designed <i>Ch</i>	Date	Approved By	Date
Drawn		Title	
Checked		Sheet No. of	Drawing No.

Nerdrum 95 of 65

Concrete	4,000	psi	for walls
Concrete	4,000	psi	for flatwork



Verdictum 46 of 65




WASTE STORAGE POND  
 Ran Nerdrum  
 T.26N. R.1E. Sec.25  
 Township of Thorp, Clark Co., WI.

Clark County  
 Land Conservation  
 Department

Designed	By	Date	Approved	Date

Sheet No. of








# Manure Pump Hopper and Pipe Installation Details

Installation of Piston Pump/Hopper will require #4 rebar Grade 60 to be placed 12" □-C around the hopper. Approx. 4.5 yards of 4000 psi concrete will be required to secure hopper in place. Rebar is to be bent around pump and transfer pipe. Minimum 15" bar overlap.

See Technician for more details.




WASTE STORAGE POND  
Ron Nerdrum  
T.26N. R.1E. Sec.25  
Township of Thorp, Clark Co. WI.

Clark County  
Land Conservation  
Department


Designed	Date	Approved	Date
By		By	
Drawn		Title	
Checked		Scale	
		Sheet	
		No.	
		of	
		Drawing No.	

# Transfer Pipe Bedding Detail




Backfill is to be compacted in 6" lifts according to Wis. Const. Spec. 204 Plastic Pipes to Follow Wis. Cons. Specs. #15.

Ron Nardum  
owner  
Clark LCC, WI.  
county  
designed CDO checked  
sheet \_\_\_ of \_\_\_



ISOMETRIC VIEW



QUANTITY ESTIMATES

CONCRETE WCS #4 \_\_\_\_\_ CU. YDS.  
 (WISCONSIN CONSTRUCTION SPECIFICATION)  
 STEEL \_\_\_\_\_ LBS.  
 SAND/GRAVEL \_\_\_\_\_ CU. YDS.

NOTES:

1. SEE SHEET \_\_\_\_\_ OF \_\_\_\_\_ FOR JOINT DETAILS.
2. BAR SPLICES SHALL BE 12 INCHES MINIMUM.

$f_c = 4,000$   
 $f_y = 60,000$   
 REQUIRED SPLICE LENGTH = 18"



CONCRETE SLAB REINFORCEMENT  
 DEFORMED STEEL

CLIENT: *Ken Nordrum*

COUNTY: *Ken*


Date \_\_\_\_\_  
 Designed *CS*  
 Drawn *CS*  
 Checked \_\_\_\_\_  
 Approved \_\_\_\_\_

File Name  
 WI-565

Date  
 9/10

Sheet of

*Nordrum 51 of 65*



CROSS SECTION OF WALL AT WATERSTOP JOINT

QUANTITIES

6" WATERSTOP See Plan \_\_\_\_\_ LIN.FT.

CONSTRUCTION NOTES:

1. FACTORY CORNERS AND TRANSITIONS SHALL BE USED, LEAVING ONLY STRAIGHT BUTT JOINT SPLICES FOR FIELD WELDING.
2. SEE DWG WI-506, SHEET \_\_\_, FOR FACTORY TRANSITIONS NEEDED.
3. SEE JOINT PLAN, SHEET \_\_\_, FOR LOCATIONS OF JOINTS.

INSTALLATION:

- A. CENTER THE WATERSTOP ON THE JOINT.
- B. SECURE THE WATERSTOP ALONG ITS LENGTH AT THE CENTER BULB AND SUFFICIENTLY AT THE WEB TO HOLD IT IN PLACE.
- C. PLACE CONCRETE WITHOUT DISPLACING THE WATERSTOP.
- D. THOROUGHLY VIBRATE CONCRETE AROUND WATERSTOP TO PREVENT VOIDS.
- E. AFTER THE FIRST POUR, CLEAN THE UNEMBEDDED WATERSTOP WEB TO INSURE FULL CONTACT WITH THE SECOND POUR OF CONCRETE.
- F. INSTALLATION METHODS SHALL BE IN STRICT COMPLIANCE WITH THE MANUFACTURERS REQUIREMENTS.

SEE REVERSE SIDE FOR  
ADDITIONAL INFORMATION



**6" EMBEDDED WATERSTOP  
FOR WALL SECTIONS ONLY**

CLIENT: Ron Nordrum  
COUNTY: Clark

Date \_\_\_\_\_  
Designed CAD  
Drawn CAD  
Checked \_\_\_\_\_  
Approved \_\_\_\_\_

Drawing No.  
WI-505A  
Date  
6/07  
Sheet of

*Nordrum 52 of 65*



SPECIFICATIONS:

- A. WORK CONSISTS OF PROVIDING FLEXIBLE WATERSTOPS, EMBEDDED IN CONCRETE WALLS, TO SPAN CONTROL AND/OR CONSTRUCTION JOINTS.
- B. WATERSTOP MUST FORM A CONTINUOUS SEAL THROUGHOUT THE STRUCTURE.
- C. WATERSTOP IS TO BE MANUFACTURED PVC, THERMOPLASTIC ELASTOMERIC RUBBER, (TPE), OR POLYETHYLENE P.E. MATERIAL WITH A MINIMUM WEB THICKNESS OF 3/16".
- D. WATERSTOP IS TO BE FREE OF DIRT, OIL, AND DEFECTS.
- E. REINFORCING STEEL SHALL NOT PASS THROUGH CONTROL JOINTS.

SPLICE FABRICATION:

- A. PROVIDE FACTORY FABRICATED WATERSTOP CORNERS AND TRANSITIONS LEAVING ONLY STRAIGHT BUTT JOINT SPLICES FOR FIELD FABRICATION, UNLESS SPECIFICALLY APPROVED IN WRITING BY THE MANUFACTURER AND PERFORMED IN ACCORDANCE WITH THEIR SPECIFICATIONS.
- B. USE ONLY A SPLICING IRON SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR HEAT FUSED WELDING OF ALL SPLICES.
- C. WELDS ARE TO EXHIBIT A CONTINUOUS BEAD OF EXCESS MELTED MATERIAL, FREE OF DEFECTS.
- D. SPLICES ARE TO BE HEAT WELDED WITH THE CENTER BULB AND RIBS ALIGNED.
- E. ADHESIVES, SOLVENTS, LAP JOINTS, AND EDGE WELDING ARE NOT ACCEPTABLE.
- F. EMBEDDED WATERSTOPS MAY NOT BE WELDED OR JOINED TO OTHER WATERSTOPS OF DIFFERENT SIZE, CONFIGURATION, OR MATERIAL.





#### CONSTRUCTION NOTES

1. THESE JOINT DRAWINGS ARE TO BE ADAPTED TO A SPECIFIC STRUCTURE OR SYSTEM. FOR THE JOINT LOCATION PLAN SEE SHEET \_\_\_\_.
2. WATERSTOP DIMENSIONS SHALL BE BASED ON MANUFACTURER'S REQUIREMENTS FOR MINIMUM COVER.
3. THE WATERSTOP SHALL BE APPLIED TO EVEN SURFACES, FREE OF DIRT, OIL, OR LAITANCE.
4. THE WATERSTOP MUST BE BONDED TO THE CONCRETE AND/OR PIPE PRIOR TO PLACEMENT OF ADJOINING CONCRETE.
5. THE MANUFACTURER'S INSTALLATION INSTRUCTIONS SHALL BE FOLLOWED FOR WATERSTOP SPLICING AND ADDITIONAL INSTALLATION REQUIREMENTS.



#### LIQUID TIGHT PIPE PENETRATIONS

CLIENT:

COUNTY:


*Ken Nordrum*  
*Clark*

Designed *CDO* Date \_\_\_\_\_  
Drawn *RSO*  
Checked \_\_\_\_\_  
Approved \_\_\_\_\_

File Name Date  
WI-509 6/07

Sheet of

*Nordrum 59 of 65*



#### CROSS SECTION OF WALL OR SLAB AT WATERSTOP JOINT

#### QUANTITIES

6" WATERSTOP----- Scaplan LIN FT

1/2" EXPANSION MATERIAL----- \_\_\_\_\_ LIN FT

#### CONSTRUCTION NOTES:

1. FACTORY CORNERS AND TRANSITIONS SHALL BE USED, LEAVING ONLY STRAIGHT BUTT JOINT SPLICES FOR FIELD WELDING.
2. SEE DWG WI-506, SHEET \_\_\_, FOR FACTORY TRANSITIONS NEEDED.
3. SEE JOINT PLAN, SHEET \_\_\_, FOR LOCATIONS OF JOINTS.

#### INSTALLATION:

- A. CENTER THE WATERSTOP ON THE JOINT.
- B. SECURE THE WATERSTOP ALONG ITS LENGTH AT THE CENTER BULB AND SUFFICIENTLY AT THE WEB TO HOLD IT IN PLACE.
- C. PLACE CONCRETE WITHOUT DISPLACING THE WATERSTOP.
- D. THOROUGHLY VIBRATE CONCRETE AROUND THE WATERSTOP TO PREVENT VOIDS.
- E. AFTER THE FIRST POUR, CLEAN THE UNEMBEDDED WATERSTOP WEB TO INSURE FULL CONTACT WITH THE SECOND POUR OF CONCRETE.
- F. KEEP THE CENTER BULB UNEMBEDDED AT THE JOINT CENTERLINE.
- G. INSTALLATION METHODS SHALL BE IN STRICT COMPLIANCE WITH THE MANUFACTURER'S REQUIREMENTS.

SEE REVERSE SIDE FOR  
ADDITIONAL INFORMATION



#### 6" EMBEDDED WATERSTOP WITH EXPANSION JOINT MATERIAL FOR WALLS AND SLABS

CLIENT: Ron Neff  
COUNTY: Chad

Designed <u>SC</u>	Date	Drawing No. WI-505B
Drawn <u>SC</u>		Date 6/11
Checked		
Approved		Sheet of

Ner Neff 55-165


SPECIFICATIONS:

- A. WORK CONSISTS OF PROVIDING FLEXIBLE WATERSTOPS, EMBEDDED IN CONCRETE, TO SPAN CONTROL, CONSTRUCTION, AND/OR ISOLATION JOINTS.
- B. WATERSTOP MUST FORM A CONTINUOUS SEAL THROUGHOUT THE STRUCTURE.
- C. WATERSTOP IS TO BE MANUFACTURED PVC, THERMOPLASTIC ELASTOMERIC RUBBER, (TPE), OR POLYETHYLENE P.E. MATERIAL WITH A MINIMUM WEB THICKNESS OF 3/16".
- D. WATERSTOP IS TO BE FREE OF DIRT, OIL, AND DEFECTS.
- E. REINFORCING STEEL SHALL NOT PASS THROUGH CONTROL JOINTS.

SPLICE FABRICATION:

- A. PROVIDE FACTORY FABRICATED WATERSTOP CORNERS AND TRANSITIONS LEAVING ONLY STRAIGHT BUTT JOINT SPLICES FOR FIELD FABRICATION, UNLESS SPECIFICALLY APPROVED IN WRITING BY THE MANUFACTURER AND PERFORMED IN ACCORDANCE WITH THEIR SPECIFICATIONS.
- B. USE ONLY A SPLICING IRON SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR HEAT FUSED WELDING OF ALL SPLICES.
- C. WELDS ARE TO EXHIBIT A CONTINUOUS BEAD OF EXCESS MELTED MATERIAL, FREE OF DEFECTS.
- D. SPLICES ARE TO BE HEAT WELDED WITH THE CENTER BULB AND RIBS ALIGNED.
- E. ADHESIVES, SOLVENTS, LAP JOINTS, AND EDGE WELDING ARE NOT ACCEPTABLE.
- F. EMBEDDED WATERSTOPS MAY NOT BE WELDED OR JOINED TO OTHER WATERSTOPS OF DIFFERENT SIZE, CONFIGURATION, OR MATERIAL.





NOTE: THE SLAB OR WALL THICKNESS AT THE JOINT  
MUST BE GREATER THAN OR EQUAL TO 8".

SLAB THICKNESS = \_\_\_\_"  
SLAB THICKNESS  
AT JOINT = \_\_\_\_"  
OR  
WALL THICKNESS = \_\_\_\_"

#### CROSS SECTION OF WALL OR SLAB AT WATERSTOP JOINT

#### QUANTITIES

6" WATERSTOP - - - - - \_\_\_\_ LIN.FT.      STEEL DOWELS - - - - - \_\_\_\_ EACH  
DOWEL SLEEVES - - - - - \_\_\_\_ EACH

#### CONSTRUCTION NOTES:

1. FACTORY CORNERS AND TRANSITIONS SHALL BE USED, LEAVING ONLY STRAIGHT BUTT JOINT SPLICES FOR FIELD WELDING.
2. SEE DWG WI-506, SHEET \_\_\_, FOR FACTORY TRANSITIONS NEEDED.
3. SEE JOINT PLAN, SHEET \_\_\_, FOR LOCATIONS OF JOINTS.

#### INSTALLATION:

- A. POSITION THE WATERSTOP AND DOWEL AS SHOWN IN THE DRAWING.
- B. SECURE THE WATERSTOP ALONG ITS LENGTH AT THE CENTER BULB AND SUFFICIENTLY AT THE WEB TO HOLD IT IN PLACE.
- C. FOLLOW THE MANUFACTURERS RECOMMENDATIONS TO INSTALL THE DOWEL AND SLEEVE.
- D. PLACE CONCRETE WITHOUT DISPLACING THE WATERSTOP.
- E. THOROUGHLY VIBRATE CONCRETE AROUND THE WATERSTOP TO PREVENT VOIDS.
- F. AFTER THE FIRST POUR, CLEAN THE UNEMBEDDED WATERSTOP WEB TO INSURE FULL CONTACT WITH THE SECOND POUR OF CONCRETE.
- G. INSTALLATION METHODS SHALL BE IN STRICT COMPLIANCE WITH THE MANUFACTURER'S REQUIREMENTS.

SEE REVERSE SIDE FOR  
ADDITIONAL INFORMATION



#### 6" EMBEDDED WATERSTOP WITH STEEL DOWELS FOR WALLS AND SLABS

CLIENT: Bon Nordrum  
COUNTY: Chula

Designed COO Date \_\_\_\_\_  
Drawn ma  
Checked \_\_\_\_\_  
Approved \_\_\_\_\_

Drawing No.  
WI-505D  
Date  
6/11  
Sheet \_\_\_\_ of \_\_\_\_

*Nordrum 57 of 65*

SPECIFICATIONS:

- A. WORK CONSISTS OF PROVIDING FLEXIBLE WATERSTOPS, EMBEDDED IN CONCRETE, TO SPAN CONTROL AND/OR CONSTRUCTION JOINTS.
- B. WATERSTOP MUST FORM A CONTINUOUS SEAL THROUGHOUT THE STRUCTURE.
- C. WATERSTOP IS TO BE MANUFACTURED PVC, THERMOPLASTIC ELASTOMERIC RUBBER, (TPE), OR POLYETHYLENE P.E. MATERIAL WITH A MINIMUM WEB THICKNESS OF 3/16".
- D. WATERSTOP IS TO BE FREE OF DIRT, OIL, AND DEFECTS.
- E. REINFORCING STEEL SHALL NOT PASS THROUGH CONTROL JOINTS.

SPLICE FABRICATION:

- A. PROVIDE FACTORY FABRICATED WATERSTOP CORNERS AND TRANSITIONS LEAVING ONLY STRAIGHT BUTT JOINT SPLICES FOR FIELD FABRICATION, UNLESS SPECIFICALLY APPROVED IN WRITING BY THE MANUFACTURER AND PERFORMED IN ACCORDANCE WITH THEIR SPECIFICATIONS.
- B. USE ONLY A SPLICING IRON SPECIFICALLY RECOMMENDED BY THE MANUFACTURER FOR HEAT FUSED WELDING OF ALL SPLICES.
- C. WELDS ARE TO EXHIBIT A CONTINUOUS BEAD OF EXCESS MELTED MATERIAL, FREE OF DEFECTS.
- D. SPLICES ARE TO BE HEAT WELDED WITH THE CENTER BULB AND RIBS ALIGNED.
- E. ADHESIVES, SOLVENTS, LAP JOINTS, AND EDGE WELDING ARE NOT ACCEPTABLE.
- F. EMBEDDED WATERSTOPS MAY NOT BE WELDED OR JOINED TO OTHER WATERSTOPS OF DIFFERENT SIZE, CONFIGURATION, OR MATERIAL.

## SEEDING DATES

TIME PERIOD	DATES			TYPE OF SEEDING
Spring	April 15	through	June 1	Permanent
Summer	June 2	through	July 31	Temporary *
Late Summer	August 1	through	August 21	Permanent
Fall	August 22	through	October 15	Temporary *
Late Fall	November 1	through	Snow Cover	Dormant
Winter	No Snow Cover	through	April 14	Frost Seed

## MATERIALS

No Application Of Lime Required On This Site.(Soils Test shown none required)

No fertilizer is required.(Soils Test shows none required.)

Mulch with 1-1/2 tons per acre of straw or hay reasonably free from grain and weed seed. If other mulch materials are used, the rate of application shall meet the manufacturer's recommendations.

\* Seed a temporary cover crop of Oats at a rate of 3 bushels/acre.

A permanent seeding shall be completed during the next acceptable time period following a temporary seeding.

## MINIMUM PURE LIVE SEED (PLS)<sup>1</sup> RATE PER ACRE AND TOTAL POUNDS OF SEED NEEDED

SEEDING MIX 5			SEEDING MIX #5 x 150%		
LOCATION - Area ACRES - 2.0			LOCATION - Area ACRES - 2.0		
SPECIES	RATE (Per Acre)	POUNDS Required	SPECIES	RATE (Per Acre)	POUNDS Required
Kentucky Bluegrass	4 lbs.	8 lbs.	Kentucky Bluegrass	6 lbs.	12 lbs.
Creeping Red Fescue	3 lbs.	6 lbs.	Creeping Red Fescue	4.5 lbs.	9.0 lbs.
Winter Rye * (Cover Crop)	1.5 bu	3.0	Winter Rye * (Cover Crop)	2.25 bu	4.5

1. PLS = (% Germination X % Purity)

## SEEDBED PREPARATION

During the recommended seeding periods, seedbed preparation shall immediately follow construction activities. Prepare a fine, firm seedbed to a minimum depth of 3 inches.

## SEEDING

Inoculate legumes with the specific inoculum for the species in accordance with the manufacturer's recommendations. When using a hydroseeder, five times the recommended rate of inoculant shall be added to the hydroseeder. Inoculant shall not be mixed with liquid fertilizer. Seed grasses and legumes no more than 1/4 inch deep. Seed may be broadcast or drilled as appropriate to the site. Seeding shall be done prior to mulching, except for dormant seedings.

## MULCHING

Mulching is required..

Landowner <u>RON NERDRUM</u>		
<u>CLARK COUNTY</u>		
INTRODUCED SPECIES SEEDING ESTABLISHMENT Central Region		
U.S. DEPARTMENT OF AGRICULTURE NATURAL RESOURCES CONSERVATION SERVICE		
Date Designed <u>      </u>	Date Drawing No. <u>WI-710</u> modified <u>7/02</u>	Date <u>      </u>
Checked <u>      </u>	Sheet No. <u>      </u>	of <u>      </u>


Nerdrum 59 of 65



## Woven Wire Fence

### NOTES:

- 1) Woven wire and clips or fasteners to be 14 gauge or heavier.
- 2) Top and bottom wires in woven wire to be 11 gauge or heavier.
- 3) Woven Wire less than 32 inches high needs 2 strands of barbed wire above the woven wire.
- 4) Woven wire higher than 32 inches only needs 1 strand above the woven wire.
- 5) Barbed wire is to be two twisted strands of 12 1/2 ga. or heavier. Barbs to be 14 ga. or heavier and on approx. 5 inch centers.




Not to Scale

## Cattle Panel Fence

### NOTES:

- 1) A strand of barb wire should be placed above the cattle panels.
- 2) Barbed wire is to be two twisted strands of 12 1/2 ga. or heavier. Barbs to be 14 ga. or heavier and on approx. 5 inch centers.




Not to Scale

## General Notes

- 1) Wood posts are to be treated pine or untreated white oak ( min. dia. 3")
- 2) Woven wire or cattle panels are to be fastened at bottom, middle, and top as a minimum.
- 3) Fencing to be on outside of posts along curves and areas being protected.
- 4) Steel Posts to have minimum length of 5 1/2 ft. with a minimum depth of 1 1/2 ft.
- 5) Wood Posts to have minimum length of 6 1/2 ft. with a minimum depth of 2 ft.

## High-Tensile Wire Fence



Not to Scale

- NOTES: 1) Fence shall not allow passage of a 6 inch sphere between any fence member.
- 2) Wire shall be galvanized smooth high tensile class III steel, min. of 14 gauge in diameter.

## Fencing Options

WASTE STORAGE POND  
Ron Nerdum  
T.26N. R.1E. Sec.25  
Township of Thorp, Clark Co., WI.

Clark County Land Conservation Department

Designed	_____	Date	_____	Approved By	_____	Date	_____
Drawn	_____			Title	_____		
Checked	_____			Title	_____		
				Sheet No. _____ of _____		Drawing No.	_____

Nerdum 60 of 65



THIS IS ONLY AN EXAMPLE OF THE TYPE OF SIGN THAT MUST BE POSTED AROUND THE FACILITY. OTHER COMMERCIALY AVAILABLE SIGNS MAY BE USED.



MANURE STORAGE PIT  
WARNING SIGNS

CLIENT: Ron Nordrum  
COUNTY: Clark

Date \_\_\_\_\_  
Designed CPD  
Drawn CPD  
Checked \_\_\_\_\_  
Approved \_\_\_\_\_

Drawing Name  
WI-596A  
Date  
5/2008  
Sheet of \_\_\_\_\_

Nordrum 61 of 65

## SOIL INVESTIGATION LOG

LANDOWNER	Ron Wendrum	COUNTY	Clark
LEGAL DESC.		PRACTICE	213
HOLE NO.	1	STATION	8
SURFACE ELEVATION	99.32	DATE	8/30/11
LOGGED BY	C. Overst		

DEPTH -FT	USCS	DESCRIPTION OF MATERIALS
0-8"	ML	Topsoil, silt/loam
8'-30"	ML	silt cap, silt/loam
30"-60"	SC	gravel, orange sand mix / some red fill 3-5% cobbles
60"-9'	SM	orange sand, coarse, wet
9'-12'	SM	orange sand, mottled, fine/coarse mix, wet
		Seep @ 6' & down
		As bedrock observed

1. The first part of the document is a list of names and addresses, which appears to be a directory or a list of subscribers. The names are written in a cursive script, and the addresses are listed below them.

## SOIL INVESTIGATION LOG

\* LANDOWNER Ron Nardone  
LEGAL DESC.  
HOLE NO. 2  
SURFACE ELEVATION 99.34  
LOGGED BY C. Overly

COUNTY Clark  
 OFFICE 313  
 STATION 2  
 DATE 8/30/11

DEPTH - FT	USCS	DESCRIPTION OF MATERIALS
0-7"	ML	topsoil, silt loam, dry
7"-29"	ML	silt cap, silt loam, dry
29"-38"	SM	orange sand w/ fines, wet, medium
38"-12'	SP	gravel, orange sand, wet
Seeps @ 5' and down		
No bedrock observed		

1. The first part of the document discusses the importance of maintaining accurate records of all transactions and activities related to the project. It emphasizes the need for transparency and accountability in financial management.

2. The second part outlines the specific procedures for recording income and expenses, including the use of standardized forms and regular audits to ensure compliance with applicable laws and regulations.

3. The third part addresses the role of the board of directors in overseeing the financial health of the organization and ensuring that resources are allocated effectively to achieve the mission.

4. Finally, the document concludes by highlighting the long-term benefits of sound financial practices, such as improved operational efficiency and increased donor confidence.

## SOIL INVESTIGATION LOG

LANDOWNER Ron Nerdman  
LEGAL DESC. \_\_\_\_\_  
HOLE NO. B  
SURFACE ELEVATION 98.63  
LOGGED BY C. Overeide

COUNTY Clark  
 DISTRICT 25  
 SECTION 2  
 PAGE 8/30/11

DEPTH -FT	USCS	DESCRIPTION OF MATERIALS
0-7'	ML	topsoil, silt loam
7"-30"	ML	silt cap, silt cap w/ loam
30"-6'	GP	gravel, outwash, wet
6'-12'	SC	red till, massive, wet
12'-15'	ML	grey/blue silt, wet
		Seep @ 5'
		No bedrock observed

[illegible]

1991

44-38861-1000

11 12 13

Nerdium 64 of 65



## SOIL INVESTIGATION LOG

LANDOWNER Ron Newnam COUNTY Clark  
LEGAL DESC. \_\_\_\_\_ PRACTICE 313  
HOLE NO. 4 SECTION 8  
SURFACE ELEVATION 96.52 DATE 8/30/11  
LOGGED BY C. Oring

DEPTH -FT	USCS	DESCRIPTION OF MATERIALS
0-11"	ML	Topsoil, silt loam
11"-32"	ML	silt cap, silt loam
32"-6'	GP	gravel, orange sand mix, wet
6'-6'2"	ML	blue silt, muffles, wet
		Soaps @ 6' and down.
		No bedrock observed

*[The following section contains several pages of extremely faint, illegible text, likely bleed-through from the reverse side of the document.]*